

BLUE PRINT CONSTRUCTS

Proposal package — B1710 Office Refurbishment (Solicitation FA667526Q0002)

Solicitation: FA667526Q0002

Full proposal

PREPARED BY

Blue Print Constructs

RK Residential Homes and Commercial Constructions, LLC

UEI LM4YHVQ71QG7 · CAGE 9LET0 · Submission date _____

Ravikiran (Rocky) Nudurupati

Founder & Managing Director / Owner (100%)

rocky@blueprintconstructs.com · (469) 213-1838

Document prepared 2026-05-27 · bid-slug: b1710-office-refurb-FA667526Q0002

Table of Contents

00	Proposal package — B1710 Office Refurbishment (Solicitation FA667526Q0002)
01	Price Proposal — FA667526Q0002 B1710 Office Refurbishment
02	Technical Acceptability — FA667526Q0002 B1710 Office Refurbishment
03	Past Performance — FA667526Q0002 B1710 Office Refurbishment

SECTION 00

00

Proposal package — B1710 Office Refurbishment (Solicitation FA667526Q0002)

Proposal package — B1710 Office Refurbishment (Solicitation FA667526Q0002)

This is the submission-side of the bid workspace. The bid-prep mechanics (overview, scope decomposition, takeoff, missing-docs list, risk register) live one directory up; this directory contains the documents that will be sent to the CO with the offer.

Submission shape

The CO will receive a **single email** to `lydia.carlton@us.af.mil` CC `todd.benner@us.af.mil`, subject:

Quote – FA667526Q0002 – Blue Print Constructs (UEI LM4YHVQ71QG7)

The email body is the cover letter (see `11-rfi-cover-letter.md` for the offer-cover template — repurposed from the RFI template).

Attachments, in order (each as a separate PDF for CO convenience, named with consistent prefix):

#	Filename (target)	Source markdown	Notes
1	01_SF1449_FA667526Q0002	04-SF-1449-fill-guide	Signed SF 1449 page 1 — Blocks 12, 17, 23, 24, 30 filled
2	02_PriceProposal_BluePrint	01-price-proposal.md	Lump-sum number + line-item backup
3	03_TechnicalAcceptability	02-technical-acceptability	Equipment/material/labor list + 90-day schedule + QC + safety
4	04_PastPerformance_BluePrint	03-past-performance.md	3-pack: Hindu Temple + Holiday Inn + Lavon RV Park
5	05_RepsAndCerts_SAM-screen	05-reps-and-certs-pul	SAM.gov entity-status screenshot + reps & certs date

6	06_PaymentBondCommitment.pdf	(from bonding agent)	Per FAR 52.228-13 — see 06-bondability-letter-template.
7	07_COI_ACORD25.pdf	(from insurance broker)	Current GL coverage; verify named-insured + limits
8	08_BuyAmericanCertification.pdf (optional)	(affirmation)	Affirmation per FAR 52.225-9; all materials US-made

Mapping to evaluation factors

Per 04-evaluation-strategy.md, the CO is most likely running **comparative evaluation per FAR 12.203(c)(2)**. The attachments map to evaluation dimensions:

- **Responsiveness / responsibility** — Attachments 1, 5, 6, 7 (SF 1449 signed, SAM active, payment-bond capacity, COI)
- **Price** — Attachment 2
- **Technical acceptability** — Attachment 3 (equipment / labor / schedule)
- **Past performance** — Attachment 4 (3-pack)
- **Compliance** — Attachment 8 (Buy American), implicit in 1 (Davis-Bacon flow-down)

Files in this directory

File	Purpose
<u>00-readme.md</u>	This file — submission shape + attachment list
<u>01-price-proposal.md</u>	Lump-sum + line-item backup
<u>02-technical-acceptability.md</u>	Trade-by-trade equipment + labor + schedule narrative
<u>03-past-performance.md</u>	3-pack of past projects + reference contacts
<u>04-SF-1449-fill-guide.md</u>	Block-by-block guide to filling the SF 1449 cover

<u>05-reps-and-certs-pull-guide.md</u>	How to pull SAM screenshot + verify reps & certs currency
<u>06-bondability-letter-template.md</u>	Template request to bonding agent for payment-bond commitment
<u>07-bid-bond-form-template.md</u>	N/A for this RFQ — kept for cross-workspace consistency
<u>08-dba-or-sca-compliance.md</u>	Davis-Bacon compliance posture (not SCA — this is construction)
<u>09-site-visit-attendance-memo.md</u>	Site-walk request + rationale documentation
<u>10-submission-checklist.md</u>	Fri AM final checklist before email send
<u>11-rfi-cover-letter.md</u>	RFI cover letter (Thu AM send) + offer cover letter (Fri send)

What this directory does NOT contain

- The actual signed SF 1449 PDF (created by filling the original PDF; not stored as markdown)
- The actual COI PDF (lives in `firm/` or OneDrive; referenced here)
- The payment-bond commitment letter (lives in `firm/` once delivered; referenced here)
- The SAM screenshot (one-off at submission time; not committed to git)

Rendered artifacts (full proposal PDF + pitch-deck PPTX) generated by python

`scripts/render_proposals.py --bid bids/b1710-office-refurb-FA667526Q0002 --tier all` land in `proposal/exports/` (gitignored).

SECTION 01

01

Price Proposal — FA667526Q0002 B1710 Office Refurbishment

Price Proposal — FA667526Q0002 B1710 Office Refurbishment

Offeror: RK Residential Homes and Commercial Constructions, LLC dba Blue Print Constructs — LM4YHVQ71QG7 — 9LET0 **Solicitation:** FA667526Q0002 **Date:** _____ **Pricing arrangement:** Firm Fixed Price, single Lot **Acceptance period offered:** 30 calendar days (minimum per FAR 52.212-1)

Lump-sum quoted

■■ [AWAITING PRICE BUILD] — fill at Gate 4 (Thu PM, per 01-bid-prep-checklist.md). The lump-sum number for SF 1449 Block 23/24 lands here. Target band per 09-price-references.md \$6 mid-point: **\$90,000 – \$105,000**.

Item 0001 description	Quantity	Unit	Unit Price	Amount
--------------------------	----------	------	------------	--------

Perform all work described in the attached Statement of Work for the B1710 Office Refurbish at NAS JRB Fort Worth — including carpet tile replacement (~3,500 SF), 6" rubber base, interior paint, sheetrock in-fill of Rm 1030 doorway, Rm 1008 furniture/material disposal and wall patch with access panel, furniture relocation and restoration, daily cleanup and disposal at certified landfill, and 1-year warranty of construction. Davis-Bacon TX20260270 wages applied.	1	Lot	\$(AWAITING PRICE BUILD]	\$(AWAITING PRICE BUILD]
---	---	-----	--------------------------	--------------------------

Total firm-fixed-price quoted (Lot): \$(AWAITING PRICE BUILD]

Backup detail — line-item build-up

The CO need not approve this build-up; it is informational, transmitted for transparency and to demonstrate technical understanding per the comparative-evaluation criteria implied by FAR 12.203(c)(2). The contractual price is the single Lot number above.

#	C	Line item	Quantity	Unit	Unit cost	Extended
1		02 Selective demo + furniture relocate 41 (3,500 SF flooring + 16 rooms) 15	1	—	LS	\$(AWAITING)
2		02 Furniture + material disposal — Rm 41 1008 19	1	—	LS	\$(AWAITING)
3		01 Construction-debris disposal (~10 CY, \$(AWAITING) 74 certified landfill) 15			C	\$(AWAITING)
4		09 Carpet tile — Shaw Constellat EW24 68 (Style 59326), Color 26110 Moonlight 13 Grade A, 24"×24", glue-down. Or accepted equal per SOW \$(B.	\$(AWAITING)		SF	\$(AWAITING)
5		03 Self-leveling underlayment — allowance 54 13			SI	\$(AWAITING)
6		09 Rubber cove base 6" gray (samples for 65 owner selection per SOW \$(B) 13	\$(AWAITING)		LF	\$(AWAITING)
7		05 Interior paint — walls, primer + 2 coa 91 SW 7029 Agreeable Gray eggshell 23	~1		SI	\$(AWAITING)
8		09 Drywall in-fill at Rm 1030 doorway — 21 metal stud framing + 5/8" GWB both 16 sides + tape/bed/texture + prime + 2 coats paint	1	—	EA	\$(AWAITING)
9		05 Wall patch — Rm 1008 (~16 SF GWB + 25 finish to match) 00	1	—	E	\$(AWAITING)

10	08 Access panel — 12"×12" valve-rated, 31 Karp DSB-214M or equal — Rm 1008 13	1	—EA		\$[AWAITING]
11	01 Furniture move + restore (16 rooms, 76 2-person crew × ~3-4 working days) 00	1	—LS		\$[AWAITING]
12	01 General conditions (PM, supervision, 00 certified-payroll admin, daily cleanup, 00 dumpsters, base-access coord, mobilization×2, punch-list, 1-yr warranty)	1	—LS		\$[AWAITING]
	Direct cost subtotal				\$[AWAITING]
13	— Overhead (10%)				\$[AWAITING]
14	— Profit (10%)				\$[AWAITING]
15	— Quantity contingency (5% on direct, justified by no-site-walk per 07-risk-register.md R2)				\$[AWAITING]
	TOTAL LUMP-SUM (Item 0001)				\$[AWAITING]

Pricing notes for the CO

1. **Davis-Bacon compliance.** All labor priced at TX20260270 (Tarrant County, Building Construction, Mod 0, 02 Jan 2026) rates per FAR 52.222-6. Certified-payroll administration (WH-347 weekly) is included in the general conditions line.
2. **Buy American.** All construction materials in scope are domestic-manufactured per FAR 52.225-9: Shaw carpet tile (Dalton, GA), Sherwin-Williams paint (Cleveland, OH), Roppe/Johnsonite/Burke Mercer rubber base (US-Ohio plants), USG/National Gypsum drywall (multi-state US), Karp Associates access panel (Maspeth, NY). No Buy American determination required.
3. **Carpet equivalency.** Quoted at SOW spec (Shaw Constellat EW24 Style 59326, Color 26110 Moonlight Grade A). Dye-lot H6958 confirmation will be made at submittal time per AF IMT 3000 process; if H6958 is not in current production, the closest in-production lot will be submitted for owner approval per SOW §B.
4. **Paint scope.** Pricing assumes walls only in the C/B/P-marked areas + hallway per floor plan annotation "paint all hallway". Ceiling paint, baseboards, doors, and trim are NOT included

unless the CO clarifies otherwise (see RFI). Price-add available on request.

5. **Site visit.** No site walk was offered before submission; pricing reflects SOW-stated quantities with 5% contingency for field-verify-after-award. Differing Site Conditions claims will be made per FAR 52.236-2 if material variance is found.
6. **Acceptance period.** 30 calendar days from offer due date (consistent with FAR 52.212-1 default).
7. **Validity of payment-bond capacity.** Surety commitment letter attached as Attachment 06 confirms capacity for the FAR 52.228-13 payment bond (100% of contract price, post-award, within 10 days).

Signature

The lump-sum offer is binding on the offeror per SF 1449 Block 30 signature. The lump-sum value above is the entire consideration for the work described in the Statement of Work and incorporated documents.

Offeror name: RK Residential Homes and Commercial Constructions, LLC dba Blue Print Constructs

Authorized signer: _____ Signature: _____ Date: _____

SECTION 02

02

Technical Acceptability — FA667526Q0002 B1710 Office Refurbishment

Technical Acceptability — FA667526Q0002 B1710 Office Refurbishment

Offeror: RK Residential Homes and Commercial Constructions, LLC dba Blue Print Constructs

Solicitation: FA667526Q0002 **Submission date:** _____

This document supports the comparative evaluation regime implied by FAR 52.212-1 Deviation 2026-00038 + the absence of an explicit FAR 52.212-2 Evaluation clause in Section M. Per 04-evaluation-strategy.md, the CO will weigh: (a) understanding of the work (this document's equipment/material/labor list), (b) realism of the schedule (90-day Gantt below), (c) past performance (separate document — 03-past-performance.md), (d) price (01-price-proposal.md).

1. Understanding of the work

The B1710 Office Refurbishment is a **single-building, occupied-condition interior finishes renovation** at Building 1710, NAS JRB Fort Worth, covering approximately 3,500 SF of office and common-area space. The work is a coordinated 4-trade scope: demolition, drywall (limited), carpet tile + base, and paint. There is one specialty item (access panel for valve in Rm 1008) and a minor structural infill (sheetrock-in of Rm 1030 doorway).

We have read the SOW in full and the floor plan; our scope decomposition is in

`../02-scope-of-work.md`.

1.1 Critical-path activities

In order of duration: 1. **Paint** (Item C in SOW) — longest single-trade duration; requires phased room-by-room access. ~12 working days for ~13,500 SF wall area with a 2-painter crew, 2 coats over primer. 2. **Carpet tile + base install** (Item B) — second-longest; ~10-12 working days for 3,500 SF tile + 1,300 LF base with a 2-person crew. Must follow paint completion in each room to avoid overspray onto new flooring. 3. **Demolition + furniture relocate** (Item A) — must lead all other trades in each room; ~5-7 working days for 16 rooms. 4. **Drywall in-fill at Rm 1030 + Rm 1008 patch + access panel** (Items D/F) — short duration (~3 working days) but must precede paint in those two rooms. 5. **Disposal** (Item E + general) — continuous through PoP; 10 CY roll-off staged on-base per coordinated delivery with `steven.munnell@us.af.mil`.

1.2 Sequence — by-room batching

We will divide the 16 C/B/P rooms into **4 batches of 4 rooms each** to minimize disruption to AFRC operations per SOW §3.1.2:

- **Batch 1** (week 1-2): Rooms 1002, 1006, 1008, 1009 — includes Rm 1008 wall patch + access panel
- **Batch 2** (week 3-4): Rooms 1013, 1020, 1022, 1023
- **Batch 3** (week 5-6): Rooms 1025, 1026, 1028, 1029

- **Batch 4** (week 7-8): Room 1030 (includes doorway sheetrock-in) + hallway + remaining + punch-list

This sequence allows the AFRC tenant to vacate rooms in rolling fashion (4 at a time), preserving operational continuity. Floats in weeks 9-12 absorb any furniture-coordination slip and the final close-out.

1.3 Working hours + base access

Per SOW §SCHEDULE: 0700–1600 M-F. Material deliveries via the commercial vehicle gate (Alta Mere Drive × Ridgmar Meadows Road) 0600-1400 M-F. Base-access vetting for prime + sub personnel coordinated with steven.munnell@us.af.mil post-NTP; lead time 3-5 business days from passname submission. Same procedure as on the Cmd Post + NDI project (separate workspace; same base).

2. Equipment, materials, and labor

Per the comparative-evaluation criteria, this section lists every material, every equipment line, and every labor classification touched by the scope. This is the "RSMeans-style output" type of artifact AF Reserve COs typically expect on a technical-acceptability evaluation.

2.1 Materials list

#	Material	Spec	Source / Manufacturer	Qty estimate	Davis-Bacon labor class
1	Carpet tile, 24"×24", 100% Nylon	Shaw Constellat EW24 Style 59326, Color 26110 Moonlight Grade A	Shaw Industries — Dalton, GA (US-made; Buy American compliant)	3,500 SF + 5% waste	Floor Layer
2	Carpet adhesive	Shaw-spec release adhesive (Lok-Dots or equal)	Shaw or local distributor	~50 gal	Floor Layer

3	Self-leveling underlayment	Cementitious, 1/8" avg depth	Mapei, ARDEX, or equal — US-made	~500 SF	Floor Layer
4	Rubber cove base, 6" tall	Commercial grade, gray (color from samples per SOW)	Roppe (Fostoria OH), Johnsonite (Chagrin Falls OH), or Burke Mercer (US-made)	~1,300 LF	Floor Layer
5	Cove-base cement	Standard cove-base adhesive	Roppe, Johnsonite, or equal	~6 gal	Floor Layer
6	Interior latex paint, primer	Sherwin-Williams PrepRite ProBlock or equal	Sherwin-Williams — Cleveland OH (US-made)	~30 gal	Painter
7	Interior latex paint, finish, eggshell	SW ProMar 200 (or equivalent), Color SW 7029 Agreeable Gray	Sherwin-Williams — Cleveland OH	~110 gal (2 coats × ~13,500 SF)	Painter
8	5/8" Type X GWB	Standard commercial gypsum board	USG, National Gypsum, or CertainTeed (US-made)	~60 SF	Drywaller
9	Metal stud, 3-5/8" or 6", 25-gauge	Per Rm 1030 doorway in-fill framing	ClarkDietrich or equal — US-made	~7 LF + plates	Carpenter

10	Joint compound, tape, primer-sealer	Standard GWB finish set	USG, Sheetrock, or equal	Allowance	Drywaller + Painter
11	Access panel, 12"×12", steel-frame plaster-bead, valve-rated	Karp Associates DSB-214M or Acudor equal — US-made	Karp — Maspeth NY	1 EA	Carpenter
12	Caulks + sealants	Acoustic caulk + paintable latex caulk	Standard commercial	Allowance	Painter + Drywaller

All listed materials are domestic-manufactured (Buy American Act compliant per FAR 52.225-9). No foreign-source materials proposed; no Buy American determination required.

2.2 Equipment + tooling list

Item	Use	Davis-Bacon class
24-ft pickup truck or box truck	Material delivery + tool transport (escorted to commercial gate per Section G)	Driver / Laborer
Floor-roller (75 lb), seam-roller, knee-kicker, tile cutter	Carpet tile install	Floor Layer
Cove-base hand-roller, miter cutter, scribe tools	Cove base install	Floor Layer
Sprayer (HVLP for cut-in, pump for roll-out), rollers, brushes, drop cloths, plastic sheeting, masking tape	Paint application	Painter
Track saw, screw gun, drywall cutters, joint-compound tools	Drywall in-fill at Rm 1030	Drywaller + Carpenter

Drill, hole-saw, level, screw gun	Access panel install	Carpenter
Hand tools (utility knife, tape measure, pry bar, demolition tools)	Demolition + general	All trades
Wet-vac, brooms, dust pans, mops	Daily cleanup per SOW	Laborer
Roll-off dumpster (~10 CY)	Construction debris per SOW \$A	(Disposal vendor)
Portable Government toilet (none — using Government toilets per SOW)	N/A	—
First-aid kit + fire extinguisher	OSHA 29 CFR 1926 site safety	Safety

2.3 Labor list — by trade

Trade	Davis-Bacon classification (TX20260270)	Loaded rate (estimate; verify against WD PDF)	Work hours estimate
Floor Layer (carpet + base)	Floor Layer / Resilient Floor Layer	\$26 – \$34 / hr	~140 hr (2 workers × 8-10 days)
Painter	Painter	\$26 – \$34 / hr	~160 hr (2 workers × 10-12 days)
Drywall / Taper	Drywall Hanger + Taper	\$30 – \$38 / hr	~24 hr
Carpenter	Carpenter	\$32 – \$40 / hr	~24 hr
Laborer Group 1	Laborer Group 1	\$20 – \$26 / hr	~96 hr (demo + furniture move + cleanup)

Project Manager / Superintendent	Not DBA-rated; firm overhead	(firm rate)	~60 hr over 90-day PoP
Safety Officer (collateral to PM)	Not DBA-rated; firm overhead	(firm rate)	(collateral)
QC (collateral to PM)	Not DBA-rated; firm overhead	(firm rate)	(collateral)

Total estimated trade labor: **~444 hours** across 90-day PoP. Compresses to ~3 working weeks of intense activity, framed by mobilization and close-out. Field-verify and refine after Gate 2 takeoff.

3. Schedule — 90 calendar days from NTP

Week	Cal days from NTP	Activity	Owner
1	1–7	Mobilization: base-access submission for personnel; commercial vehicle gate procedure; receive site survey + verify quantities; submittals to CO via AF IMT 3000 (carpet, base, paint, panel)	PM
2	8–14	Submittal approval period (assume 5-7 cal days CO turnaround); order materials with lead-time confirmed; Batch 1 demo + furniture relocate (Rooms 1002, 1006, 1008, 1009)	PM + Laborer

3	15–21	Batch 1: Rm 1008 wall patch + access panel install; Batch 1 paint walls (primer + 1st coat)	Carpenter + Drywaller + Painter
4	22–28	Batch 1: paint 2nd coat; carpet + base install; Batch 2 demo + furniture relocate	Painter + Floor Layer + Laborer
5	29–35	Batch 1 punch-list + restore furniture; Batch 2 paint (primer + 1st coat)	All trades
6	36–42	Batch 2: paint 2nd coat; carpet + base; Batch 3 demo + furniture relocate	Painter + Floor Layer + Laborer
7	43–49	Batch 2 punch-list + restore furniture; Batch 3 paint (primer + 1st coat)	All trades
8	50–56	Batch 3: paint 2nd coat; carpet + base; Batch 4 demo (incl. Rm 1030 doorway opening + sheetrock-in)	Painter + Floor Layer + Carpenter + Drywaller
9	57–63	Batch 3 punch-list + restore furniture; Batch 4 paint (Rm 1030 + hallway)	All trades
10	64–70	Batch 4 paint 2nd coat; carpet + base in Batch 4 + hallway; final furniture restore	Painter + Floor Layer + Laborer

11	71–77	Final punch-list walk; touch-ups; cleanup; close-out documentation prep	All trades
12	78–84	Pre-final inspection + corrections; warranty letter delivery; final cleanup	PM
13	85–90	Final inspection by CO/COR; substantial completion; close-out	PM + CO

3.1 Float

Approximately **15-20 calendar days of float** across the schedule, primarily absorbed in weeks 11-13. Critical-path drivers: paint cure time between coats (24 hr per SW spec), carpet tile cure after install (24 hr light traffic, 72 hr heavy), and the 4-room-batch sequencing that prevents over-occupying the AFRC office spaces.

3.2 Holidays + observed days

- Juneteenth — Fri 2026-06-19 (no work; falls in week 1-2 depending on actual NTP date)
- Independence Day observed — Fri 2026-07-03 (likely week 4-5)
- Labor Day — Mon 2026-09-07 (week 11-12 boundary)

3.3 Working hours

Per SOW §SCHEDULE: 0700-1600 M-F. No weekend or after-hours work without written CO approval. Material deliveries via commercial gate 0600-1400 M-F.

4. Quality control plan

We will execute the project under our firm's standard QC plan, summarized:

- **Daily** — Site supervision; punch-walk each completed room before move-on to next batch
- **Per-trade hold-points** — Demolition completion / drywall completion / paint 1st coat dry / paint 2nd coat dry / carpet install acceptance / base install acceptance — internal QC signature each
- **Submittals** — AF IMT 3000 forms for each material before procurement (carpet, base, paint, drywall, access panel)

- **Substantial completion walk-through** — Pre-final and final inspections per SOW with the CO/COR
- **Warranty** — 1-year warranty of construction per FAR 52.246-21 + Letter of Guarantee delivered at substantial completion per SOW §PART III

5. Safety plan

- **OSHA 29 CFR 1910 + 1926 compliance** — all trade work
- **DAFMAN 91-203** — Air Force OSH standards per SOW §PART I
- **Daily site-safety check** — by the on-site PM/super (Rocky)
- **Fall protection** — N/A in this single-story interior renovation; ladders + scaffolds rated for use
- **No-Notice Inspections** — Contractor cooperates with DOL inspectors or installation Safety per SOW §OCCUPATIONAL SAFETY
- **Dust + debris control** — Daily cleanup; covered dumpsters; no spread to airfield
- **Government-furnished restroom** — Used per SOW; paint cleanup explicitly NOT in facility restrooms or janitor closet
- **Personnel identification** — Hard-hat company markings; AF-approved ID for each employee
- **PII handling** — No SSNs in offer email; base-access vetting forms collected post-NTP through 301 LRS sponsor

6. Personnel

For this 90-day, \$90-105K-target project at AFRC small-scale, the firm's owner-operator pattern applies:

Role	Name	Bio source
Project Manager / Superintendent / Safety Officer / Quality Control	Ravikiran (Rocky) Nudurupati , Founder & Managing Director, Blue Print Constructs	Per firm/firm-profile.json → key_personnel[0]. PMP, CSM, SAFe; 22 years professional + 4 years construction-firm leadership.
Trade crew	Mixed self-perform + sub crew, depending on Gate 4 sub-quote decisions	See 02-scope-of-work.md §8

Bonding agent	_____	Per firm/firm-profile.json → bonding (data to surface)
---------------	-------	--

This staffing arrangement is consistent with BPC's prior delivery model on similar-scale projects (Hindu Temple of Southlake, Holiday Inn Hall Park).

7. Affirmations

- All proposed materials are **domestic-manufactured** per FAR 52.225-9 (Buy American). No Buy American determination requested.
- Davis-Bacon TX20260270 wages will be paid; certified payroll (WH-347) submitted weekly per FAR 52.222-6, 52.222-8, 52.222-10.
- Blue Print Constructs is a **Small Business** under NAICS 236220 (\$45M size standard) per its current SAM.gov registration.
- Blue Print Constructs has the **bonding capacity** to provide the FAR 52.228-13 payment bond at 100% of contract price within 10 days of award. Commitment letter attached.
- Blue Print Constructs has **current Commercial General Liability** coverage; ACORD 25 attached.
- The offeror is not subject to any **debarment, suspension, or proposed-for-debarment** action; not listed on SAM Exclusions.

SECTION 03

03

Past Performance — FA667526Q0002 B1710 Office Refurbishment

Past Performance — FA667526Q0002 B1710 Office Refurbishment

Offeror: RK Residential Homes and Commercial Constructions, LLC dba Blue Print Constructs
Solicitation: FA667526Q0002

***Past-performance picks for this bid** (from `firm/firm-profile.json` → `past_project_selection_rules`): Most-relevant analog set for this 100% Small-Business AFRC interior-finishes RFQ at NAS JRB Fort Worth: 1. **Hindu Temple of Southlake** — institutional finishes (10,700 SF Assembly A-3 renovation: demo, finishes, toilet partitions, partition framework). Most-comparable to B1710 in scope shape (multi-room interior finishes), in delivery context (occupied institutional building), and in trade mix (drywall, paint, flooring). 2. **Holiday Inn (Hall Park, Frisco)** — commercial hospitality renovation; closest analog to AFRC office-occupied work where guests/personnel are in adjacent rooms. 3. **Lavon RV Park** — federal-style coordination + scope discipline + \$1M performance-bond procurement. Demonstrates BPC's capability to deliver under formal contract terms equivalent to federal procurement standards.*

Per the comparative-evaluation regime (see `../04-evaluation-strategy.md`), the CO will likely use CPARS, SPRS, and direct contact with these references. Each reference below provides: project shape, scope, contract value, delivery method, role, completion status, and the owner-side reference contact.

Reference 1 — Hindu Temple of Southlake (institutional interior renovation)

Field	Value
Project name	Hindu Temple of Southlake — Place of Religious Worship renovation
Owner	North Texas Hindu Heritage Society
Owner address	595 South Kimball Avenue, Southlake, TX 76092
Owner-side project #	2024-024
Project size	≈10,700 SF Assembly A-3 (Place of Religious Worship) renovation
Contract value	_____

Delivery method	Negotiated lump-sum (owner direct)
Role	General Contractor
Start	Drawings dated 2025-06-20 (PDF), updated 2025-09-12 (Arch + Structural)
Status	In execution per material quote 2025-10-30
Reference contact	_____
Source folder	Hindu Temple of South Lake/ on OneDrive

Relevance to B1710 (CO-facing narrative):

- **Multi-room interior finishes scope** — demolition, drywall (limited), toilet partitions, partition framework, finishes — parallels the multi-room (16-room) interior finishes scope at B1710.
- **Institutional / nonprofit owner** — comparable formality of contract administration and owner-coordination requirements.
- **Trade mix** — drywall, painting, flooring, specialty (partition) — all present in both projects.
- **Active execution as of 2025-10-30** — proves BPC's mid-execution capacity for an institutional client.

Reference 2 — Holiday Inn (Hall Park, Frisco) (commercial hospitality renovation)

Field	Value
Project name	Holiday Inn (Hall Park) — hospitality renovation
Owner	Holiday Inn franchisee at Hall Park, Frisco, TX
Owner address	Hall Park, Frisco, TX
Contract value	_____
Delivery method	_____

Role	General Contractor
Completion	_____
Reference contact	_____
Scope summary	Commercial renovation projects for hospitality client per Rocky Nudurupati's professional profile

Relevance to B1710 (CO-facing narrative):

- **Occupied-building renovation** — hospitality renovations are inherently occupied-condition; rooms are vacated in rolling batches while adjacent rooms remain in operation. **Direct analog** to B1710 SOW §3.1.2 *"minimize interruption of the normal duty day of Government activity"*.
- **Commercial finishes scope** — hospitality renovations are dominantly carpet + paint + drywall work, same trade mix as B1710.
- **Repeat client / preferred-vendor relationship** — Rocky's profile lists Holiday Inn (Hall Park) as a featured client, indicating sustained quality and on-time delivery.

Reference 3 — Lavon RV Park (federal-style coordination + bonding)

Field	Value
Project name	Lavon RV Park — 30-lot RV park new construction
Owner	Lavon Leisure 78 RV Park LLC
Owner address	614 Forest Hill Dr, Murphy, TX 75094
Site address	County Road 597, Farmersville, TX 75442
Contract value	\$1,050,000
Contract type	Standard AIA A101-2020 fixed-price; AIA A201-2020 general conditions

Delivery method	Design-Bid-Build (fixed lump-sum)
Role	General Contractor
Start date	2025-07-30
Substantial completion	2026-04-30 (per contract; status to confirm before citing as 'complete')
Bond	\$1,000,000 performance bond per contract Article 8
Reference contact	_____
Source folder	Lavon RV Park/ on OneDrive

Relevance to B1710 (CO-facing narrative):

- **Bonding capacity demonstrated** — BPC successfully procured a \$1,000,000 performance bond on this project, establishing firm-level bonding capacity well above the B1710 payment-bond requirement (~\$100K max under FAR 52.228-13).
- **Formal contract administration** — AIA A101-2020 + A201-2020 mirrors the contract-administration formality of federal FAR-flowdown procurement. Demonstrates BPC's capability to operate under formal contract terms equivalent to federal procurement standards.
- **Multi-trade GC coordination** — site work, MEP, utilities, fencing, retaining walls, building construction — proves BPC's GC depth across many trades, including the carpentry / framing / drywall trades present at B1710.
- **Fixed-lump-sum execution discipline** — both projects are firm-fixed-price, requiring tight cost control and accurate takeoffs.

At-a-glance summary table

#	Project	Owner	Value	Status	Trade-mix overlap with B1710

1	Hindu Temple of Southlake	North Texas Hindu Heritage Society	—	In execution (2025-2026)	Demo + drywall + finishes + paint — direct analog
2	Holiday Inn (Hall Park, Frisco)	Holiday Inn franchisee	—	—	Carpet + paint + drywall + occupied-building — direct analog
3	Lavon RV Park	Lavon Leisure 78 RV Park LLC	\$1,050,000	In execution (start 2025-07-30)	GC coordination + bonding capability + DBA-equivalent formal contract — federal-style discipline analog

CPARS / SPRS background

Blue Print Constructs is a new federal contractor; **no CPARS history yet** on prior federal awards. The references above are commercial / institutional / nonprofit — equivalent past performance in scope and shape, even if not specifically federal-CPARS-rated.

Per FAR 15.305(a)(2)(iv) and SAP comparative-evaluation practice, the CO may treat the **lack of negative CPARS findings as neutral** (rather than a strike against the offeror), and may give weight to non-federal past performance that is otherwise analogous in scope, magnitude, and complexity. The three references above are submitted on that basis.

If the CO requests **additional references** beyond the three above, BPC can provide on request from: - Volli (pickleball) — interior + exterior painting commercial reference - 250+ single-family-home portfolio — cumulative volume reference via GC partner contacts (That 1 Painter, Touchmark, Bridge View Build, Hill Design Build) - Commercial strip mall — drywall + tape/bed/texture reference

Owner authorization to contact references

By submission of this offer, the offeror authorizes the Contracting Officer to contact any of the listed reference contacts directly for verification of past performance. The offeror's preferred mode of contact verification is by email to the listed owner-side POC in the first instance; phone follow-up at the POC's discretion.