



Adam's Trade & Services, Inc.

7600 Chevy Chase Drive Bldg. 2 Suite 300 Austin, TX 78752

737-376-0759 | atsinc.tx@gmail.com

Camp Maxey Roof Replacement **Project Information**

Project Owner:

Texas Military Department (TMD)

Prime Contractor:

Adam's Trade & Services, Inc.

Submit Quote/Price Proposal to the following Email:

patrickgrabowski.ats@gmail.com

Send Questions by Email, if any, By:

Tuesday, June 9, 2026

Send Quote By:

Friday, June 26, 2026

Project Location:

6351 US 271 N Powderly, TX 75473 Bldg. 1

Site Visit:

Monday June 1, 2026 at 8:00 am CST OR 1:00 pm CST

Contact **Patrick Grabowski** regarding attendance

- This Project is Sales Tax Exempt -

***Note:** Use Pricing Schedule on the following page



Adam's Trade & Services, Inc.

7600 Chevy Chase Drive Bldg. 2 Suite 300 Austin, TX 78752

737-376-0759 | atsinc.tx@gmail.com

Camp Maxey Roof Replacement **Project Information**

Use **Pricing Schedule** Below

Description	Amount (\$)
1. General Conditions & Mobilization	\$ _____
2. Demolition & Removal (all Roof Areas)	\$ _____
3. Lower Roof Replacement	\$ _____
4. Upper Roof Replacement	\$ _____
5. Cleanup	\$ _____
Total Base Bid (Not to Exceed)	\$ _____

***Note:** Scope of Work and more information on the following pages



Camp Maxey Roof Replacement

Project Information

1. Scope of Work:

- 1.1. Goal:** Replace the Camp Maxey Building 1 roof
- 1.2.** Providing the materials, equipment, and incidentals required to make the project completely and fully operable.
- 1.3.** Provide the labor, equipment, tools, and consumable supplies required for a complete project.
- 1.4.** Provide special tools, spare parts, lubricants, supplies, or other materials as indicated in contract documents for the operation and maintenance of the project.
- 1.5. THIS PROJECT SHALL COMPLY WITH THE "BUY AMERICAN ACT."** The contractor covenants and agrees that he/she will not expend any funds appropriated by Congress without complying with the Buy American Act (41 U.S.C. 10). Reference Project Plans and Supplemental General Conditions for additional information.

1.6. Lower Roof Section:

- 1.6.1.** Remove all loose gravel & dispose off site
- 1.6.2.** Remove all drip edge, gutter, downspouts & counter flashing metal
- 1.6.3.** Install 1/2" High Density ISO cover board, mechanically fastened through the Lightweight & into the metal deck, per wind uplift calculations
- 1.6.4.** Install 60 Mil TPO membrane over the HD ISO, fully adhered
- 1.6.5.** Install 60 Mil TPO flashing on all walls & curbs, fully adhered
- 1.6.6.** Install new pipe penetrations & TPO wrap on all vent stacks
- 1.6.7.** Install new 1/2" plywood around the perimeter to match the new 1/2" HD cover board thickness
- 1.6.8.** Install new 24 ga, TPO coated metal drip edge around perimeter
- 1.6.9.** Install new 24 ga, pre-finished metal counterflashing, gutter & downspouts

1.7. Upper Roof Section:

- 1.7.1.** Remove all loose gravel & dispose offsite
- 1.7.2.** Remove all drip edge, gutter, downspouts & counter flashing metal
- 1.7.3.** Install 1/2" High Density ISO cover board, Fully Adhere with Low Rise Foam per wind uplift calculations
- 1.7.4.** Install 60 Mil TPO membrane over the HD ISO, fully adhered
- 1.7.5.** Install 60 Mil TPO flashing on all walls & curbs, fully adhered
- 1.7.6.** Install new pipe penetrations & TPO wrap on all vent stacks



Camp Maxey Roof Replacement

Project Information

- 1.7.7. Install new 1/2" plywood around the perimeter to match the new 1/2" HD cover board thickness
- 1.7.8. Install new 24 ga, TPO coated metal drip edge around perimeter
- 1.7.9. Install new 24 ga, pre-finished metal counterflashing, gutter & downspouts

2. Additional Subcontractor Responsibilities:

- 2.1. Subcontractor is responsible to become familiar with the project site, including but not limited to: condition of project site and field measurements
- 2.2. Subcontractor to verify all measurements
- 2.3. Take all proper measurement(s) during pre-construction meeting prior to ordering material(s)
- 2.4. Additional material(s) fee: The Subcontractor is held liable for payment of any additional materials required if there is not enough materials
- 2.5. Any mistakes and, or damage caused by Subcontractor and their Employees

3. Attachment(s):

- A. 'Photos, Camp Maxey Roof Replacement.pdf'

4. Milestones and Deliverables:

- 4.1. Subcontractor shall submit for the approval of Adam's Trade & Services, Inc. all product data sheets referenced below prior to starting work:
 - A. Materials

5. Project Specifications and Requirements:

- 5.1. Background Check: Subcontractor and their Employees working on Project Site must submit to Background check, conducted by the Owner
- 5.2. Wage Rates: Do not pay less than the wage scale of various classes of labor as set forth in 29 USC Section 206. Published wage rates for the State of Texas and county of the project can be located at <https://beta.sam.gov/> (Davis-Bacon Act) pursuant to Chapter 2258, Texas Government Code
- 5.3. All work will be done during regular business hours, Monday through Friday from 8:00am - 5:00pm. No work to be done on State and, or Federal holidays. No work to be done on weekends, Saturday / Sunday. If work to be done outside Monday through Friday from 6:30am - 5:00pm, Subcontractor to provide a minimum 24 hour notification to the Prime contractor for review and needs to be approved.
- 5.4. Work area to be cleaned at the end of every work day
- 5.5. All garbage and old materials to be hauled off site / placed in dumpster by Subcontractor
- 5.6. Project to be conducted in accordance to Local, State, & Federal laws, regulations, & standards
- 5.7. Project to be conducted in accordance to all rules and regulations set forth by Owner at Location
 - Such as but not limited to:



Camp Maxey Roof Replacement

Project Information

- a) Do not permit alcoholic beverages or illegal substances on the site. Do not allow personnel under the influence of alcoholic beverages or illegal substances to enter or remain on the site at any time. Persons on site under the influence of alcoholic beverages or illegal substances will be permanently prohibited from returning to the site. Criminal or civil penalties may also apply.
- b) No smoking or use of any tobacco products is allowed within building footprint. Designate a smoking site safely away from any combustible materials and a minimum of 100 feet from a doorway.
- c) Do not allow firearms or weapons of any sort to be brought onto the site under any conditions.
- d) Manage site to allow access to site and control construction operations.
- e) Employ competent workmen, skilled in the occupation for which they are employed. Provide work meeting quality requirements of the contract documents as determined by the engineer and owner.
- f) Assume responsibility for safety at the site. Protect the safety and welfare of personnel at the site.
- g) Provide safe access to move through the site. Provide and maintain barricades, guard rails, covered walkways, and other protective devices to warn and protect from hazards at the Site.
- h)

6. Workmanship Warranty. Standard one (1) year from the goods acceptance date by the "Owner"

7. Manufacturer Warranty. Materials warranty will be provided in accordance to all manufacturer warranties

8. Project Term: All work shall be completed within one (1) year

9. Project Laws and Codes:

- A. All work to be done in accordance to all Local, State, and Federal laws and regulations
- B. All work to be done in accordance to all OSHA laws and standards
- C. All work to be done up to code

10. Prior to Starting Project:

10.1. List of Names of everyone that will be on Project Site, including but not limited to:

- A. Employees / Associates
- B. Delivery Personnel

10.2. Pre Construction meeting shall be conducted

10.3. All Milestones and Deliverables shall be approved by Adam's Trade & Services, Inc.

10.4. Subcontractor will provide the following documents to Adam's Trade & Services, Inc.



Adam's Trade & Services, Inc.

7600 Chevy Chase Drive Bldg. 2 Suite 300 Austin, TX 78752

737-376-0759 | atsinc.tx@gmail.com

Camp Maxey Roof Replacement

Project Information

(Unless this was previously provided)

- A. W-9
- B. COI – Liability and Workers Compensation
- C. Insurance (as stated in Section 12)

11. During Project:

11.1. Inspections during Project with Adam's Trade & Services, Inc.

11.2. Substantial Completion and Final Walkthrough with Adam's Trade & Services, Inc. and Owner

11.3. Proper dress code, but not limited to, in accordance to OSHA laws, regulations, & standards

12. Insurance Requirements:

Certificate Holder:

Adam's Trade & Services, Inc.

7600 Chevy Chase Drive Bldg 2 Suite 300 Austin, TX 78752

Tel 737-376-0759 | Email atsinc.tx@gmail.com

Insurance:

Subcontractor must, at all times during the term of the project and any renewals or extensions, maintain and provide a Certificate of Insurance naming Adam's Trade & Services, Inc. certificate holder for required insurance.

Certificates may not be modified or canceled until at least thirty (30) days' notice has been provided to the State.

Subcontractor shall provide:

(A) General Commercial Liability insurance in amount of \$1,000,000 per occurrence (Combined Single Limit Bodily Injury and Property Damage) and \$2,000,000 Annual Aggregate;

(B) Auto Liability, including Hired Auto and Non-Owned Auto (Combined Single Limit Bodily Injury and Property Damage), in amount of \$1,000,000 per occurrence; and

(C) Worker's Compensation Insurance in the amount required by law. Insurance shall not limit Subcontractor obligation to indemnify, defend, or settle any claims.

(D) Adam's Trade & Services, Inc. as additional insured

If you have any questions or concerns about this project information, please contact Patrick Grabowski at patrickgrabowski.ats@gmail.com. We look forward to hearing from you.

PHOTOS:



