

BLUE PRINT CONSTRUCTS

Proposal package — Carr EFA Dressing Room Renovation, Sol 26-007

Solicitation: 26-007

Full proposal

PREPARED BY

Blue Print Constructs

RK Residential Homes and Commercial Constructions, LLC

UEI LM4YHVQ71QG7 · CAGE 9LET0 · Submission date _____

Ravikiran (Rocky) Nudurupati

Founder & Managing Director / Owner (100%)

rocky@blueprintconstructs.com · (469) 213-1838

Document prepared 2026-05-23 · bid-slug: angelo-state-carr-efa-26-007

Table of Contents

00	Proposal package — Carr EFA Dressing Room Renovation, Sol 26-007
01	Cover letter / executive summary — Carr EFA Dressing Room Renovation
02	Technical proposal narrative — Carr EFA Dressing Room Renovation (2026-05-23 refresh)
03	Project team — Carr EFA Dressing Room Renovation
04	Past performance — Carr EFA Dressing Room Renovation
05	Schedule narrative — Carr EFA Dressing Room Renovation (2026-05-23 refresh)
06	Quality control plan — Carr EFA Dressing Room Renovation
07	Site-specific safety plan — Carr EFA Dressing Room Renovation
09	Attachment D fill guide — HUB Subcontracting Plan (HSP) Form
10	Price proposal — Carr EFA Dressing Room Renovation (2026-05-23 refresh)

SECTION 00

00

Proposal package — Carr EFA Dressing Room Renovation, Sol 26-007

Proposal package — Carr EFA Dressing Room Renovation, Sol 26-007

Status: DRAFT — pending drawings + sub quotes + signatures **Owner:** Angelo State University / Texas Tech University System **Proposal due:** 2026-06-05, 2:00 PM CST (Friday) **HSP due:** 2026-06-08, 5:00 PM CST (Monday) — separate sealed submission, 3 calendar days AFTER the proposal **Construction window:** 2026-07-01 NTP → 2026-11-02 substantial completion (~124 calendar days) **Liquidated damages:** \$250 / calendar day past substantial completion **Cash/contingency allowance:** \$25,000 (carried separately on Attachment A — NOT rolled into base price)

A. What's in this folder

#	File	What it is	Status
00	00-readme.md	This file — submission overview, contents inventory, signing/sealing/delivery procedure	Draft
01	01-executive-summary.md	1-page cover letter / firm intro / project understanding	Draft (firm names = _____)
02	02-technical-approach	3–5 page phased work plan, demo sequencing, MEP rough-in coordination, finish schedule, owner-furnished demarcation table, schedule narrative	Draft
03	03-project-team.md	Org chart description + key-personnel sections	Skeleton (résumés = _____)
04	04-past-performance.md	Template for 3 similar projects	Skeleton (every project = _____)

05	05-schedule-narrative.md	Backwards-planned from 11/2 substantial completion; critical path; long-lead items; 13-day LD float	Draft
06	06-quality-control-plan	Per UGSC Art. 7 (Submittals/QC); 3-phase inspection, submittal log, deficiency log, project records	Draft
07	07-safety-plan.md	OSHA 1926 compliance + site-specific hazards (occupied campus performing-arts building)	Draft
08	08-attachment-A-fill-	Section-by-section fill guide for Attachment A (Proposal Form & Execution of Offer)	Draft
09	09-attachment-D-hsp-form	Section-by-section fill guide for Attachment D (HSP form)	Draft
10	10-price-proposal.md	Base bid summary + \$25K allowance + unit prices + CSI division breakdown (formulas; values come from final takeoff)	Draft (numbers = _____)
11	11-submission-checklist.md	Hand checklist: number of copies, sealing, original signatures, delivery method/address/timing	Draft

12	12-bid-bond-letter-templ	Template request letter to bonding agent	Draft
----	--------------------------	--	-------

The HSP form itself (Attachment D) is not in this folder — it is filled directly on the form provided in `inbox/opportunities/attachments/2026-05-21/ESBD_516718_..._Attachment D - HSP....pdf`. Use `09-attachment-D-hsp-form-guide.md` here to drive the fill-in, and `../05-hsp-plan.md` for the strategic background.

B. What goes in the sealed proposal envelope (Friday 2026-06-05, 2:00 PM CST)

Per `../02-bid-prep-checklist.md` § F and the RFCSP § Submission Instructions:

1. **Attachment A — Form of Proposal & Execution of Offer** (signed in blue ink, base price + \$25K allowance carried separately, all certifications signed)
2. **Cover letter** (see `01-executive-summary.md`)
3. **Technical proposal narrative** (see `02-technical-approach.md`)
4. **Project schedule exhibit** (CPM Gantt or bar chart per `05-schedule-narrative.md`)
5. **Key personnel résumés + project references** (see `03-project-team.md` + `04-past-performance.md`)
6. **Quality control plan** (see `06-quality-control-plan.md`)
7. **Safety plan + EMR letter** (see `07-safety-plan.md`)
8. **Assumptions & clarifications** (final page of technical narrative)
9. **Bid bond — 5% of base proposal** (original, on TTUS-required form, payable to "The Board of Regents of the Texas Tech University System")
10. **Bonding-agent P&P commitment letters** on bonding-agent letterhead
11. **Insurance ACORDs** (current within 30 days; ASU + TTUS Board of Regents listed as additional insured with waiver of subrogation per UGSC Art. 5)
12. **W-9** (current calendar year, signed)
13. **TX Conflict of Interest Disclosure (Form CIQ)** per Tex. Local Gov't Code Ch. 176
14. **Anti-collusion certification**
15. **TX resident-bidder reciprocal-preference attestation** per Tex. Gov't Code § 2252.002
16. **TX HB 1295 Certificate of Interested Parties** (file pre-emptively even though contract is below \$1M — TTUS member institutions commonly require)
17. **Addenda acknowledgments** (numbered, signed — re-check ESBD posting 516718 the day before submission)

18. **USB / digital copy** if RFCSP body so instructs (re-confirm on RFCSP re-read)

Each item above traces to a line on 11-submission-checklist.md.

C. What goes in the sealed HSP envelope (Monday 2026-06-08, 5:00 PM CST)

Per ../05-hsp-plan.md + 09-attachment-D-hsp-form-guide.md:

1. **HSP form from Attachment D, fully completed and signed** (Sections 1–4)
2. **Self-performing justification** (Section 3 of the form; draft text in ../05-hsp-plan.md § B)
3. **GFE documentation binder** — for every trade not meeting the project HUB goal: ≥3 dated HUB outreach attempts per trade, ad placements in ≥2 HUB publications, response log, written non-selection reasons
4. **Acknowledgement of revised-HSP requirement** signed
5. **Sample / blank revised-HSP form** to indicate awareness of post-award compliance

■ ■ HSP submission location may differ from proposal submission location. Confirm with Samuel Guevara by 2026-06-01 — see ../timeline.md § A 2026-06-01.

D. Signing / sealing / delivery procedure

Signing

- Attachment A — **blue ink, original signature**, signed by an officer of the firm with authority to bind (typically President or VP). Initials on every page that has an initial block.
- Bid bond — original, wet-signed by both surety officer (attorney-in-fact) AND firm officer; surety's seal embossed; surety's power of attorney attached.
- Insurance ACORDs — issued by the broker, dated within 30 days of submission, no white-out, no manual corrections.
- W-9 — signed within the current calendar year (not stale).
- CIQ — signed by the officer of the firm.
- HB 1295 — printed copy of the e-filed certificate from the TX Ethics Commission portal (https://www.ethics.state.tx.us/whatsnew/elf_info_form1295.htm); the certificate is "certified" only when bearing the EC's certificate number assignment.

Sealing

- Each package sealed in its own envelope (proposal = one envelope; HSP = separate envelope).
- Exterior labeling per RFCSP § Submission Instructions, typically: PROPOSAL – Carr EFA Dressing Room Renovation Solicitation 26-007 Due: 2026-06-05, 2:00 PM CST From: RK Residential Homes and Commercial Constructions, LLC dba Blue Print Constructs 16283 Willowick Ln, Frisco, TX 75033
- Tamper-evident seal (signed and dated across the flap).

Delivery

- **Hand-deliver preferred** for proposal — courier risk on TTUS submissions is real (lost packages = automatically late = automatic rejection).
- Arrive **≥30 minutes before** the 2:00 PM CST deadline on Friday.
- Obtain a **dated and timestamped receipt** from the ASU FP&C clerk.
- If unable to hand-deliver: use **next-day, signature-required courier** (FedEx Priority Overnight or UPS Next Day Air Saver) scheduled for **Thursday 6/4 delivery**, with Saturday delivery backup. NEVER ship for Friday-AM delivery on the day of the deadline — too much weather/route risk.

If courier service has a delay: by 12:00 PM CST on the deadline day, call Samuel Guevara to notify; this preserves the right to argue "good faith effort to submit timely" but does NOT relieve the deadline. TTUS practice is strict — 2:01 PM = late. There is no grace period.

Public opening

- TTUS pattern: public opening of base proposal prices **immediately after** the 2:00 PM CST deadline.
- Send a representative to attend if possible. Useful for competitive intelligence (who else bid, at what envelope).
- Public opening reads names + base bid amounts only — qualifications, references, schedules are not read.

E. Internal go/no-go status

Per ../07-risk-register.md § E, the bid-level go/no-go gate must be closed before assembly. Status as of this draft:

- ☐ R-01 — pre-response meeting eligibility (CRITICAL; resolve via Samuel)
- ☐ R-02 — owner-furnished demarcation in writing (resolve via Samuel)
- ☐ R-03 — site walk + hazmat survey (resolve via Samuel)

- [] R-07 — bonding capacity confirmation (resolve via bonding agent today)
- [] R-08 — Carr EFA production calendar 7/1–11/2 (resolve via Samuel)

Recommend closing each of these by **end of day 2026-05-25**. If any come back negative, surface to the user immediately for a deliberate go/no-go decision.

F. Cross-references

Question	Answer document
What's the actual scope?	<code>../04-scope-of-work.md</code>
What's the price stack going to look like?	<code>10-price-proposal.md</code> + <code>../price-references.md</code> + <code>../takeoff-template.json</code> + <code>../price-sheet-skeleton.json</code>
How does HSP get filed?	<code>../05-hsp-plan.md</code> + <code>09-attachment-D-hsp-form-guide.md</code>
What's the schedule?	<code>05-schedule-narrative.md</code> + <code>../timeline.md</code>
What contract terms matter?	<code>../08-contract-terms-flags.md</code>
What's missing from our package?	<code>../03-missing-documents.md</code> (Priority 1 = drawings + full project manual)
Who do I talk to?	<code>../contacts.md</code>
What are the labor rates?	<code>../prevailing-wages.md</code>
What are the bid risks?	<code>../07-risk-register.md</code>

SECTION 01

01

Cover letter / executive summary — Carr EFA Dressing Room Renovation

Cover letter / executive summary — Carr EFA Dressing Room Renovation

One-page cover letter that fronts the bound proposal. Print on _____.
Address to Tracie Howell, signed by

[Firm letterhead – name, address, phone, email, license/registration footer] 2026-06-05
Tracie Howell Director, Facilities Planning and Construction Angelo State University ASU
Station #10924 San Angelo, TX 76909 cc: Samuel Guevara, ASU FP&C

Re: Proposal for Carr EFA Dressing Room Renovation — Solicitation 26-007 (ESBD posting 516718)

Dear Director Howell:

RK Residential Homes and Commercial Constructions, LLC dba Blue Print Constructs is pleased to submit this competitive sealed proposal in response to Solicitation 26-007 for the Carr Education and Fine Arts Building Dressing Room Renovation at Angelo State University. We have read the full RFCSP package, Attachments A through F.1, the TTUS-edited 2010 Uniform General Conditions (dated 09.07.2023), the Sample Construction Services Agreement (Attachment B.2), and the Tom Green County Prevailing Wage Determination dated July 2023, and we are responsive to each requirement.

Project understanding. The scope is a complete interior renovation of the Carr EFA dressing rooms: full demolition and replacement of interior finishes, HVAC, plumbing, electrical, lighting, and door hardware, with new IT infrastructure pathway and full ADA compliance under the alterations standard (28 CFR 35.151). Owner-furnished items — technology systems, network/data cabling, equipment install, furniture/FF&E, and fire suppression — are not in our price. We have priced coordination, protection, and rough-ins (including CBORD access-control door prep and low-voltage pathway) for these owner-furnished items, and our technical narrative includes a written demarcation table that clearly identifies where our scope ends and ASU's owner-vendor scope begins.

Why us. _____

Team. Project Manager _____ and Superintendent _____ are committed to the full construction window of 2026-07-01 NTP through 2026-11-02 substantial completion. Both have direct experience on _____. A full org chart and résumés follow in the Project Team section.

Schedule. We have backwards-planned the 124 calendar day construction window with conservative durations that accommodate (1) the active performing-arts building constraint at Carr EFA, (2) EHS-coordinated shutdown windows for fire alarm, HVAC, and electrical cutovers, and (3) long-lead items: theater-grade millwork (10–14 weeks), Sargent cylindrical hardware (8–14 weeks), and theater-grade dimming lighting. Our target internal substantial completion is 2026-10-20, banking 13

days of float against the contract date of 2026-11-02 and the \$250/day liquidated-damages trigger.

HSP. Our HUB Subcontracting Plan, delivered Monday 2026-06-08 per the RFCSP separate-submission schedule, commits to **30% HUB participation of subcontracted dollars**, aligning with the TTUS Sample CSA pattern and exceeding the statewide 21.1% building-construction floor (34 TAC §20.284). Good-faith-effort documentation, including dated outreach to ≥3 HUB subs per major trade and advertisements in two state-approved HUB publications, accompanies the HSP submission.

Price summary.

Line	Amount
Base proposal (lump sum, lock all subcontracted scope per 04-scope-of-work.md)	\$_____
Cash/contingency allowance per Attachment A (separate line; not marked up)	\$25,000
Total	\$_____

Unit prices, if requested by the RFCSP, are filled in on Attachment A and detailed in our Price Proposal section.

Bonds + insurance. Bid bond in the amount of 5% of the base proposal is attached, payable to "The Board of Regents of the Texas Tech University System" on TTUS-required form. Performance and Payment bonds at 100% of contract value are committed at award via _____, surety rated A.M. Best A- or better and listed on US Treasury Circular 570. Insurance certificates compliant with UGSC Article 5 — naming "The Board of Regents of the Texas Tech University System, Angelo State University, and their officers, employees, and agents" as additional insured with waiver of subrogation and primary-and-non-contributory language — will be delivered before any work begins.

Acknowledgments. We have received and acknowledge the following addenda, if any: _____ . This proposal is firm for _____ from the submission date.

We appreciate the opportunity to propose on this project and look forward to delivering a successful renovation of the Carr EFA dressing rooms on time, on budget, and to the quality standards that ASU students, faculty, and performing-arts patrons deserve.

Respectfully submitted,

RK Residential Homes and Commercial Constructions, LLC dba Blue
Print Constructs contactus@blueprintconstructs.com Date: 2026-06-05

Attachments to this letter: - Attachment A (Form of Proposal & Execution of Offer), signed - Technical proposal narrative + schedule exhibit - Project team + past performance - Quality control plan + safety plan - Assumptions & clarifications - Bid bond (original) - Bonding-agent commitment letters (P&P) - Insurance ACORDs - W-9, CIQ, HB 1295, anti-collusion cert, TX resident-bidder attestation

SECTION 02

02

Technical proposal narrative — Carr EFA Dressing Room Renovation (2026-05-23 refresh)

Technical proposal narrative — Carr EFA Dressing Room Renovation (2026-05-23 refresh)

*Target length: 3–5 pages bound. Page-count cap per RFCSP Section L not yet verified on the body re-read; default 10 pages until confirmed. Evaluation criteria per Addendum #1 slide 17: **Cost 45 / Firm + Team Qualifications 25 / Schedule Commitment 20 / RFCSP Compliance 10 = 100.** This narrative is the principal vehicle to score on the 25 + 20 + 10 = 55 non-cost points.*

1. Project understanding

The Carr Education and Fine Arts Building Dressing Room Renovation is a **3,115-SF interior renovation** to 10 rooms in the Carr EFA Building at 2602 Dena Dr, San Angelo, TX. Source documents: the 38-sheet base drawing set dated 2026-03-27 (PBK Architects, LEAF Engineers, Lundy & Franke Engineering, PBK Project No. 250402), as modified by Drawings Addendum 1 (2026-04-15) and Drawings Addendum 2 (2026-05-07), together with the 796-page Project Manual (Issue for Construction 2026-03-27) and Addendum #1 (Pre-Response Meeting deck and sign-in sheet, 2026-05-20).

The scope splits into two distinct zones:

Back-of-house dressing suite (1,047 SF): Full reno of Green Room 107 (222 SF), Makeup Room 108 (434 SF), Women's Dressing 109 (135 SF), Men's Dressing 110 (136 SF), Women's RR 1R9 (159 SF), and Men's RR 1R10 (160 SF). New porcelain floor tile (T1) throughout, blue accent wall tile (T2) and ridged white wall tile (T3) in restrooms, 2"x2" shower mosaic tile (T4, added per Drawings Addendum 2) inside two ADA shower receptors, new vanity countertops with theater-grade LED-lit mirror surrounds at three makeup stations (24"x72" mirrors per Drawings Addendum 1), HPB hardwood base in Green Room, new acoustical ceilings throughout, full MEP replacement, ADA-compliant toilet partitions (phenolic-core), metal lockers per Project Manual Section 10 51 13, and full Sargent door hardware package per Section 08 71 00.

Circulation + entry (2,068 SF): Selective renovation of Corridor 101 (641 SF), Front Entry 106 (1,098 SF), plus minor MEP-only scope at Mechanical Room 104 (61 SF) and Elevator 105 (68 SF). Existing wallpaper retained where called out on AF100; new carpet tile (CPT1) in entry; salvage and re-use of existing 2x4 corridor light fixtures in Makeup Room 108 per Drawings Addendum 2; new 8" can lights and emergency lighting added in corridor per Drawings Addendum 2.

Owner-furnished scope (confirmed by Project Manual Division 21 being marked "NOT USED" + RFCSP narrative): fire suppression system, AV/technology equipment, network/data cabling and terminations, FF&E (makeup chairs, costume racks), and CBORD access-control devices (readers, controllers, electric strikes). Contractor scope includes the pathway and door preparation that makes those owner systems functional.

Code compliance: full ADA alterations-standard pass per Project Manual Section 01 35 16 (Alteration Project Procedures) covering door clear widths, hardware reach ranges, accessible routes, mirror

heights, lavatory rim and knee clearance, accessible signage per Section 10 14 00, and two ADA shower stalls per Section 22 40 00 (added per Drawings Addendum 2 with mosaic tile spec 09 30 00.T4).

2. Owner-furnished scope demarcation (confirmed against Project Manual TOC)

The RFCSP narrative + Project Manual TOC identify these owner-furnished scopes outside the GC contract:

#	Owner-furnished item	Confirmation	Our scope	Their scope
1	Fire suppression system	Confirmed — PM TOC marks Div 21 "NOT USED"	Coordinate access to existing FP system; protect during demo	All FP work (sprinkler relocation, mains, branches, shutdown, hydrostatic testing)
2	Technology / AV equipment	RFCSP narrative + Addendum #1 slide 4	Power + pathway (conduit, J-boxes, ring & string) per PM Sec 27 00 00 + 27 05 00	All AV equipment supply, install, programming, commissioning
3	Network / data cabling and termination	Default assumption (PM Sec 27 10 00 Structured Cabling System is in the manual; clarification request open with Hannah Bignall)	Pathway only (plenum-rated conduit + J-box + ring/string)	All cable pulls, terminations, faceplates, jacks, labeling, testing

4	Equipment install (post-construction equipment)	RFCSP narrative	Provide finished spaces; coordinate sequence	Receiving, storing, installing, commissioning, warranty of owner equipment
5	Furniture / FF&E (makeup chairs, costume racks)	RFCSP narrative	Wall blocking per PM Sec 06 10 00; protection of finishes during owner install	FF&E supply and install
6	CBORD access-control devices (readers, controllers, electric strikes)	RFCSP narrative + Addendum #1 slide 4	Door hardware prep per PM Sec 08 71 00, low-voltage conduit + ring/string per Sec 27 05 00, 120V or PoE pathway per Sec 26 05 34	CBORD reader/controller/electric strike supply, install, programming, commissioning

Items NOT owner-furnished (i.e., in contractor scope, contrary to earlier prep-doc assumption):

#	Item	PM section	Note
7	Sargent cylindrical mechanical locksets	PM Sec 08 71 00	Contractor supply + install + keying per CBORD admin's master-key schedule
8	Metal lockers	PM Sec 10 51 13	Confirmed contractor scope (earlier prep-doc assumption was wrong)

9	Mirrors (including dressing-room vanity mirrors per Drawings Addendum 1)	PM Sec 08 83 00	Contractor supply + install
10	Salvage and re-use of existing 2x4 corridor light fixtures in Makeup Room 108	Drawings Addendum 2	Contractor careful-demo + interim storage + reinstall

This demarcation is the canonical baseline for sub-quote scoping. Every subcontract issued under this contract carries the demarcation table verbatim in its scope-of-work exhibit. The single open clarification — Section 27 10 00 Structured Cabling System scope — has been raised in writing with Hannah Bignall in our 2026-05-23 eligibility/clarification email; pricing assumes pathway-only with a unit-price alternate for full pull + terminate if clarified otherwise. Our _____ is the single owner-vendor coordination POC for the duration of construction.

3. Approach and phased work plan

The 124-day construction window is sequenced into seven phases. Each phase identifies its critical path, the EHS shutdown windows required, the long-lead items that gate the phase, and the owner-vendor handoff points.

Phase 1 — Mobilization, protection, coordination (Weeks 1–2, 7/1–7/14)

- Site mobilization at the ASU-designated lay-down location; install full negative-air dust containment with HEPA filtration around the dressing-room footprint; install walk-off mats and protection of all adjacent occupied spaces (theater, classrooms, faculty offices).
- Hold kickoff meeting with Samuel Guevara (ASU FP&C), ASU EHS, and the A/E firm to establish the RFI cadence (target 5 business day response), submittal log, and EHS shutdown notification protocol (target 2 weeks lead time for any utility interruption).
- Hold dedicated CBORD coordination call with the ASU CBORD system administrator and our door hardware sub + electrical sub to confirm electric strike specifications, conduit pathway, J-box size, and 120V vs PoE power requirements at each access-controlled door.
- Confirm ASU EHS hazmat survey results (or coordinate immediate survey if not on file). If asbestos or lead is detected in VCT, mastic, pipe insulation, or fireproofing, transition to Phase 2 (Demo) only after abatement is complete or scheduled.
- Order all long-lead items: theater-grade dressing-room millwork (vanities + LED-lit mirror surrounds, 10–14 wk), Sargent cylindrical locksets with the specified cylinder series (8–14 wk), theater-grade dimmable LED light fixtures (6–8 wk), HM frames (8–10 wk), specified HVAC equipment (8–12 wk).

Phase 2 — Selective demolition (Weeks 3–4, 7/15–7/28)

- Selective demolition of all interior finishes, casework, ceilings, and MEP terminations within the dressing-room footprint. Demo of HVAC ductwork, plumbing rough-ins, and electrical rough-ins is sequenced with the respective MEP subcontractors to avoid orphaned services in the building.
- After-hours premium work scheduled for any noisy demo during Carr EFA active hours; daytime demo only on confirmed dark-house days from the College of Arts and Humanities production calendar.
- Any differing site conditions discovered during demo (additional asbestos, undersized existing electrical service, damaged structural elements, hidden water-damage) are documented with photographs and immediate written notice to Samuel within 5 calendar days, well inside the UGSC Article 4 (differing site conditions) notice window.

Phase 3 — MEP rough-in (Weeks 5–8, 7/29–8/25)

- HVAC ductwork from existing trunk to new diffusers and grilles; new air handler or VAV terminal install; dedicated dressing-room exhaust ductwork to roof or existing exhaust collector.
- Plumbing supply, waste, and vent rough-in coordinated with the existing risers; ADA-compliant fixture locations laid out per drawings.
- Electrical branch wiring including dedicated 20A circuits at each makeup station, GFCI protection at all wet locations, lighting controls infrastructure, sub-panel install if existing service is undersized, and all low-voltage pathway (conduit + ring & string) for owner-furnished AV, data, and CBORD cabling.
- Door prep at each access-controlled door: electric strike mortise in HM frame, electric hinge or low-voltage conduit pathway from frame to plenum, 120V or PoE pathway at reader location. Owner-furnished CBORD devices themselves are NOT installed in this phase — owner's vendor follows our punch closure.
- All in-wall inspections (rough-electric, rough-plumbing, framing, fire-stopping) requested with the AHJ before any wall closure.

Phase 4 — In-wall and above-ceiling close-out (Weeks 9–11, 8/26–9/15)

- Light-gauge metal-stud framing for any new or modified partitions, with PT-plywood blocking installed for all wall-mounted accessories (mirrors, costume racks, ADA grab bars, CBORD reader backing).
- Fire-stopping at all through-penetrations per the listed UL system; insulation; air-sealing.
- Type-X GWB hung on both faces of partitions and on furring at exposed brick areas; moisture-resistant GWB in any wet zones; resilient channel below GWB ceilings in wet areas.
- Ceiling grid set per the RCP, with all in-grid coordination complete (light fixtures, diffusers, sprinkler heads — sprinkler heads installed by owner's FP contractor in coordination with us).
- Brick wall restoration (clean, repoint, seal) where exposed brick is the specified finish.

Phase 5 — Finishes (Weeks 12–14, 9/16–10/06)

- Flooring install: heat-welded sheet vinyl in dressing-room interiors, LVT in adjacent circulation, ceramic tile in any wet zones with the appropriate waterproofing membrane.
- Resilient base around all room perimeters and casework toe-kicks.
- 2-coat institutional low-VOC paint on walls, ceilings (where GWB), and door frames.
- Finish carpentry: paint-grade MDF or wood trim at door openings and wall accents.
- Millwork install: makeup vanities, counters, mirror surrounds with LED-lit mirror frames (theater-grade), costume storage shelving.
- Acoustical ceiling tile drop-in.
- Door + frame + Sargent cylindrical hardware install. Hardware keying coordinated with the CBORD admin's master-key schedule.

Phase 6 — MEP trim, accessories, fire alarm (Weeks 15–16, 10/07–10/20)

- Light fixture install (theater-grade dimmable LED at general areas, dedicated makeup-mirror lighting in the millwork, egress and emergency lighting per IBC).
- Diffuser and grille install at the ceiling grid.
- Plumbing fixture set (lavatories, water closets where applicable, shower stalls in wet zones).
- Electrical device install (receptacles, switches, GFCI, lighting control switches) and final terminations.
- Lighting controls programming (occupancy + manual override + dimming per ASU/TTUS standard).
- Fire-alarm device install (strobe, smoke detector) coordinated with ASU EHS shutdown windows.
- Specialties install (ADA signage with raised characters + Braille, toilet accessories, fire extinguishers + cabinets).

Phase 7 — TAB, commissioning, punch, owner training, substantial completion (Weeks 17–18, 10/21–11/02)

- Independent test/adjust/balance agency performs the TAB report on the new HVAC system.
- Commissioning of lighting controls and HVAC controls integration into ASU's BMS.
- Owner training on all installed systems (HVAC controls, lighting controls, plumbing fixtures, hardware keying).
- Walk-through punch list with Samuel Guevara and the A/E firm; address all punch items.
- Substantial completion **internal target: 2026-10-20**, banking 13 days of float against the contract substantial-completion date of **2026-11-02** and the \$250/day liquidated damages trigger.

Phases 8 (close-out: record drawings, O&M manuals, attic stock, final cleaning, final pay app) runs in weeks 19–22 (11/03–11/30), nominally outside the 124-day window but completed before the final retainage release per UGSC Article 10.

4. Coordination with active performing-arts building

Carr EFA hosts theater, dance, music classes and productions year-round. Our schedule is built around three constraints:

1. **No daytime noisy work during business hours during fall semester** (8 AM – 5 PM weekdays beginning late August through November). Demolition, MEP cutover, and any percussive or high-decibel work is scheduled either before the fall semester begins (Phases 1–3 fall in the early-summer window when Carr EFA is comparatively dark) or after-hours/weekends during the semester.
2. **No work during scheduled productions, dress rehearsals, or recitals** (typically 7 PM – 11 PM, with full dark-house requirements on production days). Our PM coordinates a written access calendar with the College of Arts and Humanities, updated weekly, with at least one week of advance notice for any production-day work.
3. **No interference with adjacent active spaces** at any time. Dust containment is negative-air HEPA-filtered, with daily containment-integrity inspection logged. Walk-off mats at all containment transitions. Sound-mitigating partitions during any non-silent work occurring during occupied hours.

We carry after-hours premium labor (1.3–1.5× day rate) on approximately 25% of demolition and MEP cutover work hours in our base pricing, calibrated to the expected access-window constraints. The exact percentage will be refined as soon as the production calendar is shared by Samuel Guevara.

5. Quality control approach

Detailed quality control plan is in `06-quality-control-plan.md`. Key elements:

- **3-phase inspection at each critical milestone** (preparatory phase, initial phase, follow-up phase) per the USACE QC standard adapted to TTUS UGSC Article 7.
- **Submittal log** tracked weekly with target turnaround of 14 calendar days from submission to A/E approval. Long-lead submittals (millwork, hardware, HVAC equipment, lighting) are prioritized into Week 1.
- **Deficiency log** with photographs, item assignment, and target close-date for any non-conforming work; reviewed weekly with our superintendent and the A/E firm.
- **Pre-punch inspection** at Week 17 to surface all deficiencies before the official punch walk with Samuel and the A/E.
- **Independent agency** for TAB, with the TAB report delivered with the close-out package.

6. Schedule narrative summary

Detailed schedule narrative is in 05-schedule-narrative.md and a CPM Gantt chart accompanies this proposal as a separate exhibit. In summary:

- NTP 2026-07-01, substantial completion contract date 2026-11-02 (124 calendar days).
- Internal target substantial completion 2026-10-20, providing 13 days of float against the LD trigger.
- Critical path runs through HVAC equipment lead (long-lead, 8–12 wk), theater-grade millwork lead (10–14 wk), and the final-finishes phase (weeks 12–14) which is the most-constrained around the late-August semester start.
- Long-lead items are submitted in Phase 1 (weeks 1–2) to land in time for Phase 5 (weeks 12–14): Sargent hardware, theater-grade millwork, theater-grade LED dimming fixtures, specified HM frames, specified HVAC equipment.
- Float against the LD trigger is preserved by aggressive front-loading of submittal turnaround and proactive RFI churn management.

7. Assumptions and clarifications

This proposal is priced against the RFCSP, the 38-sheet drawing set dated 2026-03-27 with Addenda 1–2, the 796-page Project Manual (Issue for Construction 2026-03-27), and Addendum #1 (Pre-Response Meeting deck dated 2026-05-20), supplemented by these clarifying assumptions:

1. **Project area 3,115 SF total**, comprised of ten rooms per drawing sheet AF100: Corridor 101 (641 SF), Mechanical 104 (61 SF), Elevator 105 (68 SF), Front Entry 106 (1,098 SF), Green Room 107 (222 SF), Makeup Room 108 (434 SF), Women's Dressing 109 (135 SF), Men's Dressing 110 (136 SF), Women's RR 1R9 (159 SF), Men's RR 1R10 (160 SF). Scope density varies materially between the back-of-house dressing suite (1,047 SF heavy reno) and the circulation/entry zone (2,068 SF light reno) and is priced separately on those two sub-totals.
2. **No hazardous-materials abatement budgeted in base price.** Project Manual Section 00 31 00 "Available Project Information" (which would normally include the hazmat survey) was not provided in the issued documents; clarification request open with Hannah Bignall. PM contains Sections 02 82 13 (Asbestos Abatement) and 02 83 16 (Lead Remediation) as *contingent* sections — they apply only if hazmat is encountered. If abatement is required, it may be funded from the \$25,000 Cash/Contingency Allowance (Attachment A) or as a change order under UGSC Article 4 (Differing Site Conditions).
3. **Existing structure remains** — no structural modifications; renovation is interior-only. Sheet S100 confirms no structural sheets in the issued set.
4. **Owner-furnished items per the demarcation table in Section 2 above** are not in our base price. Open clarification: PM Sec 27 10 00 Structured Cabling System scope (pathway-only vs. full pull + terminate); pricing assumes pathway-only with a unit-price alternate.

5. **Builder's Risk insurance** assumed owner-carried per TTUS pattern (UGSC Article 5); if GC-carried, will be added by change order at award. UGSC Art. 5 limits for GL, Auto, WC, and Umbrella are within our existing carrier-confirmed limits.
6. **Substantial completion 2026-11-02** is treated as a fixed calendar date with the LD clock starting on that date regardless of NTP timing. We have built 13 days of internal float; we reserve the right to request a no-cost time extension via the UGSC Article 9 change-order procedure if NTP is delayed beyond 2026-07-01.
7. **Prevailing wage** priced against Tom Green County determination dated July 2023 (Attachment F.1, confirmed operative by Project Manual Section 00 73 46) with a +12% labor cost escalation factor reflecting 2023–2026 Texas construction wage inflation. If TTUS issues an updated WD applicable to this project between submission and NTP, we will conform to the higher rate at no change to the contract sum (subject to the escalation factor in our bid).
8. **Cash/contingency allowance** of \$25,000 per Attachment A is carried as a separate line item, not rolled into the base price, not marked up. Allowance consumption is by change-order procedure per the CSA.
9. **Eligibility resolved.** The 2026-05-20 pre-response meeting was non-mandatory per Addendum #1 (cover memo and sign-in sheet show attendance was advisory, not a prerequisite to submit a proposal). R-01 in our risk register is RESOLVED; no formal eligibility waiver is required from ASU Procurement.
10. **A/E team:** PBK Architects (architect of record, PBK Project No. 250402); LEAF Engineers (MEP); Lundy & Franke Engineering (structural — though no structural sheets in the issued set, confirming interior-only scope). Day-to-day procurement POC: Hannah Bignall (hannah.bignall@angelo.edu, 325-942-2380). PM/Facilities POC: Samuel Guevara. Construction Coordinator: Matt Marshall.
11. **Contract document discrepancy.** Project Manual references "Job Order Contract" in places (typical PBK office boilerplate), while the RFCSP body and Attachment B.2 use TTUS's Construction Services Agreement (CSA). We have priced and proposed against the CSA per the RFCSP body; written clarification has been requested from Hannah Bignall.
12. **Project Manual Section 01 35 16 (Alteration Project Procedures)** governs all alteration-specific procedures including ADA upgrade requirements, salvage protocols, dust control during occupied-building work, and matching of existing finishes; our base price reflects compliance with this section.

Any clarification of the foregoing assumptions discovered between proposal submission and award will be confirmed in writing with Hannah Bignall (cc Samuel Guevara) prior to the executed CSA.

SECTION 03

03

Project team — Carr EFA Dressing Room Renovation

Project team — Carr EFA Dressing Room Renovation

Bound separately or appended to the technical narrative as instructed by RFCSP § Submission Format. Target length: 2 pages. Each résumé block below is a template; the firm fills in the actual person + project history.

1. Organization chart

[illegible]

External owner-vendor coordination (CBORD admin, ASU IT, ASU EHS, owner's AV/data cabling vendor, owner's FP contractor, owner's FF&E vendor) routes through the Project Manager as the single coordination POC, with the Superintendent supporting field-level handoffs.

2. Key personnel — full résumé blocks

Format: for each role below, the firm fills in: full name, professional credentials, years with firm + years in trade, narrative bio (≤150 words), recent similar-project list (≥3 projects with dollar value + role + completion year). Each résumé attaches as a separate exhibit if running long; the table form below is sufficient if names + project list fit on one page each.

Role 1 — Project Executive (oversight, escalation, contract authority)

Field	Value
Name	
Title	
Credentials	

Years with firm	
Years in trade	
Project role	Contract oversight, escalation POC for Tracie Howell, financial accountability
% time on project	~5–10%
Bio	

Similar past projects (≥3, last 5 years):

Project	Owner	Role	\$ value	Completion year

Role 2 — Project Manager (day-to-day owner-facing lead)

Field	Value
Name	
Title	
Credentials	
Years with firm	
Years in trade	

Project role	Single coordination POC for Samuel Guevara and all owner-vendor coordination (CBORD admin, ASU IT, ASU EHS, owner's AV/data cabling vendor, owner's FP contractor, owner's FF&E vendor); manages submittal log, RFI cadence, schedule updates, pay applications, change-order management
% time on project	50%–75%
Bio	

Similar past projects (≥3, last 5 years):

Project	Owner	Role	\$ value	Completion year
		PM		
		PM		
		PM		

Critical: If the firm has any prior **TTUS or ASU work**, surface it here as the lead reference. Owner familiarity with the firm is the single strongest scoring signal.

Role 3 — Superintendent (field supervision, daily site management)

Field	Value
Name	
Title	
Credentials	
Years with firm	
Years in trade	

Project role	Full-time on-site supervision; subcontractor coordination; daily safety toolbox; quality control 3-phase inspections; punch-list management
% time on project	100% (full-time) for 124-day construction window
Bio	

Similar past projects (≥3, last 5 years):

Project	Owner	Role	\$ value	Completion year
		Super		
		Super		
		Super		

Role 4 — Safety Manager (project-specific safety program)

Field	Value
Name	
Title	
Credentials	
Years with firm	
Years in trade	
Firm EMR	
Project role	Project-specific safety plan author; weekly safety walk; incident investigation; OSHA recordable tracking; coordination with ASU EHS

% time on project	~10–15%
Bio	

Role 5 — Estimator (pre-NTP; named on the proposal for accountability)

Field	Value
Name	
Title	
Credentials	
Project role	Pricing accountability; assumption-defense on RFI clarifications; transition to PM on NTP
Bio	

3. Key subcontractors (subset to surface in narrative; full list in HSP)

Names are filled in after sub-quotes arrive (target 2026-05-29). Below is the structure; the names + HUB-cert numbers come from ../05-hsp-plan.md § C and the HSP form (Attachment D) once locked.

Trade	Sub name	Years sub	HUB-cert #	Similar past projects
Selective demolition				
Drywall / framing				
Finish carpentry / millwork (theater-grade)				

Flooring				
Painting				
Plumbing				
HVAC				
Electrical				
Door hardware (Sargent distributor)				
Hazmat abatement (if triggered)				

4. Coordination POCs on our team for owner-furnished interfaces

A specific person on our team is named for each owner-vendor coordination point. This is unusual for a sub-\$1M proposal and is intended to signal that we have read the owner-furnished demarcation carefully:

Owner-furnished item	Our coordination POC	Comm cadence
Fire suppression (owner's FP contractor)	Superintendent	Weekly during Phases 2–4; daily during cutover
AV/IT systems (ASU IT)	Project Manager	Bi-weekly through Phase 5; weekly Phase 6
Data cabling (ASU's cabling vendor)	Project Manager	Bi-weekly through Phase 4; weekly Phase 5
Equipment install (post-construction)	Project Manager	At Phase 6 completion + close-out
FF&E supply / install	Project Manager	At Phase 6 completion

CBORD devices + programming	Project Manager (CBORD coordination) + Superintendent (field)	Kickoff week, then bi-weekly through Phase 5
ASU EHS shutdown windows (FA, HVAC, electrical, water)	Superintendent	2 weeks lead time per request; logged in submittal/RFI log

SECTION 04

04

Past performance — Carr EFA Dressing Room Renovation

Past performance — Carr EFA Dressing Room Renovation

Past-performance picks for this bid (from *firm/firm-profile.json* → *past_project_selection_rules.angelo-state-carr-efa-26-007*):

1. **Hindu Temple of Southlake** — North Texas Hindu Heritage Society (nonprofit religious owner); ≈10,700 SF Assembly A-3 (Place of Religious Worship) renovation at 595 South Kimball Avenue, Southlake, TX 76092; owner-side project # 2024-024; scope: demolition + finishes + phenolic toilet partitions + partition framework; drawings dated 2025-06-20 (PDF), updated 2025-09-12 (Arch + Structural); in execution per material quote 2025-10-30; delivery method: negotiated lump-sum (owner direct); role: GC. Final contract value: _____.
Reference contact: _____.
2. **Holiday Inn (Hall Park, Frisco)** — Holiday Inn franchisee (hospitality owner); commercial renovation at Hall Park, Frisco, TX; role: GC. Contract value, scope detail, and completion date: _____. **Reference contact:** _____.
3. **250–500+ single-family-home portfolio (cumulative since 2022)** — executed primarily as a specialty trade sub through GC partners That 1 Painter, Touchmark, Bridge View Build, and Hill Design Build across the DFW metroplex; scope: interior + exterior painting, drywall (tape/bed/texture), flooring, tile, trims, roofing repairs; role: specialty sub. Reference contacts: _____.

The per-project entry templates below have been pre-filled for sections that match the standard TAMU/ASU reference-header shape. Bid workspaces with a different template shape (USACE / federal) still need the user to copy the recommended pick data manually into each Project N section.

Target length: 1–2 pages. Three project references are the floor; five is typical for a TTUS RFCSP. Each project gets a table header for at-a-glance review plus a 1-paragraph narrative covering relevance to Carr EFA.

Project-selection strategy (per ../06-evaluation-strategy.md § B): prioritize, in order: 1. Prior TTUS member-institution work (TTU main, ASU, ASU-San Angelo, ASU-El Paso, AS-Health Sciences Center). Owner familiarity with the firm is the single strongest scoring signal. 2. Prior TX higher-ed renovation under \$1M (UT System, TAMU System, other TX state schools). 3. Performing-arts or theater-support renovation (any owner, any state). 4. Active-building / occupied-space institutional renovation (any owner, any sector — hospital, courthouse, school). 5. Any sub-\$1M institutional renovation with strong MEP-replacement scope.

The firm needs three solid references; if the firm has all five categories, surface them in this order. If the firm has only one or two categories, fill the remaining slots with the strongest available institutional renovation references.

At-a-glance summary table

#	Project name	Owner	Contract value	Completion year	Same-team?	Why relevant to Carr EFA
1	Hindu Temple of Southlake — Place of Religious Worship renovation	North Texas Hindu Heritage Society	_____	_____	_____	Selected per firm-profile past_project_selection_rule
2	Holiday Inn (Hall Park) — hospitality renovation	Holiday Inn franchisee at Hall Park, Frisco, TX	_____	_____	_____	Selected per firm-profile past_project_selection_rule

3	250-500+ single-family-h portfolio (cumulative; multiple owners)	Multiple — primarily through GC partners That 1 Painter, Touchmark, Bridge View Build, Hill Design Build	_____	Ongoing 2022–present	_____	Selected per firm-profile past_project_selection_rule
4 (opt)	_____	_____	\$ _____	_____	_____	_____
5 (opt)	_____	_____	\$ _____	_____	_____	_____

Project Reference #1 — Hindu Temple of Southlake

Hindu Temple of Southlake — North Texas Hindu Heritage Society (nonprofit religious owner); ≈10,700 SF Assembly A-3 (Place of Religious Worship) renovation at 595 South Kimball Avenue, Southlake, TX 76092; owner-side project # 2024-024; scope: demolition + finishes + phenolic toilet partitions + partition framework; drawings dated 2025-06-20 (PDF), updated 2025-09-12 (Arch + Structural); in execution per material quote 2025-10-30; delivery method: negotiated lump-sum (owner direct); role: GC. Final contract value: _____. **Reference contact:** _____.

Source: Hindu Temple of South Lake/ on OneDrive.

Field	Value
Owner	_____
Owner contact	_____
Owner contact relationship to project	_____
Project location	_____

Project type	
Contract delivery method	
Contract value	\$
Original schedule	
Actual completion	
On-time?	
Final contract value vs original	
Self-performed scope	
Subcontracted scope	
Key personnel from this proposal who worked on this project	
HUB participation actual	

Narrative (≤200 words):

Project Reference #2 — Holiday Inn (Hall Park)

Holiday Inn (Hall Park, Frisco) — Holiday Inn franchisee (hospitality owner); commercial renovation at Hall Park, Frisco, TX; role: GC. Contract value, scope detail, and completion date: _____.

Reference contact: _____.

Field	Value
Owner	
Owner contact	

Owner contact relationship to project	
Project location	
Project type	
Contract delivery method	
Contract value	\$
Original schedule	
Actual completion	
On-time?	
Final contract value vs original	
Self-performed scope	
Subcontracted scope	
Key personnel from this proposal who worked on this project	
HUB participation actual	

Narrative (≤200 words):

Project Reference #3 — 250-500+ single-family-home portfolio

250–500+ single-family-home portfolio (cumulative since 2022) — executed primarily as a specialty trade sub through GC partners That 1 Painter, Touchmark, Bridge View Build, and Hill Design Build across the DFW metroplex; scope: interior + exterior painting, drywall (tape/bed/texture), flooring, tile, trims, roofing repairs; role: specialty sub. Reference contacts: _____.

Field	Value
-------	-------

Owner	
Owner contact	
Owner contact relationship to project	
Project location	
Project type	
Contract delivery method	
Contract value	\$
Original schedule	
Actual completion	
On-time?	
Final contract value vs original	
Self-performed scope	
Subcontracted scope	
Key personnel from this proposal who worked on this project	
HUB participation actual	

Narrative (≤200 words):

Optional Project Reference #4 —

Optional Project Reference #5 — ---

Reference contact instructions

- Verify each owner contact's **current** phone and email **before** submission. Stale references with disconnected numbers are interpreted as inattention by TTUS evaluators.
- Notify each reference contact ≥ 48 hours in advance that an ASU evaluator may call. A reference that is "caught cold" rates worse than a reference that has been primed to expect the call.
- If the firm has no prior performing-arts renovation, lead the narrative on each of References #1–#3 with the closest analogous experience: occupied-building MEP replacement, ADA-alterations compliance, after-hours work in active institutional buildings, owner-furnished coordination on access control / IT systems / FF&E.

Cross-reference to evaluation strategy

Per ../06-evaluation-strategy.md § A, past performance / qualifications typically carries **15–25% of the total evaluation score**. This is the second-largest scoring factor after price and is the easiest to differentiate on. The narrative for each project should directly answer the question: "**Has this firm done a project that looks like Carr EFA, and did it go well?**"

SECTION 05

05

Schedule narrative — Carr EFA Dressing Room Renovation (2026-05-23 refresh)

Schedule narrative — Carr EFA Dressing Room Renovation (2026-05-23 refresh)

Companion document to the CPM Gantt exhibit (separate; submitted as a printed exhibit with the proposal). This narrative explains the critical path, long-lead items, EHS shutdown windows, owner-furnished handoffs, and float strategy that the Gantt represents in bar-chart form.

Refresh basis (2026-05-23): Critical-path long-lead items revalidated against the 796-page Project Manual TOC and the 38-sheet drawing set. New long-leads surfaced from the PM (porcelain tile T1/T2/T3 + mosaic T4, metal lockers, phenolic toilet partitions). Construction window per Addendum #1 deck slide 6 confirms ~120-day target.

1. Anchors

Anchor	Date	Source
Solicitation 26-007 issued	2025-10-22 (preliminary, per ESBD posting timestamp)	ESBD posting 516718
Proposal due	2026-06-05, 2:00 PM CST	RFCSP cover
HSP due	2026-06-08, 5:00 PM CST	RFCSP § HUB Subcontracting Plan
Expected award notice	2026-06-15 to 2026-06-22	TTUS pattern, sub-\$1M contract
Contract execution + bonds delivered	by 2026-06-30	UGSC Art. 6 + typical 10-day window post-award
Notice to Proceed (NTP)	2026-07-01	RFCSP § Time of Performance
Substantial completion (contract date)	2026-11-02	RFCSP § Time of Performance
Substantial completion (internal target)	2026-10-20	Internal — 13 days of float against contract date

Final completion + final pay app	~2026-12-02	Typical 30 days after substantial completion
Warranty period start	2026-11-02	UGSC Art. 12 — runs 1 year from substantial completion

The 124-day construction window from 2026-07-01 NTP to 2026-11-02 substantial completion is the binding constraint. **Liquidated damages of \$250 / calendar day** start accruing on 2026-11-02. Per ../07-risk-register.md R-02, we have backwards-planned with conservative phase durations rather than aggressively compressing — schedule predictability scores higher with TTUS evaluators than the absolute shortest duration.

2. Phase-by-phase durations (matched to 02-technical-approach.md § 3)

Phase	Weeks	Dates	Duration	Critical-path activities	Float days
Phase 1 — Mobilization, protection, coordination	1–2	7/1–7/14	14 cd	Site mob, dust containment, CBORD kickoff, EHS protocol established, ALL long-lead submittals out the door	0 (no slack — Week 1 deliverables drive Phase 5)
Phase 2 — Demolition	3–4	7/15–7/28	14 cd	Strip dressing rooms to demising walls + structure; MEP demo coordinated with subs; hazmat abatement if triggered	2 (light Phase 2 contingency for hazmat finds)

Phase 3 — MEP rough-in	5–8	7/29–8/25	28 cd	HVAC ductwork, plumbing supply/waste/vent rough, electrical branch wiring, CBORD door prep, low-voltage pathway, in-wall inspections	3 (Phase 3 slack for RFI churn)
Phase 4 — In-wall + above-ceiling close-out	9–11	8/26–9/15	21 cd	Framing, blocking, fire-stopping, GWB, ceiling grid set, brick restoration	2
Phase 5 — Finishes	12–14	9/16–10/06	21 cd	Flooring, paint, finish carpentry, millwork install (theater-grade), ACT, door/frame/hardware install	0 (no slack — millwork lead drives this phase)
Phase 6 — MEP trim + fire alarm + specialties	15–16	10/07–10/20	14 cd	Light fixtures, diffusers, plumbing fixtures, devices, lighting controls programming, FA, signage, accessories	3

Phase 7 — TAB + commissioning + punch + owner training + substantial completion	17–18	10/21–11/02	13 cd	TAB report, controls commissioning, owner training, punch walk, substantial completion target 10/20 , then 13 days of float to 11/2	13 (the float bank)
Phase 8 — Close-out	19–22	11/03–11/30	28 cd	Final punch closure, record drawings, O&M, attic stock, final clean, final pay app	n/a (after substantial completion)

Total Phases 1–7: 125 calendar days from 7/1 to 11/3 — one day over the contract date — but the internal target is 10/20, banking 13 days of float against 11/2. Phase 8 close-out is per the warranty / retainage schedule, not the substantial completion clock.

3. Critical path

The critical path runs through three serial dependencies:

Long-lead submittals (Week 1) ■ ▼ Theater-grade millwork manufacture + delivery (10–14 weeks → land by Week 12) ■ ▼ Phase 5 finishes (Weeks 12–14) – millwork install is the last gate before Phase 6 starts ■ ▼ Phase 6 MEP trim (Weeks 15–16) – lighting fixtures depend on millwork being in place (for makeup-mirror LED frames) ■ ▼ Phase 7 TAB + commissioning + punch (Weeks 17–18) ■ ▼ Substantial completion 10/20 internal target → 11/2 contract date with 13 days float

Any slip in Phase 5 finishes by more than 13 calendar days triggers the LD clock. This is why Phase 1 long-lead submittals are non-negotiable in Week 1.

4. Long-lead items (gating activities)

Item	Lead time	Order by	Land by	Risk if slipped
Theater-grade millwork (makeup vanities + LED-lit 24"x72" mirror surrounds per Drawings Addendum 1, costume storage) — PM Sec 06 41 16 + 08 83 00	10–14 weeks	Week 1 (7/8)	Week 12 (9/22)	Phase 5 cannot start; LD-trigger risk
Sargent door hardware — PM Sec 08 71 00 (specified series)	8–14 weeks	Week 1 (7/8)	Week 12 (9/22)	Phase 5 finish/hardware install delayed; substitute Sargent-compatible cylinder via submittal if needed
Theater-grade dimmable LED light fixtures + replacement of corridor fixtures relocated to Makeup Room 108 per Drawings Addendum 2 — PM Sec 26 51 00	6–8 weeks	Week 1 (7/8)	Week 10 (9/8)	Phase 6 MEP trim delayed
HM frames + doors — PM Sec 08 11 13 + 08 14 16	8–10 weeks	Week 1 (7/8)	Week 11 (9/15)	Phase 5 door install delayed

HVAC equipment (specified AHU/VAV + dampers per LEAF Engineers MEP sheets M001–M501) — PM Sec 23 (full division)	8–12 weeks	Week 1 (7/8)	Week 10 (9/8)	Phase 6 HVAC trim delayed; commissioning delayed
Porcelain floor + wall tile (T1 + T2 + T3 + T4 mosaic added per Drawings Addendum 2) — PM Sec 09 30 00	6–8 weeks	Week 2 (7/14)	Week 11 (9/15)	Phase 5 flooring delayed
Metal lockers (contractor scope per PM Sec 10 51 13, contrary to earlier prep assumption)	8–10 weeks	Week 1 (7/8)	Week 12 (9/22)	Phase 5 specialty install delayed
Phenolic-core toilet partitions (ADA-compliant, restrooms 1R9 + 1R10) — PM Sec 10 21 13.19	6–8 weeks	Week 2 (7/14)	Week 11 (9/15)	Phase 6 specialties delayed

Shower receptors + valves (two ADA shower receptors confirmed per Drawings Addendum 2) — PM Sec 22 40 00	6–8 weeks	Week 2 (7/14)	Week 11 (9/15)	Phase 6 plumbing fixture set delayed
CBORD electric strikes + readers (owner-furnished, we accept delivery)	n/a (owner-supplied)	Owner orders	Per owner schedule	Phase 6 cannot finish door install until strikes on site

Submittal turnaround target: 14 calendar days from sub to A/E approval. If A/E response slips past 14 days, we escalate via Samuel Guevara.

5. EHS shutdown windows (require 2 weeks lead time per UGSC Art. 8)

Utility	Required for	Typical duration	Coordination
Fire alarm system	FA device relocation (Phase 6)	4–6 hours	ASU EHS — coordinate test/quiet period
HVAC	New air handler / VAV cutover (Phase 6)	8 hours	ASU EHS — coordinate cutover with Carr EFA building manager; ideally a weekend
Electrical (sub-panel cutover)	Phase 5 final + Phase 6 trim	2–4 hours per circuit	ASU EHS — schedule outside business hours

Water (plumbing tie-in)	Phase 3 rough + Phase 6 fixture trim	2–4 hours	ASU Facilities — usually low-impact since dressing rooms are off main distribution
Sprinkler (FP is owner-furnished but coordinate access)	Phases 2–4	Per owner's FP contractor schedule	Owner's FP contractor — we provide access only

All shutdowns are requested ≥ 2 weeks in advance via written notice to Samuel Guevara per the UGSC Article 8 procedure. Shutdowns are batched where possible to minimize disruption to the active building.

6. Owner-furnished handoff schedule (the "demarcation in time" complement to the demarcation in space)

Owner-furnished scope	Required from owner	When (week)	What we deliver
Owner's FP contractor on-site coordination	Sprinkler-head relocation per new ceiling grid	Phase 4 (Week 10)	Open ceiling, clean access, electrical lockout
CBORD device + programming schedule	Devices on site for install	Phase 6 (Week 16)	Door prep complete, low-voltage pathway terminated at reader, 120V/PoE pathway ready
ASU IT data cabling pulls	Cable + termination + jacks	Phase 6 (Week 16, after Phase 5 finishes close out)	Pathway open + ring & string + faceplate ready
ASU AV equipment install	AV equipment on site	Phase 6 → Phase 7 transition	Power + pathway in place, mounting blocking installed
ASU FF&E delivery	Furniture, costume racks, lockers if applicable	Post-substantial-completion (Week 19+)	Spaces clean, punch closed, ready for FF&E install

These handoffs are tracked in the project's submittal/RFI log alongside our own deliverables.

7. Float strategy

Internal target substantial completion 2026-10-20 banks 13 calendar days of float against the contract date of 2026-11-02 and the \$250/day LD trigger. The float is intended for:

1. **Hazmat surprises in Phase 2** if ASU EHS survey is unfavorable (consume 2–5 days of float).
2. **Differing site conditions** discovered during demo or MEP rough-in — undersized existing electrical service, cast-iron DWV requiring transition fittings, surprise plenum obstructions (consume 2–5 days of float per finding).
3. **A/E RFI response delay** beyond 14 days (consume 1–2 days per delayed response).
4. **Long-lead item slip** beyond stated manufacturer lead time (consume 5–10 days if a long-lead lands 1 week late).
5. **Active-building access window narrowing** if Carr EFA's production schedule absorbs more daytime hours than assumed (consume after-hours premium labor, not float days, where possible).

If the 13-day float is exhausted by mid-Phase 5 (around 10/01), we escalate to Samuel Guevara via the UGSC Article 9 change-order procedure for a no-cost time extension. We do NOT silently absorb schedule slip into the LD-trigger window.

8. Schedule risk callouts (cross-reference to `../07-risk-register.md`)

Risk	Schedule impact	Mitigation reflected in this schedule
R-02 — owner-furnished scope mis-priced	None on schedule if scope is correct; major on schedule if a scope item slips between owner and us at the wrong moment	Demarcation table reviewed at kickoff (Week 1); coordination POCs named in <code>03-project-team.md</code> § 4
R-03 — existing-conditions surprises (hazmat, undersized MEP)	Up to 5 days per finding	Phase 2 has 2 days of slack; float bank has 13 days
R-06 — CBORD coordination friction	Up to 3 days at Phase 6 door install	CBORD kickoff in Week 1
R-08 — Carr EFA active-building access	Up to 1 day/week of lost productive time during fall semester	After-hours premium labor budgeted in pricing; production calendar confirmed by Week 1

R-09 — schedule slip past 11/2	LD clock; \$250/day	Internal target 10/20 with 13 days float
R-10 — fixed-date vs days-from-NTP substantial completion	If NTP slips, the LD clock still starts on 11/2	Assumptions & Clarifications in 02-technical-approach.md § 7 ties substantial completion to receiving NTP by 7/1
R-12 — drawing-set thinness → RFI churn	1–2 days per RFI delay beyond 14 days	RFI cadence in submittal log; 14-day target with escalation procedure
R-16 — Sargent lock supply chain	Up to 4 weeks if Sargent has supply constraints	Order Week 1; substitute Sargent-compatible cylinder series via submittal if needed
R-17 — theater-grade millwork lead	Up to 4 weeks if specialty manufacturer slips	Order Week 1; identify alternative manufacturers in submittal package; carry expedite fee in GCs

9. Schedule deliverables with the proposal

Submitted with the proposal as separate exhibits:

1. **CPM Gantt** showing 124-day window with the 7 construction phases + Phase 8 close-out, critical path highlighted, long-lead items shown as separate procurement bars
2. **Long-lead item schedule** with order dates + manufacturer lead times + landing dates + critical-path impact
3. **EHS shutdown window plan** with the 5 shutdown types + required notice + estimated duration

Submitted post-award as a contract submittal:

4. **Baseline CPM schedule** per UGSC Article 8 — fully resource-loaded, fully cost-loaded, updated monthly

SECTION 06

06

Quality control plan — Carr EFA Dressing Room Renovation

Quality control plan — Carr EFA Dressing Room Renovation

Submitted with the proposal as a separate exhibit (or appended to the technical narrative). Tied to UGSC Article 7 (Submittals + Construction Quality Control) and Article 11 (Project Closeout). The plan is project-specific to Carr EFA; it is not a boilerplate corporate QC manual.

1. QC organizational responsibility

Role	QC accountability
Project Manager (_____)	Owns the QC plan; ensures 3-phase inspection happens at each milestone; chairs the weekly QC meeting; submits the monthly QC report with each pay app per UGSC Art. 10
Superintendent (_____)	Conducts the 3-phase inspections in the field; logs deficiencies; verifies sub-installed work against approved submittals before turning over to next trade
Project Engineer (_____)	Maintains the submittal log + RFI log + deficiency log; submits weekly QC summary to PM
Subcontractor foremen	First-line QC at the trade level; participate in 3-phase inspections of their own work
A/E (_____)	Reviews and approves submittals; participates in milestone inspections; approves substantial completion punch list
Owner's representative (Samuel Guevara, ASU FP&C)	Participates in major milestone inspections; receives monthly QC report; signs off on substantial completion

2. The 3-phase inspection method

Adapted from the USACE Quality Control standard to align with UGSC Article 7 expectations. Applied to every "definable feature of work" (DFOW) — i.e. each trade scope on each room. The DFOW list is in the project QC binder, derived from the schedule of values + finish schedule + door schedule.

Preparatory phase (before work begins on a DFW)

Checklist (per DFW):

- ☐ Approved submittals on file (no work begins without approved submittal)
- ☐ Materials on site, inspected for damage, matches approved submittal
- ☐ Predecessor work complete and accepted (e.g. framing complete before drywall starts)
- ☐ Tools, equipment, and crew identified and competent for the work
- ☐ Safety review of the DFW's hazards (active-building consideration — see [07-safety-plan.md](#))
- ☐ Code/spec/drawing references identified; sub foreman has read the spec section
- ☐ Mock-up or sample required? If yes, mock-up complete and approved
- ☐ Coordination with adjacent trades / owner-furnished items confirmed (see [02-technical-approach.md](#) § 2)

Initial phase (when work first starts on a DFW)

Within 1 working day of starting the DFW, inspect:

- ☐ Layout / setup matches drawings (square, level, plumb where applicable)
- ☐ First-piece installation matches approved submittal and approved mock-up
- ☐ Workmanship matches industry standard for the trade
- ☐ Documentation: photographs of first-piece installation logged in the QC binder
- ☐ If non-conforming: stop work, correct first piece, document correction before proceeding

Follow-up phase (during ongoing work and at completion of the DFW)

- ☐ Daily / weekly visual inspection while the DFW is in progress
- ☐ At DFW completion, walk the entire scope with the sub foreman + superintendent
- ☐ Final inspection documented in the QC log with photographs
- ☐ Sub formally turns DFW over to the next trade (next-trade signs accepting the predecessor work — protects all parties on coordination errors)
- ☐ All deficiencies entered into the deficiency log with target close date

3. Submittal management (per UGSC Article 7)

Submittal log

Maintained electronically and shared with Samuel Guevara + A/E weekly. Each row:

- Submittal number
- Spec section reference
- Submittal description
- Date submitted by sub to us
- Date submitted by us to A/E
- A/E review status (approved, approved as noted, revise and resubmit, rejected)
- Date A/E returned to us
- Date we returned to sub
- Number of review cycles
- Critical-path linkage (yes/no)

Submittal targets

- **Long-lead submittals** (millwork, hardware, HVAC equipment, lighting fixtures, HM frames) — submitted in Week 1 of construction. See 05-schedule-narrative.md § 4.
- **Standard submittals** — submitted no later than 30 calendar days before the related work begins.
- **Sample / mock-up submittals** — paint colors, flooring samples, millwork finish samples — submitted ≥ 45 days before installation to allow mock-up + approval cycles.
- **A/E review target turnaround** — 14 calendar days. Escalate to Samuel if A/E response slips past 14 days.

Critical submittals for Carr EFA

#	Submittal	Spec section	Critical-path	Notes
1	Theater-grade millwork (vanities + LED mirror surrounds)	06 41 00	Yes	10–14 wk lead; cannot start Phase 5 without

2	Sargent cylindrical hardware schedule	08 71 00	Yes	Sargent specified by name; submit keying schedule coordinated with CBORD admin
3	Hollow metal frames	08 11 13	Yes	8–10 wk lead
4	Theater-grade dimmable LED light fixtures	26 51 00	Yes	6–8 wk lead
5	HVAC equipment	23 00 00	Yes	8–12 wk lead
6	Plumbing fixtures (ADA-compliant)	22 40 00	No	4–6 wk
7	Sheet vinyl + LVT flooring samples + mock-up	09 65 00 / 09 65 19	No	Mock-up required pre-install
8	Paint colors + sheen confirmation	09 91 23	No	Mock-up panel required
9	ADA signage type + Braille verification	10 14 00	No	Sample required
10	TAB agency qualifications	23 05 93	No	Submit early; agency selected pre-NTP

11	Acoustical ceiling tile + grid	09 51 13	No	3–4 wk lead
12	Low-voltage pathway plan (for CBORD coordination)	27 05 00	Yes (for CBORD coordination)	Submitted Week 1
13	Brick wall restoration mock-up	04 03 00	No	Mock-up panel before production work
14	Schedule of values	per UGSC	n/a	Submitted with first pay app per UGSC Art. 10
15	Site-specific safety plan	per UGSC	n/a	Already in 07-safety-plan.md

4. Material testing + inspection (per UGSC Art. 7 + Article 9)

Test / inspection	Frequency	Responsible	Notes
In-wall rough-in (framing, electrical, plumbing, fire-stopping)	Before drywall hung	AHJ + Superintendent	Per IBC and IFC
Sprinkler-head locations (in coord with owner's FP contractor)	At ceiling grid set	Owner's FP contractor + Superintendent	Coordination — not our QC scope
TAB report	Before substantial completion	Independent agency (subcontracted; _____)	UGSC Art. 7 requirement

Commissioning of HVAC controls + lighting controls	Phase 7	Controls vendor + Cx agent if owner provides	Coordinate with ASU BMS team
Air quality / IAQ testing post-construction	Before owner occupancy (if specified)	Independent agency	Confirm requirement against spec
Hazardous-materials abatement air clearance	Post-abatement (if abatement is triggered)	Licensed abatement consultant (separate from abatement sub)	Required by TX DSHS

5. Deficiency log + non-conformance

A deficiency log is maintained from Day 1 of construction. Each deficiency captures:

- Date discovered
- Location (room + grid coordinates)
- Description with photograph
- Sub responsible
- Reference (drawing # + spec section + submittal #)
- Corrective action assigned
- Target close date (typically within 5 working days)
- Verified-closed date

Recurring deficiencies (same sub, same issue twice) trigger a sub-level corrective-action meeting with the sub's project manager. Three recurrences trigger a sub-level performance review with the firm's PM and the sub's principal.

6. Daily QC documentation

- **Daily log** — superintendent's daily report including crews on site, work performed, deliveries, inspections, weather, visitors, RFIs/changes, safety incidents
- **Photographic log** — minimum 5 photos/day of progress, plus all milestone photos, all deficiencies, and all owner-furnished interface points
- **Materials log** — every material delivery logged with date, sub, item, condition, storage location
- **Tool / equipment log** — for major equipment (scaffold, lifts, generators)

All logs maintained in the project QC binder, with electronic backup pushed to the firm's project management system daily. Owner has access to summary reports through Samuel Guevara on request.

7. Punch list management (Phase 7 and Phase 8)

Pre-punch inspection (internal, Week 17)

Conducted by the PM + superintendent + each sub. Identifies ALL deficiencies before the official punch walk with the owner and A/E. The pre-punch list is closed (or items assigned with target dates) BEFORE the official punch walk begins. This separates the internal QC closure from the owner-facing punch, which scores far better with TTUS evaluators.

Official punch walk (Week 17–18 transition)

- Walk attendees: Samuel Guevara (or designee), A/E representative, our PM, our superintendent, key subs
- Punch list compiled on the walk; each item assigned to a responsible party with target close date (typically 14 calendar days from walk)
- Items that materially affect occupancy or substantial completion criteria are corrected before substantial completion is requested
- Items that do not materially affect substantial completion may be deferred to the post-substantial-completion punch closure period (typically 30–60 days)

Substantial completion criteria (per UGSC Art. 11)

A formal Request for Substantial Completion is submitted to Samuel when: - All systems are operational and tested - All life-safety systems are commissioned (FA, egress lighting, emergency lighting) - TAB report submitted and accepted - Punch list issued and major items closed - Building can be safely occupied for its intended use

ASU has the right to occupy the dressing rooms at substantial completion even if a non-material punch list remains open.

Final completion (per UGSC Art. 11)

- All punch items closed and signed off
- All submittals approved and reconciled
- All record drawings delivered
- All O&M manuals delivered
- All attic stock delivered to ASU's designated location
- All warranties delivered (1-year general warranty + manufacturer warranties for HVAC, lighting, plumbing fixtures, finishes)

- Owner training completed and documented
- Final cleaning complete
- All releases of lien from subs delivered
- Final pay application submitted

8. Owner training (per UGSC Art. 7)

System	Audience	Duration	Documentation
HVAC controls + integration with ASU BMS	ASU Facilities mechanical staff	2 hours	Recorded session + O&M manual reference
Lighting controls (dimming, occupancy, manual override)	ASU Facilities electrical staff + Carr EFA building manager	1 hour	Recorded session + O&M manual reference
Plumbing fixtures (sensor faucets if installed, mixing valves, shut-offs)	ASU Facilities plumbing staff	1 hour	O&M manual reference
Door hardware + Sargent keying + CBORD coordination	ASU Facilities + CBORD admin	1 hour	Keying schedule + maintenance manual
Finish maintenance (sheet vinyl, paint touch-up, ACT)	ASU Facilities + Carr EFA building manager	30 minutes	Maintenance manual with manufacturer cleaning instructions

Owner training scheduled in Phase 7 (Week 17). Recordings kept on file by ASU FP&C per UGSC Art. 11.

9. Record drawings + O&M manuals (per UGSC Art. 11)

Record drawings

- Format: CAD (latest AutoCAD .dwg) + PDF
- Content: full set of drawings with all as-built revisions marked clearly

- Source: superintendent's red-line master maintained throughout construction
- Delivery: electronic + 2 hard copies to ASU FP&C at final completion

O&M manuals

- Format: PDF + 3 hard copies
- Content: divided by CSI division, with each section containing:
- Manufacturer spec sheets
- Operating instructions
- Maintenance schedule
- Warranty information
- Replacement part schedule (with sourcing information)
- Recommended attic stock
- Delivery: at final completion; reviewed and accepted by ASU Facilities before final retainage release

10. Warranty tracking (1-year general + manufacturer-specific)

- 1-year general warranty from substantial completion per UGSC Art. 12
- Warranty call-back log maintained by the PM for the full warranty period
- Warranty walks scheduled at 30 days, 90 days, 6 months, and 11 months post-substantial-completion (the 11-month walk surfaces any latent issues before warranty expiration)
- Manufacturer-specific warranties pass through to ASU (HVAC 5–10 yr, lighting 5 yr, finishes per spec, plumbing fixtures per manufacturer)

11. QC reporting cadence

Cadence	Output	To
Daily	Superintendent's daily report	PM, project engineer
Weekly	QC summary (submittals + RFIs + deficiencies + 3-phase inspections completed + milestones reached)	PM, Samuel Guevara, A/E

Monthly	Pay-application QC report (per UGSC Art. 10) including HSP PAR	Samuel Guevara, TTUS HUB Operations
Milestone	3-phase inspection report per DFOW	A/E, Samuel Guevara on request
Substantial completion	Substantial completion package (punch list, TAB report, commissioning report, owner training records)	Samuel Guevara, A/E
Final completion	Final completion package (record drawings, O&M manuals, attic stock log, warranty documentation, final lien releases)	Samuel Guevara, A/E, ASU Facilities

SECTION 07

07

Site-specific safety plan — Carr EFA Dressing Room Renovation

Site-specific safety plan — Carr EFA Dressing Room Renovation

Submitted with the proposal as a separate exhibit (or appended to the technical narrative). Compliant with **29 CFR 1926 (OSHA Construction Industry Standards)** and the firm's corporate safety program. This plan is **project-specific to Carr EFA** — it identifies the hazards unique to renovating dressing rooms in an active performing-arts building on a TX university campus.

1. Safety policy + EMR

Item	Value
Firm's safety policy	
Most recent 3-year EMR (Experience Modification Rate)	
OSHA recordable incident rate (last 3 years)	
OSHA DART rate (last 3 years)	
Active OSHA citations (last 5 years)	
Safety committee chair	
Project Safety Manager	

A low EMR (< 1.0) is the strongest single safety differentiator. If the firm's EMR is below industry average, lead the safety section with the number.

2. Site-specific hazard analysis (the Carr EFA-unique risks)

Standard 29 CFR 1926 hazards (fall protection, electrical, scaffolding, PPE, hazardous chemicals, hot work) are addressed by the firm's corporate safety program and are not re-litigated here. The project-specific hazards below DO require additional planning.

Hazard 1 — Working in an active performing-arts building

Risk: Carr EFA hosts theater, dance, and music productions and classes during portions of the 7/1–11/2 construction window. Faculty, staff, students, and patrons share the building.

Controls:

- Daily safety toolbox includes an "active-building today?" check; high-noise / high-dust work permitted only during confirmed dark-house windows
- Permanent dust containment partitions with negative-air HEPA filtration; daily containment-integrity inspection
- Walk-off mats at every containment transition; HEPA vacuum of debris escape weekly
- Sound-mitigation partitions during any non-silent work that could occur during occupied hours
- Egress routes through and around the dressing-room footprint clearly signed; ASU EHS-approved temporary egress plan posted at each containment door
- Coordination call with the Carr EFA building manager + College of Arts and Humanities calendar contact at kickoff and weekly thereafter

Hazard 2 — Hazardous-materials abatement (lead, asbestos, PCBs)

Risk: Carr EFA is older construction. Asbestos in VCT, floor mastic, pipe insulation, and fireproofing is realistic. Lead in pre-1978 paint layers is realistic.

Controls:

- ASU EHS hazmat survey obtained or coordinated pre-NTP (if not on file, an emergency survey is scheduled in Week 1; see R-03 in `../07-risk-register.md`)
- If positive: licensed TX-DSHS abatement sub mobilized; sub's site-specific abatement plan integrated with our overall safety plan; abatement area sealed with critical barriers + decontamination chamber + air monitoring; ASU EHS notified
- Air clearance testing by an independent agency before re-entry
- Worker exposure monitoring per 29 CFR 1926.1101 (asbestos) / 1926.62 (lead) as applicable
- Waste manifested and disposed at a TCEQ-permitted facility; manifest copies to ASU FP&C

Hazard 3 — Fire-alarm shutdown coordination during demo + MEP work

Risk: Carr EFA's fire-alarm system must be active for occupied portions of the building. Demo and MEP work near devices requires planned shutdowns; uncoordinated work near an active FA device can trigger nuisance alarms (with evacuation impact) or worse, deactivate FA protection during a live event.

Controls:

- 2-week advance notice to ASU EHS for any FA shutdown per UGSC Art. 8
- Fire watch during any active shutdown — minimum 1 hour after work ends

- No work that could activate an FA device (welding, grinding, dusty work) within 10 feet of any active device without prior owner authorization + temporary device protection (per device manufacturer's bagging procedure)
- Daily start-of-shift verification that all FA devices in the work area are properly bagged or de-energized per the agreed plan

Hazard 4 — Electrical lockout/tagout in a live institutional building

Risk: Carr EFA shares electrical service across multiple uses. Lockout/tagout (LOTO) of dressing-room circuits must NOT inadvertently de-energize adjacent active spaces.

Controls:

- LOTO program per 29 CFR 1926.417 + 1910.147; verified breaker IDs against single-line diagram pre-LOTO
- Coordinate any panel-level LOTO with ASU Facilities electrical staff
- All sub-electricians follow our LOTO procedure; we audit weekly
- Sub-panel work scheduled outside business hours where possible
- Temporary power for our work pulled from a dedicated panel; no shared circuits with active loads

Hazard 5 — Dust and indoor air quality for performers and patrons

Risk: Performer health is acutely sensitive to dust and chemical fumes (paints, adhesives, sealers) — they sing and recite in the spaces. Standard institutional IAQ controls are insufficient.

Controls:

- Negative-air HEPA filtration on the dust containment, with daily filter inspection
- Low-VOC paints, adhesives, sealers, and finishes (specified in the finish schedule and in our sub-quotes)
- After-hours work for any high-VOC application (or shift to a different product if available)
- Air quality monitoring during paint and adhesive applications
- Notification to the Carr EFA building manager 48 hours before any work that may produce odor migration

Hazard 6 — Confined-space / above-ceiling work

Risk: Above-ceiling MEP work above an occupied building requires fall-protection planning and protection of occupants below.

Controls:

- Fall protection per 29 CFR 1926.501 for any work at heights >6 feet

- Hard-barrier protection below all above-ceiling work (no work above active corridors during occupancy)
- All scaffolding and ladder use per OSHA standards; daily inspection
- Confined-space evaluation if above-ceiling space is determined to be a permit-required confined space (typical above-ceiling work is non-permit but evaluation is documented)

Hazard 7 — After-hours work

Risk: Significant portions of demo and MEP cutover are after-hours. Reduced lighting, reduced ASU staffing, and fatigue are real factors.

Controls:

- Project-supplied task lighting in all work areas during after-hours operations
- Two-person minimum on site at all times during after-hours work
- Sign-in / sign-out at the campus security office for every after-hours entry
- Maximum 12-hour shifts; fatigue mitigation per the firm's overtime policy
- ASU Security informed of after-hours work and worker identifications
- Emergency contact tree posted at every entrance; ASU EHS on the contact tree

Hazard 8 — Coordination with owner's vendors (FP, AV/IT, FF&E)

Risk: Owner's vendors will be in our work area at various points. Coordination errors lead to safety incidents (one trade's lockout sequence conflicts with another's energization; one trade's hot work conflicts with another's combustible storage).

Controls:

- Owner-vendor pre-work coordination meeting before each owner-vendor enters the work area
- Owner-vendor signs in to our project safety brief on first day
- No simultaneous work by owner's vendor and our crews in the same room without a documented dual-trade safety plan
- ASU EHS coordinates with both us and owner's vendors

3. Training requirements

Training	Who	When
----------	-----	------

OSHA 30	All supervisors (PM, super, foremen, safety manager)	Current within 5 years
OSHA 10	All workers and sub workers on site	Current within 5 years
Project-specific orientation	Every worker (sub or self) on first day	Day 1
Hazcom (chemical-specific)	All workers handling chemicals	At each new chemical introduced
Lockout/tagout	All electrical and mechanical workers	Pre-task
Fall protection (specific to each fall hazard)	All workers exposed to falls	Pre-task
Asbestos / lead awareness	Workers in abatement areas	Per 29 CFR 1926.1101 / .62; if abatement triggered
Fire watch (for hot work)	Designated fire watches	Pre-task
First aid / CPR	At least 2 workers on site at all times	Current within 2 years

4. Safety meetings + reporting

Meeting / report	Frequency	Attendees / recipient
Daily toolbox / pre-task briefing	Daily at shift start	All workers on site, led by foreman
Weekly safety walk	Weekly	Safety manager + super + sub foremen
Weekly safety meeting	Weekly	All foremen + PM + super + safety manager

Monthly safety summary	Monthly with pay app	Samuel Guevara, ASU EHS
Incident report (any recordable or near-miss)	Within 24 hours of incident	PM → Samuel + ASU EHS + firm's safety committee
Quarterly safety audit	Quarterly	Safety manager + firm's safety committee chair

5. PPE policy

Minimum PPE on site for all workers (per 29 CFR 1926.95 and firm policy):

- Hard hat (ANSI Z89.1 Type I Class E)
- Safety glasses (ANSI Z87.1)
- High-visibility vest (Class 2 minimum during after-hours work)
- Steel-toed boots (ASTM F2413)
- Hearing protection in 85 dBA+ areas (continuous monitoring of high-noise work)
- Fall protection harnesses and lanyards when working at heights >6 feet
- Respiratory protection (N95 minimum for dusty work; half-face P100 for abatement-adjacent work; full-face per abatement sub's plan in abatement areas)

Visitor PPE — hard hat, safety glasses, high-vis vest provided at the site entrance.

6. Emergency response

- **Emergency contact tree** posted at every entrance:
- 911 first
- ASU Police Department: 325-942-2071 (24/7)
- ASU Health Services: 325-942-2173
- ASU Facilities Emergency: 325-942-2257
- Samuel Guevara: (469) 213-1838
- Firm's PM: _____
- Firm's Safety Manager: _____
- **Nearest hospital:** Shannon Medical Center, San Angelo — ~3 miles from ASU campus
- **Evacuation plan:** posted at each containment door; routes use Carr EFA's existing egress; assembly point at _____
- **Fire watch:** assigned for all hot work; continues 1 hour after work ends

- **First aid kit:** ANSI Z308.1 Class B on site at all times; one in each work zone

7. Substance abuse policy

8. Hazardous-materials handling

- All chemicals on site logged with SDS available in the site office and in each work zone
- Storage per manufacturer requirements; combustibles segregated from oxidizers; flammables in a vented, labeled cabinet
- Spill kit on site; chemical-specific cleanup procedures per SDS
- Disposal manifested per TCEQ regulations
- TX Right-to-Know training current for all workers handling chemicals

SECTION 09

09

Attachment D fill guide — HUB Subcontracting Plan (HSP) Form

Attachment D fill guide — HUB Subcontracting Plan (HSP) Form

Source:

inbox/opportunities/attachments/2026-05-21/ESBD_516718_1778880887164_Attachment D - HSP....pdf. The v3 extract at exports/calibration_v3/estimate.json bid_packages[11] confirms this is the State of Texas HSP form required with the bid response.

*Strategic background in ../05-hsp-plan.md. This document is the **fill-in operational guide** for the actual TX HSP form.*

Deadline: 2026-06-08, 5:00 PM CST (Monday) — **3 calendar days AFTER the proposal itself.** Failure to submit = automatic rejection of the proposal even if the proposal package was responsive.

1. HSP form structure (TX standard HSP form per 34 TAC §20.285)

The State of Texas HSP form has 4 main sections. Each is filled per the guidance below.

Section	Title	What it covers	Page count typical
1	Respondent information	Firm name, address, contacts, HUB status	1
2	Subcontracting intentions	Per-subcontract: vendor, scope, \$ value, HUB status	Multiple (1 per subcontract)
3	Self-performing justification	What the firm self-performs and why	1
4	Affirmation + GFE documentation	Compliance affirmations + GFE attachments	1 + GFE binder

The form is fillable on the TX Comptroller's website at

<https://comptroller.texas.gov/purchasing/vendor/hub/forms.php> (the "HSP Form" link); use the most recent version (currently the 06/2024 revision per Comptroller's posting). The PDF in Attachment D

is the same form, agency-customized for ASU/TTUS.

2. Section 1 — Respondent information

Block A — Respondent identification

Field	What to enter	Source
Respondent name (legal)	RK Residential Homes and Commercial Constructions, LLC dba Blue Print Constructs	—
Respondent address		—
Telephone		—
Email		—
Federal Tax ID		—
TX Vendor ID (TIN)		—
Solicitation number	26-007	RFCSP cover
Project name	Carr EFA Dressing Room Renovation	RFCSP cover
Agency (issuing entity)	Angelo State University, a member of the Texas Tech University System	RFCSP cover

Block B — Respondent HUB status

Field	What to enter	Source
Is the respondent a TX HUB-certified firm?		TX Comptroller HUB program

If Yes — HUB certification number		TX Comptroller-issued
HUB certification expiration date		TX Comptroller
HUB ownership category		TX Comptroller certification

If the firm is itself HUB-certified, this earns automatic scoring weight. If not, this fills with "No" and the HSP commitment in § 2 carries the HUB-participation story.

Block C — Project value + subcontracting estimate

Field	What to enter	Source
Total project value (the firm's bid)		10-price-proposal.md
Estimated % to be self-performed		
Estimated \$ to be self-performed		
Estimated % to be subcontracted		
Estimated \$ to be subcontracted		
HUB participation goal (project-specific)		RECSP body / Attachment B.2
HUB participation committed (target)	30% of subcontracted \$ = ~\$120K	../05-hsp-plan.md § C

3. Section 2 — Subcontracting intentions (one entry per subcontract)

This is the heart of the HSP. For each planned subcontract, complete the following block:

Per-subcontract block template

Field	What to enter
Subcontract # (sequential)	1, 2, 3, ...
Trade / scope description	E.g. "Selective demolition"
Estimated \$ value	
% of total project value	
Vendor name	
Vendor address	
Vendor phone + email	
Vendor HUB certification number	
HUB certification expiration date	
Vendor TX Tax ID	
Vendor's HUB category	
Subcontract scope summary	Cite the relevant row from ../04-scope-of-work.md § C

Per-trade planned entries (per ../05-hsp-plan.md § C)

Subcontract #	Trade	Estimated \$	Target HUB share
1	Selective demolition (interior + MEP demo)	\$30K–\$45K	75% target

2	Drywall / metal-stud framing	\$15K–\$30K	50% target
3	Masonry / brick restoration (clean, repoint, seal)	\$5K–\$15K	25% target
4	Doors / frames / hardware (Sargent material buy)	\$15K–\$30K	HUB distributor if available
5	Finish carpentry / millwork (theater-grade)	\$40K–\$70K	25% target (HUB rare in specialty)
6	Acoustical ceilings	\$10K–\$15K	50% target
7	Flooring (sheet vinyl + LVT + tile if wet)	\$25K–\$40K	50% target
8	Painting (low-VOC institutional)	\$10K–\$20K	100% target
9	Plumbing	\$35K–\$55K	50% target
10	HVAC (full replacement)	\$60K–\$90K	25% target
11	Electrical (full replacement + theater-grade lighting)	\$60K–\$90K	50% target
12	Low-voltage pathway	\$5K–\$10K	50% target
13	Hazmat abatement (if EHS survey triggers)	\$0–\$20K	25% target
14	Specialties / signage / accessories	\$5K–\$10K	HUB material distributor

For each subcontract entry, ONE of:

- **(a)** A HUB-certified sub has bid and is selected → fill in the HUB cert number + scope + dollar value
- **(b)** A non-HUB sub has bid and is selected → fill in the entry; in the GFE binder document why no HUB sub was selected (price differential >5%, schedule incompatibility, qualifications gap, bonding gap)
- **(c)** Bidding is ongoing → mark "Pending" and provide best estimate; revise post-award if needed

■■ **DO NOT populate Section 2 with HUB sub names without having actually contacted them.** That is HSP fraud and a debar-from-state-work event. The per-trade plan in `.../05-hsp-plan.md` § C is the **planning target**; Section 2 entries reflect **actual sub commitments** as of 2026-06-08.

4. Section 3 — Self-performing justification

The form has a free-text block (typically 1 page) for justifying any work the firm intends to self-perform. Draft text:

SELF-PERFORMING JUSTIFICATION Blue Print Constructs intends to self-perform the following scopes of work on the Carr EFA Dressing Room Renovation, with the justification stated for each: 1. Project management, supervision, and general conditions (Div 01) Estimated value: \$60,000 (12% of contract) Justification: In-house project management and superintendence are the firm's core capability. Direct accountability for schedule, cost control, and quality control to ASU FP&C requires our personnel to lead day-to-day field operations. Subcontracting project management would dilute accountability and increase coordination overhead to the detriment of project outcomes. 2. Field engineering, layout, submittal management, and RFI coordination (Div 01) Estimated value: \$15,000 (3% of contract) Justification: Integral to project management; not commercially available as a stand-alone subcontracted service for a project of this size. 3. Project closeout activities – punch list management, record drawings assembly, O&M manual compilation, owner training coordination, attic stock distribution Estimated value: \$10,000 (2% of contract) Justification: In-house close-out specialist is faster and more accurate than subbing; close-out quality directly affects final retainage release and warranty period customer satisfaction. Total self-performed: ~\$85,000 (~17% of contract value) The remaining ~83% of the contract value, approximately \$400,000, is subcontracted across the trades listed in Section 2 above. The HUB participation goal of 30% of subcontracted dollars (~\$120,000) is calculated against the subcontracted \$400,000 base, not the \$485,000 total contract value, in accordance with 34 TAC §20.285 and TTUS HSP practice.

5. Section 4 — Affirmation + GFE documentation

Block A — Affirmation (sign each)

The form has typically 3–5 affirmations the officer signs:

Affirmation	What it confirms
HSP completeness	The HSP is complete and accurate to the best of the respondent's knowledge
Good-faith effort	The respondent has made a good-faith effort to subcontract to HUB-certified firms
Revised HSP commitment	If subcontracting scope changes post-award, the respondent will submit a revised HSP to TTUS HUB Operations for approval before engaging the new sub
Reporting commitment	The respondent will file monthly Progress Assessment Reports (PARs) with each pay application post-award
Documentation retention	The respondent will retain all HSP-related documentation (vendor outreach, sub-quotes, GFE binder) for the contract retention period

Block B — GFE documentation (the make-or-break)

For every trade where the HUB allocation is light or where no HUB sub was selected, the GFE binder includes:

Dated HUB outreach records — ≥3 HUB subs solicited per trade, with method (email, fax, certified mail), date, recipient, and outcome (response received / no response). Per [../05-hsp-plan.md](#) § D, use the CMBL search starting points to identify candidate HUB subs.

Advertisement records — Ad placement in ≥2 TX HUB publications: - TX Comptroller's HUB News (<https://comptroller.texas.gov/purchasing/vendor/hub/news.php>) - Texas Construction News OR Hispanic Contractors Association of TX bid list OR NAWIC TX Chapter OR Greater San Antonio Black Chamber of Commerce publication Each ad copy + placement confirmation in the binder.

Response log — One row per HUB outreach with: date sent, sub name, contact, method, response, bid amount (if any), outcome (selected / not selected / no response).

Non-selection reasons — For each HUB sub that bid but was not selected, a written explanation: price differential >5%, schedule incompatibility, qualifications gap, bonding gap, or other documented reason.

Trade-specific GFE narrative — For each trade with light HUB allocation (masonry, theater-grade millwork, HVAC, hazmat per ../05-hsp-plan.md § C), a 1-paragraph narrative explaining why the HUB share is limited. Examples:

*"**Masonry / brick restoration:** Specialty masonry subcontractors for brick restoration (clean, repoint, seal) in west Texas are limited; HUB-certified specialty masonry firms in the San Angelo / Abilene / Midland radius are even thinner. We solicited 3 HUB-certified masonry firms (_____); 1 responded with a bid 18% above the non-HUB market quote and 2 did not respond. We selected the non-HUB sub based on the >5% price differential rule."*

HUB outreach event attendance records — If the firm attended any TTUS HUB Operations or TX Comptroller HUB outreach events, attach attendance records.

HSP outreach packet template — A copy of the template email/letter used in the HUB outreach (the template is in ../contacts.md Draft #3).

6. Cross-reference to outreach files

The HUB outreach emails to actually send are in ../outreach/05-email-hub-sub-template.md. Once HUB subs are identified per ../05-hsp-plan.md § D, the template is customized per trade and sent. Each send is logged in the GFE binder.

local/hub-outreach-log.csv (gitignored per bids/*/local/) is the working log; the GFE binder is the finalized printed/bound version delivered with the HSP submission.

7. Submission procedure

Where to deliver

_____ — TTUS member institutions sometimes split HSP delivery from proposal delivery. Possible locations:

- **ASU FP&C** (same as proposal) — most likely
- **TTUS HUB Operations** (Lubbock — TTU main campus) — less likely for an ASU project but possible per TTUS centralization pattern

How to deliver

- Sealed envelope, separate from the proposal envelope

- Exterior labeling: HSP – Carr EFA Dressing Room Renovation Solicitation 26-007 Due: 2026-06-08, 5:00 PM CST From: RK Residential Homes and Commercial Constructions, LLC dba Blue Print Constructs
- Hand-deliver preferred; if courier, schedule for Saturday 6/6 or Monday 6/8 AM delivery with signature required
- Arrive ≥30 minutes before 5:00 PM CST deadline on Monday
- Obtain dated/timestamped receipt

What goes in the envelope

1. **Completed HSP form** (all 4 sections, signed in blue ink by an officer)
2. **GFE binder** — tabbed by trade, with: - Tab A: GFE outreach log (master CSV → printed table) - Tab B: HUB sub outreach records (email/fax/letter copies + delivery confirmations) - Tab C: Advertisement records (ad copies + placement confirmations from ≥2 publications) - Tab D: Response log (table) - Tab E: Non-selection rationale (one entry per non-selected HUB bid) - Tab F: Trade-specific GFE narratives - Tab G: Outreach packet template + per-trade scope narratives sent - Tab H: HUB cert verifications (CMBL search printouts dated within 7 days of submission)
3. **Acknowledgement of revised-HSP requirement** — signed by an officer
4. **Sample / blank revised-HSP form** — to indicate awareness of post-award compliance

8. QC pass on the HSP package

On 2026-06-03 (Wednesday — per `../timeline.md`), the HSP undergoes a **separate** QC pass by a 2nd-set-of-eyes reviewer who has not prepared the HSP. Per `../05-hsp-plan.md` § G, target the final HSP print run for **COB Friday 2026-06-05** (same day as proposal submission) to avoid a Monday-AM scramble.

18-point HSP QC checklist

- ☐ Respondent legal name matches Attachment A exactly
- ☐ FEIN matches Attachment A and W-9
- ☐ All Section 1 blocks filled
- ☐ Section 2 has one entry per planned subcontract
- ☐ Each Section 2 HUB entry has a current (un-expired) HUB cert number, verified on CMBL search within 7 days of submission
- ☐ Section 3 self-performing justification narrative complete and signed
- ☐ HSP commitment % is at or above the project-specific HUB goal (default 30%)
- ☐ Section 4 affirmations all signed in blue ink

- ☐ GFE binder is complete: ≥ 3 HUB outreach attempts per trade, dated, with method
- ☐ At least 2 HUB publications have ad placements documented
- ☐ Every non-selected HUB bid has a written non-selection rationale
- ☐ Trade-specific GFE narratives present for every trade with light HUB allocation
- ☐ Acknowledgement of revised-HSP signed
- ☐ HSP form signed by an officer with binding authority
- ☐ No white-out, no manual corrections
- ☐ Sealed envelope with correct exterior labeling
- ☐ Delivery location confirmed with Samuel
- ☐ Calendar block for hand delivery on 2026-06-08

SECTION 10

10

Price proposal — Carr EFA Dressing Room Renovation (2026-05-23 refresh)

Price proposal — Carr EFA Dressing Room Renovation (2026-05-23 refresh)

Documents the price-build for the bid: subtotal stack, contingency/OH/profit overlay, the separately-carried \$25K cash/contingency allowance, the unit-price grid (formulas only — values come from final takeoff), and the line-item breakdown by CSI division.

Refresh basis (2026-05-23): Project area verified at **3,115 SF** per drawing sheet AF100 (vs. earlier prep-doc assumption of ~2,500 SF — 25% larger). Contingency dropped from 8% to 7% reflecting drawing + PM in hand. Owner-furnished demarcation tightened: lockers are CONTRACTOR scope (PM Sec 10 51 13), Division 21 Fire Suppression IS owner-furnished (PM TOC marks Div 21 "NOT USED"). Working bid envelope refined from \$425K–\$560K mid \$485K to **\$465K–\$575K mid \$520K** per ../price-references.md § A.

A. Pricing framework (matches ../takeoff-template.json _meta)

Parameter	Value	Notes
Region multiplier	1.0	Tom Green County / San Angelo typically clears at 0.88–0.93 of national; using 1.0 as a conservative ceiling until RSMeans City Cost Index lookup confirms. Tom Green County prevailing wage is the labor floor per ../prevailing-wages.md (confirmed operative WD per PM Sec 00 73 46).
Contingency	7%	Reduced from 8% now that drawings + PM are in hand. Could drop to 6% post-site walk; bump to 10% if Section 00 31 00 hazmat survey (currently missing from PM) reveals issues.
Overhead	10%	Standard TX state institutional rate

Profit	6%	Mid-range for TX state institutional work; drop to 5% if pricing competitiveness is the differentiator vs. the 5 confirmed competitor firms (TPI Construction, Lee Lewis Construction, Crockett Facilities Services, San Angelo-based GCs), raise to 7% if a strong past-performance / HSP narrative gives margin headroom
Cash/contingency allowance	\$25,000.00	Per Attachment A — SEPARATE line; NOT rolled into base; NOT marked up
Bid bond cost	1.0–1.5% of bid	Included in markup or carried separately per bonding-agent quote (outreach/03-email-bonding-agent.md)
P&P bond cost	1.0–1.5% of bid	Included in markup
Insurance load	~1.0% of bid	Standard TX broker quote per UGSC Art. 5
Project area	3,115 SF total	Verified per AF100; back-of-house 1,047 SF (heavy reno @ \$350–\$420/SF) + circulation/entry 2,068 SF (light reno @ \$50–\$95/SF) per ../price-references.md § A

B. Total proposal stack (the formulas)

Direct cost subtotal = SUM(line items in C below) [from takeoff] Contingency = Direct cost × 7% [computed] Subtotal with contingency = Direct cost + Contingency [sum]
 Overhead = Subtotal with contingency × 10% [computed] Profit = Subtotal with contingency × 6% [computed] Bid subtotal = Subtotal with contingency + Overhead + Profit [sum] Bond

```
+ insurance load (~2.5%) = Bid subtotal × 2.5% [computed]
BASE PROPOSAL PRICE = Bid subtotal + Bond + insurance load [→ Attachment A § 2a]
Cash/contingency allowance = $25,000.00 [→ Attachment A § 2b – fixed by owner]
TOTAL PROPOSAL = BASE PROPOSAL PRICE + $25,000 [→ Attachment A § 2c]
```

Working envelope (refined 2026-05-23): \$465K – \$575K per ../price-references.md § A using verified 3,115 SF and split-zone \$/SF. Midpoint **~\$520K** is ~\$35K above the implied \$500K published budget — this reflects the 25%-larger-than-assumed area but is still well within typical TTUS contingency-aware budget ranges. **Base proposal alone should land in \$440K–\$550K (midpoint ~\$495K)** with the \$25K allowance brought separately to the \$465K–\$575K all-in.

Bid-positioning advice (per ../price-references.md § B refresh): Submit at **mid-low to mid** (~\$485K–\$505K base) to be competitive against TPI / Lee Lewis / Crockett (who likely target \$475K–\$515K), but not below \$470K base — anything below that signals scope misread on the 3,115 SF.

C. Direct cost breakdown by CSI division (formulas, not values)

Each row pulls from ../takeoff-template.json once quantities are filled. Formulas are SUM-of-line-items within each division. _____ is the placeholder for each numeric value.

	Di Title	Direct cost	% Source of subtotal
01	General Requirements (PM + super + temp facilities + close-out)	_____	12% ../takeoff-template.json line items div 01
02	Existing Conditions / Selective Demolition (finishes + MEP demo + hazmat allowance if any)	_____	6–10% 02
04	Masonry (brick restoration — clean, repoint, seal)	_____	1- div 04

06	Wood / Plastics / Composites (carpentry + blocking + finish carpentry + theater millwork)		8-14% 06
08	Openings (doors, HM frames, Sargent hardware, CBORD prep)		4- div 08
09	Finishes (framing, GWB, ACT, flooring, base, paint)		14-22% 09
10	Specialties (signage, toilet accessories, fire extinguishers)		1- div 10
21	Fire Suppression	\$0	0% OWNER-FURNISHED — PM TOC marks Div 21 "NOT USED" — DO NOT PRICE
10 51 13	Metal Lockers		1- CONTRACTOR scope per PM Sec 10 51 13 (corrected from earlier prep-doc assumption that this was owner-furnished)
22	Plumbing (fixtures + rough-in + showers if applicable)		8-14% 22
23	HVAC (full system replacement + exhaust + TAB + controls)		14- div 23
26	Electrical (full replacement + theater-grade lighting + controls + sub-panel if needed)		14-22% 26

27	Communications (low-voltage pathway only — CABLE is owner-furnished)		1- div 27
28	Electronic Safety / Security (FA device relocation — CBORD devices are owner-furnished)		1-20% div 28
	Direct cost subtotal		~1 sum
	Contingency (8%)		computed
	Subtotal with contingency		sum
	Overhead (10%)		computed
	Profit (6%)		computed
	Bid subtotal		sum
	Bond + insurance (~2.5%)		computed
	BASE PROPOSAL PRICE		sum
	Cash/contingency allowance (Attachment A)	\$25,000.00	fixed
	TOTAL PROPOSAL		sum

■ Sales tax is **NOT** included in any line. ASU is sales-tax-exempt per Attachment E (TX Form 01-339). Subcontractors and material suppliers invoice without TX sales tax for items incorporated into the work.

D. Unit prices (formulas — values come from final takeoff)

Per Attachment A's standard unit-price grid, the bid carries unit prices for owner-directed change items. These set the ceiling for change-order pricing during construction — bid at full retail (sub cost + full GC

markup), NOT shaved.

[VERIFY ON PDF: confirm exactly which unit prices the Attachment A grid requests]. The list below is the typical TTUS pattern; replace with the actual grid contents on the form once confirmed.

#	Item	Unit	Add price	Deduct price
1	Additional/deduct dressing-room SF (full reno including finishes + MEP)	SF		
2	Additional door + HM frame + Sargent cylindrical lockset + CBORD prep	EA		
3	Additional 20A receptacle (dedicated circuit + device)	EA		
4	Additional dimmable LED fixture (theater-grade)	EA		
5	Additional ADA lavatory + plumbing rough-in	EA		
6	Additional ADA water closet + plumbing rough-in	EA		

7	Additional makeup-mirror surround with LED frame (millwork)	EA		
8	Additional SF of acoustical ceiling tile (grid + tile)	SF		
9	Additional SF of sheet vinyl flooring (heat-welded)	SF		
10	Additional SF of paint (2 coats institutional)	SF		
11	Hazmat abatement (VCT + mastic per SF if found)	SF		n/a (deduct n/a — abatement is presence-triggered)

Unit-price computation pattern

For each unit price, the formula is:

Add unit price = (sub bare cost × 1.10 sub OH/profit) × 1.08 contingency × 1.10 GC overhead × 1.06 GC profit × 1.025 bond + insurance = sub cost × ~1.357 effective markup

For deduct unit prices, deduct at the same sub bare cost without the markup stack — the markup is already in the base lump-sum.

E. Allowance handling — the \$25K cash/contingency

Per Attachment A and ../04-scope-of-work.md § D-8:

- **Separate line on Attachment A.** Do NOT include in the base proposal price.
- **NOT marked up.** Bid this line at exactly \$25,000.00.

- **Allowance consumption mechanism (post-award).** Allowance is drawn against during construction via Pending Change Order (PCO) procedure per UGSC Art. 9. Each draw requires Samuel Guevara's written authorization. Common consumption scenarios:
- Differing site conditions (e.g. surprise asbestos requires abatement; surprise undersized electrical service requires sub-panel upgrade): allowance preferred to a change order because no contract-sum increase required
- Owner-directed minor scope additions (e.g. add 1 outlet at a position the owner identifies post-NTP)
- Late-stage A/E clarification that adds work below the change-threshold value
- **What allowance is NOT for.** Owner-directed major scope changes get a normal change order (Article 9), not the allowance. Allowance is for unforeseen scope, not directed scope.
- **Reconciliation at substantial completion.** Any unconsumed allowance is returned to ASU as a deduct via final change order. The firm does NOT retain unspent allowance.

F. Markup discipline (per ../06-evaluation-strategy.md § D)

- **Sub cost at face value** — no shaving sub quotes to make the headline number. If a sub bids \$35K, \$35K goes in the base.
- **General conditions priced from the 124-day window** at the firm's in-house rate, not at a "win the bid" reduced rate.
- **Bond + insurance load** — ~1.5% bond + ~1.0% insurance combined = ~2.5% on a sub-\$1M TX state job.
- **Contingency 8%** — driven by the 4 risks listed in ../takeoff-template.json _meta.contingency_pct_note. Bump to 12% if drawings prove thin OR site walk surfaces existing-conditions surprises.
- **Overhead 10%** standard.
- **Profit 6%** mid-range for TX state institutional.
- **Don't over-shave.** TTUS rejects bids >25% below median as "non-responsible." The \$500K published budget is a strong signal of median; landing at \$425K–\$485K is competitive without flagging non-responsibility.

G. Sensitivity analysis (what if scope is different)

Run these scenarios against the final takeoff (per ../price-references.md § E):

Scenario	SF	MEP scope	Base proposal	Total (with \$25K)	Notes
----------	----	-----------	---------------	--------------------	-------

A — Light reno	2,000	finishes + light MEP	~\$275K	~\$300K	Below \$500K budget — owner has discretion for additional scope
B — Mid reno (most likely)	2,500	full MEP replacement	~\$460K	~\$485K	Matches published \$500K budget
C — Heavy reno (upper bound)	3,000	full MEP + showers + theater-grade millwork	~\$655K	~\$680K	Exceeds \$500K budget — surface to user immediately if drawings indicate Scenario C

Once drawings land, run the takeoff against each scenario. If Scenario C is the drawn scope at \$500K budget, surface to user + Samuel immediately for a budget conversation BEFORE the proposal goes in.

H. Pricing QC checklist (2026-06-02 internal pricing review meeting)

- ☐ All `../takeoff-template.json` line items have quantities filled from drawings (or marked \$0 if owner-furnished — verify against the demarcation table)
- ☐ All sub quotes received and reconciled against the takeoff — no orphaned scope items, no double-bid items
- ☐ Owner-furnished items (FP, AV cabling, FF&E, CBORD devices) confirmed at \$0
- ☐ Hazmat allowance reconciled with ASU EHS survey result (or carry default \$10K–\$25K with assumption documented)
- ☐ After-hours premium labor (~25% of demo + MEP cutover hours) priced at the appropriate burden factor
- ☐ Long-lead items priced at the supplier's confirmed quote (theater millwork, Sargent hardware, HVAC equipment)
- ☐ Bond + insurance load matches the bonding-agent + broker quotes

- ☐ Contingency 8% applied to direct cost subtotal
- ☐ OH 10% applied to direct + contingency
- ☐ Profit 6% applied to direct + contingency
- ☐ Bond + insurance 2.5% applied to bid subtotal
- ☐ \$25K allowance kept SEPARATE from base
- ☐ Sales tax NOT included in any line
- ☐ Unit prices computed at full retail (sub cost + full markup stack)
- ☐ Total proposal lands in \$425K–\$560K envelope (or surface deviation to user)
- ☐ Total proposal is NOT more than 25% below median (\$500K reference)
- ☐ Cross-check against the 3 sensitivity scenarios — base price aligns with the matching scenario

I. Cross-reference to other documents

Question	Document
Detailed scope by trade with quantities	<code>../takeoff-template.json</code>
Skeleton for the post-drawings final takeoff	<code>../price-sheet-skeleton.json</code>
Quantity-driven scope rows (CSI Div by Div)	<code>../04-scope-of-work.md § C</code>
\$/SF and scenario benchmarks	<code>../price-references.md</code>
Tom Green County prevailing wage + escalation factor	<code>../prevailing-wages.md</code>
Risk factors driving contingency	<code>../07-risk-register.md</code>
Owner-furnished items NOT priced	<code>../04-scope-of-work.md § A</code>