

BLUE PRINT CONSTRUCTS

# Proposal package — B1710 Office Refurbishment (Solicitation FA667526Q0002)

Solicitation: FA667526Q0002

*Full proposal*

PREPARED BY

**Blue Print Constructs**

RK Residential Homes and Commercial Constructions, LLC

UEI LM4YHVQ71QG7 · CAGE 9LET0 · Submission date \_\_\_\_\_

**Ravikiran (Rocky) Nudurupati**

Founder & Managing Director / Owner (100%)

rocky@blueprintconstructs.com · (469) 213-1838

*Document prepared 2026-05-28 · bid-slug: b1710-office-refurb-FA667526Q0002*

# Table of Contents

---

|           |                                                                                   |
|-----------|-----------------------------------------------------------------------------------|
| <b>00</b> | <b>Proposal package — B1710 Office Refurbishment (Solicitation FA667526Q0002)</b> |
| <b>01</b> | <b>Price Proposal — FA667526Q0002 B1710 Office Refurbishment</b>                  |
| <b>02</b> | <b>Technical Acceptability — FA667526Q0002 B1710 Office Refurbishment</b>         |
| <b>03</b> | <b>Past Performance — FA667526Q0002 B1710 Office Refurbishment</b>                |



SECTION 00

00

---

# Proposal package — B1710 Office Refurbishment (Solicitation FA667526Q0002)

# Proposal package — B1710 Office Refurbishment (Solicitation FA667526Q0002)

This is the submission-side of the bid workspace. The bid-prep mechanics (overview, scope decomposition, takeoff, missing-docs list, risk register) live one directory up; this directory contains the **documents that will be sent to the CO with the offer**.

## Submission shape

The CO will receive a **single email** to `lydia.carlton@us.af.mil` CC `todd.benner@us.af.mil`, subject:

*Quote — FA667526Q0002 — Blue Print Constructs (UEI LM4YHVQ71QG7)*

The email body is the cover letter (see `11-rfi-cover-letter.md` for the offer-cover template — repurposed from the RFI template).

Attachments, in order (each as a separate PDF for CO convenience, named with consistent prefix):

| # | Filename (target)            | Source markdown            | Notes                                                         |
|---|------------------------------|----------------------------|---------------------------------------------------------------|
| 1 | 01_SF1449_FA667526Q0002      | 04-SF-1449-fill-guide      | Signed SF 1449 page 1 — Blocks 12, 17, 23, 24, 30 filled      |
| 2 | 02_PriceProposal_BluePrint   | 01-price-proposal.md       | Lump-sum number + line-item backup                            |
| 3 | 03_TechnicalAcceptability    | 02-technical-acceptability | Equipment/material/labor list + 90-day schedule + QC + safety |
| 4 | 04_PastPerformance_BluePrint | 03-past-performance.md     | 3-pack: Hindu Temple + Holiday Inn + Lavon RV Park            |
| 5 | 05_RepsAndCerts_SAM-screen   | 05-reps-and-certs-pull     | SAM.gov entity-status screenshot + reps & certs date          |
| 6 | 06_PaymentBondCommitment     | 06-bonding agent)          | Per FAR 52.228-13 — see 06-bondability-letter-template.       |

|   |                                            |                         |                                                     |
|---|--------------------------------------------|-------------------------|-----------------------------------------------------|
| 7 | 07_COI_ACORD25.pdf                         | (from insurance broker) | Current GL coverage; verify named-insured + limits  |
| 8 | 08_BuyAmericanCertification.pdf (optional) | (line item statement)   | Affirmation per FAR 52.225-9; all materials US-made |

## Mapping to evaluation factors

Per 04-evaluation-strategy.md, the CO is most likely running **comparative evaluation per FAR 12.203(c)(2)**. The attachments map to evaluation dimensions:

- **Responsiveness / responsibility** — Attachments 1, 5, 6, 7 (SF 1449 signed, SAM active, payment-bond capacity, COI)
- **Price** — Attachment 2
- **Technical acceptability** — Attachment 3 (equipment / labor / schedule)
- **Past performance** — Attachment 4 (3-pack)
- **Compliance** — Attachment 8 (Buy American), implicit in 1 (Davis-Bacon flow-down)

## Files in this directory

| File                                            | Purpose                                                   |
|-------------------------------------------------|-----------------------------------------------------------|
| <a href="#">00-readme.md</a>                    | This file — submission shape + attachment list            |
| <a href="#">01-price-proposal.md</a>            | Lump-sum + line-item backup                               |
| <a href="#">02-technical-acceptability.md</a>   | Trade-by-trade equipment + labor + schedule narrative     |
| <a href="#">03-past-performance.md</a>          | 3-pack of past projects + reference contacts              |
| <a href="#">04-SF-1449-fill-guide.md</a>        | Block-by-block guide to filling the SF 1449 cover         |
| <a href="#">05-reps-and-certs-pull-guide.md</a> | How to pull SAM screenshot + verify reps & certs currency |

|                                                          |                                                                 |
|----------------------------------------------------------|-----------------------------------------------------------------|
| <u><a href="#">06-bondability-letter-template.md</a></u> | Template request to bonding agent for payment-bond commitment   |
| <u><a href="#">07-bid-bond-form-template.md</a></u>      | <b>N/A for this RFQ</b> — kept for cross-workspace consistency  |
| <u><a href="#">08-dba-or-sca-compliance.md</a></u>       | Davis-Bacon compliance posture (not SCA — this is construction) |
| <u><a href="#">09-site-visit-attendance-memo.md</a></u>  | Site-walk request + rationale documentation                     |
| <u><a href="#">10-submission-checklist.md</a></u>        | Fri AM final checklist before email send                        |
| <u><a href="#">11-rfi-cover-letter.md</a></u>            | RFI cover letter (Thu AM send) + offer cover letter (Fri send)  |

## What this directory does NOT contain

- The actual signed SF 1449 PDF (created by filling the original PDF; not stored as markdown)
- The actual COI PDF (lives in `firm/` or OneDrive; referenced here)
- The payment-bond commitment letter (lives in `firm/` once delivered; referenced here)
- The SAM screenshot (one-off at submission time; not committed to git)

Rendered artifacts (full proposal PDF + pitch-deck PPTX) generated by python

`scripts/render_proposals.py --bid bids/b1710-office-refurb-FA667526Q0002 --tier all` land in `proposal/exports/` (gitignored).

SECTION 01

# 01

---

## Price Proposal — FA667526Q0002 B1710 Office Refurbishment



# Price Proposal — FA667526Q0002 B1710 Office Refurbishment

**Offeror:** RK Residential Homes and Commercial Constructions, LLC dba Blue Print Constructs — LM4YHVQ71QG7 — 9LET0 **Solicitation:** FA667526Q0002 **Date:** \_\_\_\_\_ **Pricing arrangement:** Firm Fixed Price, single Lot **Acceptance period offered:** 30 calendar days (minimum per FAR 52.212-1)

## Lump-sum quoted

■■ [AWAITING PRICE BUILD] — fill at Gate 4 (Thu PM, per 01-bid-prep-checklist.md). The lump-sum number for SF 1449 Block 23/24 lands here. Target band per 09-price-references.md \$6 mid-point: **\$90,000 – \$105,000**.

| Item 0001<br>description | Quantity | Unit | Unit Price | Amount |
|--------------------------|----------|------|------------|--------|
|--------------------------|----------|------|------------|--------|

|                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |   |     |                           |                           |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---|-----|---------------------------|---------------------------|
| Perform all work described in the attached Statement of Work for the B1710 Office Refurbish at NAS JRB Fort Worth — including carpet tile replacement (~3,500 SF), 6" rubber base, interior paint, sheetrock in-fill of Rm 1030 doorway, Rm 1008 furniture/material disposal and wall patch with access panel, furniture relocation and restoration, daily cleanup and disposal at certified landfill, and 1-year warranty of construction. Davis-Bacon TX20260270 wages applied. | 1 | Lot | [\$[AWAITING PRICE BUILD] | [\$[AWAITING PRICE BUILD] |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---|-----|---------------------------|---------------------------|

**Total firm-fixed-price quoted (Lot):** [\$[AWAITING PRICE BUILD]

## Backup detail — line-item build-up

*The CO need not approve this build-up; it is informational, transmitted for transparency and to demonstrate technical understanding per the comparative-evaluation criteria implied by FAR 12.203(c)(2). The contractual price is the single Lot number above.*

| # | C              | Line item                                                             | Quantity | Unit | Unit cost | Extended      |
|---|----------------|-----------------------------------------------------------------------|----------|------|-----------|---------------|
| 1 | 02<br>41<br>15 | Selective demo + furniture relocate<br>(3,500 SF flooring + 16 rooms) | 1        | —    | LS        | [\$[AWAITING] |

|    |                                                                                                                                                                |              |     |  |                     |
|----|----------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------|-----|--|---------------------|
| 2  | 02 Furniture + material disposal — Rm 41 1008 19                                                                                                               | 1            | —LS |  | \$[AWAITING]        |
| 3  | 01 Construction-debris disposal (~10 CY, \$[AWAITING]C' certified landfill) 74 15                                                                              |              |     |  | \$[AWAITING]        |
| 4  | 09 Carpet tile — Shaw Constellat EW24 68 (Style 59326), Color 26110 Moonlight 13 Grade A, 24"×24", glue-down. Or accepted equal per SOW \$B.                   | \$[AWAITING] | SI  |  | \$[AWAITING]        |
| 5  | 03 Self-leveling underlayment — allowance 54 13                                                                                                                | \$[AWAITING] | SI  |  | \$[AWAITING]        |
| 6  | 09 Rubber cove base 6" gray (samples for owner selection per SOW \$B) 65 13                                                                                    | \$[AWAITING] | LF  |  | \$[AWAITING]        |
| 7  | 05 Interior paint — walls, primer + 2 coats 91 SW 7029 Agreeable Gray eggshell 23                                                                              | \$[AWAITING] | SI  |  | \$[AWAITING]        |
| 8  | 09 Drywall in-fill at Rm 1030 doorway — 21 metal stud framing + 5/8" GWB both 16 sides + tape/bed/texture + prime + 2 coats paint                              | 1            | —EA |  | \$[AWAITING]        |
| 9  | 05 Wall patch — Rm 1008 (~16 SF GWB + 25 finish to match) 00                                                                                                   | 1            | —E  |  | \$[AWAITING]        |
| 10 | 08 Access panel — 12"×12" valve-rated, 31 Karp DSB-214M or equal — Rm 1008 13                                                                                  | 1            | —EA |  | \$[AWAITING]        |
| 11 | 01 Furniture move + restore (16 rooms, 76 2-person crew × ~3-4 working days) 00                                                                                | 1            | —L  |  | \$[AWAITING]        |
| 12 | 01 General conditions (PM, supervision, 00 certified-payroll admin, daily cleanup, 00 dumpsters, base-access coord, mobilization×2, punch-list, 1-yr warranty) | 1            | —LS |  | \$[AWAITING]        |
|    | <b>Direct cost subtotal</b>                                                                                                                                    |              |     |  | <b>\$[AWAITING]</b> |

|    |                                                                                             |  |  |  |                     |
|----|---------------------------------------------------------------------------------------------|--|--|--|---------------------|
| 13 | — Overhead (10%)                                                                            |  |  |  | \$[AWAITING]        |
| 14 | — Profit (10%)                                                                              |  |  |  | \$[AWAITING]        |
| 15 | — Quantity contingency (5% on direct, justified by no-site-walk per 07-risk-register.md R2) |  |  |  | \$[AWAITING]        |
|    | <b>TOTAL LUMP-SUM (Item 0001)</b>                                                           |  |  |  | <b>\$[AWAITING]</b> |

## Pricing notes for the CO

1. **Davis-Bacon compliance.** All labor priced at TX20260270 (Tarrant County, Building Construction, Mod 0, 02 Jan 2026) rates per FAR 52.222-6. Certified-payroll administration (WH-347 weekly) is included in the general conditions line.
2. **Buy American.** All construction materials in scope are domestic-manufactured per FAR 52.225-9: Shaw carpet tile (Dalton, GA), Sherwin-Williams paint (Cleveland, OH), Roppe/Johnsonite/Burke Mercer rubber base (US-Ohio plants), USG/National Gypsum drywall (multi-state US), Karp Associates access panel (Maspeth, NY). No Buy American determination required.
3. **Carpet equivalency.** Quoted at SOW spec (Shaw Constellat EW24 Style 59326, Color 26110 Moonlight Grade A). Dye-lot H6958 confirmation will be made at submittal time per AF IMT 3000 process; if H6958 is not in current production, the closest in-production lot will be submitted for owner approval per SOW §B.
4. **Paint scope.** Pricing assumes walls only in the C/B/P-marked areas + hallway per floor plan annotation "paint all hallway". Ceiling paint, baseboards, doors, and trim are NOT included unless the CO clarifies otherwise (see RFI). Price-add available on request.
5. **Site visit.** No site walk was offered before submission; pricing reflects SOW-stated quantities with 5% contingency for field-verify-after-award. Differing Site Conditions claims will be made per FAR 52.236-2 if material variance is found.
6. **Acceptance period.** 30 calendar days from offer due date (consistent with FAR 52.212-1 default).
7. **Validity of payment-bond capacity.** Surety commitment letter attached as Attachment 06 confirms capacity for the FAR 52.228-13 payment bond (100% of contract price, post-award, within 10 days).

## Signature

*The lump-sum offer is binding on the offeror per SF 1449 Block 30 signature. The lump-sum value above is the entire consideration for the work described in the Statement of Work and incorporated documents.*

Offeror name: RK Residential Homes and Commercial Constructions, LLC dba Blue Print Constructs

Authorized signer: \_\_\_\_\_ Signature: \_\_\_\_\_ Date: \_\_\_\_\_

SECTION 02

# 02

---

## Technical Acceptability — FA667526Q0002 B1710 Office Refurbishment

# Technical Acceptability — FA667526Q0002 B1710 Office Refurbishment

**Offeror:** RK Residential Homes and Commercial Constructions, LLC dba Blue Print Constructs

**Solicitation:** FA667526Q0002 **Submission date:** \_\_\_\_\_

*This document supports the comparative evaluation regime implied by FAR 52.212-1 Deviation 2026-00038 + the absence of an explicit FAR 52.212-2 Evaluation clause in Section M. Per 04-evaluation-strategy.md, the CO will weigh: (a) understanding of the work (this document's equipment/material/labor list), (b) realism of the schedule (90-day Gantt below), (c) past performance (separate document — 03-past-performance.md), (d) price (01-price-proposal.md).*

## 1. Understanding of the work

The B1710 Office Refurbishment is a **single-building, occupied-condition interior finishes renovation** at Building 1710, NAS JRB Fort Worth, covering approximately 3,500 SF of office and common-area space. The work is a coordinated 4-trade scope: demolition, drywall (limited), carpet tile + base, and paint. There is one specialty item (access panel for valve in Rm 1008) and a minor structural infill (sheetrock-in of Rm 1030 doorway).

We have read the SOW in full and the floor plan; our scope decomposition is in

`../02-scope-of-work.md`.

### 1.1 Critical-path activities

In order of duration: 1. **Paint** (Item C in SOW) — longest single-trade duration; requires phased room-by-room access. ~12 working days for ~13,500 SF wall area with a 2-painter crew, 2 coats over primer. 2. **Carpet tile + base install** (Item B) — second-longest; ~10-12 working days for 3,500 SF tile + 1,300 LF base with a 2-person crew. Must follow paint completion in each room to avoid overspray onto new flooring. 3. **Demolition + furniture relocate** (Item A) — must lead all other trades in each room; ~5-7 working days for 16 rooms. 4. **Drywall in-fill at Rm 1030 + Rm 1008 patch + access panel** (Items D/F) — short duration (~3 working days) but must precede paint in those two rooms. 5. **Disposal** (Item E + general) — continuous through PoP; 10 CY roll-off staged on-base per coordinated delivery with `steven.munnell@us.af.mil`.

### 1.2 Sequence — by-room batching

We will divide the 16 C/B/P rooms into **4 batches of 4 rooms each** to minimize disruption to AFRC operations per SOW §3.1.2:

- **Batch 1** (week 1-2): Rooms 1002, 1006, 1008, 1009 — includes Rm 1008 wall patch + access panel
- **Batch 2** (week 3-4): Rooms 1013, 1020, 1022, 1023
- **Batch 3** (week 5-6): Rooms 1025, 1026, 1028, 1029

- **Batch 4** (week 7-8): Room 1030 (includes doorway sheetrock-in) + hallway + remaining + punch-list

This sequence allows the AFRC tenant to vacate rooms in rolling fashion (4 at a time), preserving operational continuity. Floats in weeks 9-12 absorb any furniture-coordination slip and the final close-out.

### 1.3 Working hours + base access

Per SOW §SCHEDULE: 0700–1600 M-F. Material deliveries via the commercial vehicle gate (Alta Mere Drive × Ridgmar Meadows Road) 0600-1400 M-F. Base-access vetting for prime + sub personnel coordinated with [steven.munnell@us.af.mil](mailto:steven.munnell@us.af.mil) post-NTP; lead time 3-5 business days from passname submission. Same procedure as on the Cmd Post + NDI project (separate workspace; same base).

## 2. Equipment, materials, and labor

Per the comparative-evaluation criteria, this section lists every material, every equipment line, and every labor classification touched by the scope. This is the "RSMeans-style output" type of artifact AF Reserve COs typically expect on a technical-acceptability evaluation.

### 2.1 Materials list

| # | Material                         | Spec                                                            | Source / Manufacturer                                          | Qty estimate        | Davis-Bacon labor class |
|---|----------------------------------|-----------------------------------------------------------------|----------------------------------------------------------------|---------------------|-------------------------|
| 1 | Carpet tile, 24"×24", 100% Nylon | Shaw Constellat EW24 Style 59326, Color 26110 Moonlight Grade A | Shaw Industries — Dalton, GA (US-made; Buy American compliant) | 3,500 SF + 5% waste | Floor Layer             |
| 2 | Carpet adhesive                  | Shaw-spec release adhesive (Lok-Dots or equal)                  | Shaw or local distributor                                      | ~50 gal             | Floor Layer             |
| 3 | Self-leveling underlayment       | Cementitious, 1/8" avg depth                                    | Mapei, ARDEX, or equal — US-made                               | ~500 SF             | Floor Layer             |



|    |                                                              |                                                                    |                                                                               |                                 |                     |
|----|--------------------------------------------------------------|--------------------------------------------------------------------|-------------------------------------------------------------------------------|---------------------------------|---------------------|
| 4  | Rubber cove base, 6" tall                                    | Commercial grade, gray (color from samples per SOW)                | Roppe (Fostoria OH), Johnsonite (Chagrin Falls OH), or Burke Mercer (US-made) | ~1,300 LF                       | Floor Layer         |
| 5  | Cove-base cement                                             | Standard cove-base adhesive                                        | Roppe, Johnsonite, or equal                                                   | ~6 gal                          | Floor Layer         |
| 6  | Interior latex paint, primer                                 | Sherwin-Williams PrepRite ProBlock or equal                        | Sherwin-Williams — Cleveland OH (US-made)                                     | ~30 gal                         | Painter             |
| 7  | Interior latex paint, finish, eggshell                       | SW ProMar 200 (or equivalent), Color <b>SW 7029 Agreeable Gray</b> | Sherwin-Williams — Cleveland OH                                               | ~110 gal (2 coats × ~13,500 SF) | Painter             |
| 8  | 5/8" Type X GWB                                              | Standard commercial gypsum board                                   | USG, National Gypsum, or CertainTeed (US-made)                                | ~60 SF                          | Drywaller           |
| 9  | Metal stud, 3-5/8" or 6", 25-gauge                           | Per Rm 1030 doorway in-fill framing                                | ClarkDietrich or equal — US-made                                              | ~7 LF + plates                  | Carpenter           |
| 10 | Joint compound, tape, primer-sealer                          | Standard GWB finish set                                            | USG, Sheetrock, or equal                                                      | Allowance                       | Drywaller + Painter |
| 11 | Access panel, 12"×12", steel-frame plaster-bead, valve-rated | Karp Associates DSB-214M or Acudor equal — US-made                 | Karp — Maspeth NY                                                             | 1 EA                            | Carpenter           |

|    |                   |                                        |                     |           |                     |
|----|-------------------|----------------------------------------|---------------------|-----------|---------------------|
| 12 | Caulks + sealants | Acoustic caulk + paintable latex caulk | Standard commercial | Allowance | Painter + Drywaller |
|----|-------------------|----------------------------------------|---------------------|-----------|---------------------|

All listed materials are domestic-manufactured (Buy American Act compliant per FAR 52.225-9). No foreign-source materials proposed; no Buy American determination required.

## 2.2 Equipment + tooling list

| Item                                                                                                        | Use                                                                            | Davis-Bacon class     |
|-------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------|-----------------------|
| 24-ft pickup truck or box truck                                                                             | Material delivery + tool transport (escorted to commercial gate per Section G) | Driver / Laborer      |
| Floor-roller (75 lb), seam-roller, knee-kicker, tile cutter                                                 | Carpet tile install                                                            | Floor Layer           |
| Cove-base hand-roller, miter cutter, scribe tools                                                           | Cove base install                                                              | Floor Layer           |
| Sprayer (HVLV for cut-in, pump for roll-out), rollers, brushes, drop cloths, plastic sheeting, masking tape | Paint application                                                              | Painter               |
| Track saw, screw gun, drywall cutters, joint-compound tools                                                 | Drywall in-fill at Rm 1030                                                     | Drywaller + Carpenter |
| Drill, hole-saw, level, screw gun                                                                           | Access panel install                                                           | Carpenter             |
| Hand tools (utility knife, tape measure, pry bar, demolition tools)                                         | Demolition + general                                                           | All trades            |
| Wet-vac, brooms, dust pans, mops                                                                            | Daily cleanup per SOW                                                          | Laborer               |
| Roll-off dumpster (~10 CY)                                                                                  | Construction debris per SOW §A                                                 | (Disposal vendor)     |
| Portable Government toilet (none — using Government toilets per SOW)                                        | N/A                                                                            | —                     |

|                                   |                              |        |
|-----------------------------------|------------------------------|--------|
| First-aid kit + fire extinguisher | OSHA 29 CFR 1926 site safety | Safety |
|-----------------------------------|------------------------------|--------|

### 2.3 Labor list — by trade

| Trade                             | Davis-Bacon classification (TX20260270) | Loaded rate (estimate; verify against WD PDF) | Work hours estimate                      |
|-----------------------------------|-----------------------------------------|-----------------------------------------------|------------------------------------------|
| Floor Layer (carpet + base)       | Floor Layer / Resilient Floor Layer     | \$26 – \$34 / hr                              | ~140 hr (2 workers × 8-10 days)          |
| Painter                           | Painter                                 | \$26 – \$34 / hr                              | ~160 hr (2 workers × 10-12 days)         |
| Drywaller / Taper                 | Drywall Hanger + Taper                  | \$30 – \$38 / hr                              | ~24 hr                                   |
| Carpenter                         | Carpenter                               | \$32 – \$40 / hr                              | ~24 hr                                   |
| Laborer Group 1                   | Laborer Group 1                         | \$20 – \$26 / hr                              | ~96 hr (demo + furniture move + cleanup) |
| Project Manager / Superintendent  | Not DBA-rated; firm overhead            | (firm rate)                                   | ~60 hr over 90-day PoP                   |
| Safety Officer (collateral to PM) | Not DBA-rated; firm overhead            | (firm rate)                                   | (collateral)                             |
| QC (collateral to PM)             | Not DBA-rated; firm overhead            | (firm rate)                                   | (collateral)                             |

Total estimated trade labor: **~444 hours** across 90-day PoP. Compresses to ~3 working weeks of intense activity, framed by mobilization and close-out. Field-verify and refine after Gate 2 takeoff.

## 3. Schedule — 90 calendar days from NTP

| Week | Cal days from NTP | Activity | Owner |
|------|-------------------|----------|-------|
|------|-------------------|----------|-------|

|   |       |                                                                                                                                                                                                                             |                                    |
|---|-------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------|
| 1 | 1–7   | Mobilization:<br>base-access<br>submission for<br>personnel;<br>commercial vehicle<br>gate procedure;<br>receive site survey +<br>verify quantities;<br>submittals to CO via<br>AF IMT 3000 (carpet,<br>base, paint, panel) | PM                                 |
| 2 | 8–14  | Submittal approval<br>period (assume 5-7<br>cal days CO<br>turnaround); order<br>materials with<br>lead-time confirmed;<br>Batch 1 demo +<br>furniture relocate<br>(Rooms 1002, 1006,<br>1008, 1009)                        | PM + Laborer                       |
| 3 | 15–21 | Batch 1: Rm 1008<br>wall patch + access<br>panel install; Batch 1<br>paint walls (primer +<br>1st coat)                                                                                                                     | Carpenter +<br>Drywaller + Painter |
| 4 | 22–28 | Batch 1: paint 2nd<br>coat; carpet + base<br>install; Batch 2 demo<br>+ furniture relocate                                                                                                                                  | Painter + Floor Layer<br>+ Laborer |
| 5 | 29–35 | Batch 1 punch-list +<br>restore furniture;<br>Batch 2 paint (primer<br>+ 1st coat)                                                                                                                                          | All trades                         |
| 6 | 36–42 | Batch 2: paint 2nd<br>coat; carpet + base;<br>Batch 3 demo +<br>furniture relocate                                                                                                                                          | Painter + Floor Layer<br>+ Laborer |
| 7 | 43–49 | Batch 2 punch-list +<br>restore furniture;<br>Batch 3 paint (primer<br>+ 1st coat)                                                                                                                                          | All trades                         |

|    |       |                                                                                                     |                                               |
|----|-------|-----------------------------------------------------------------------------------------------------|-----------------------------------------------|
| 8  | 50–56 | Batch 3: paint 2nd coat; carpet + base; Batch 4 demo (incl. Rm 1030 doorway opening + sheetrock-in) | Painter + Floor Layer + Carpenter + Drywaller |
| 9  | 57–63 | Batch 3 punch-list + restore furniture; Batch 4 paint (Rm 1030 + hallway)                           | All trades                                    |
| 10 | 64–70 | Batch 4 paint 2nd coat; carpet + base in Batch 4 + hallway; final furniture restore                 | Painter + Floor Layer + Laborer               |
| 11 | 71–77 | Final punch-list walk; touch-ups; cleanup; close-out documentation prep                             | All trades                                    |
| 12 | 78–84 | Pre-final inspection + corrections; warranty letter delivery; final cleanup                         | PM                                            |
| 13 | 85–90 | Final inspection by CO/COR; substantial completion; close-out                                       | PM + CO                                       |

### 3.1 Float

Approximately **15-20 calendar days of float** across the schedule, primarily absorbed in weeks 11-13. Critical-path drivers: paint cure time between coats (24 hr per SW spec), carpet tile cure after install (24 hr light traffic, 72 hr heavy), and the 4-room-batch sequencing that prevents over-occupying the AFRC office spaces.

### 3.2 Holidays + observed days

- Juneteenth — Fri 2026-06-19 (no work; falls in week 1-2 depending on actual NTP date)
- Independence Day observed — Fri 2026-07-03 (likely week 4-5)
- Labor Day — Mon 2026-09-07 (week 11-12 boundary)

### 3.3 Working hours

Per SOW §SCHEDULE: 0700-1600 M-F. No weekend or after-hours work without written CO approval. Material deliveries via commercial gate 0600-1400 M-F.

## 4. Quality control plan

We will execute the project under our firm's standard QC plan, summarized:

- **Daily** — Site supervision; punch-walk each completed room before move-on to next batch
- **Per-trade hold-points** — Demolition completion / drywall completion / paint 1st coat dry / paint 2nd coat dry / carpet install acceptance / base install acceptance — internal QC signature each
- **Submittals** — AF IMT 3000 forms for each material before procurement (carpet, base, paint, drywall, access panel)
- **Substantial completion walk-through** — Pre-final and final inspections per SOW with the CO/COR
- **Warranty** — 1-year warranty of construction per FAR 52.246-21 + Letter of Guarantee delivered at substantial completion per SOW §PART III

## 5. Safety plan

- **OSHA 29 CFR 1910 + 1926 compliance** — all trade work
- **DAFMAN 91-203** — Air Force OSH standards per SOW §PART I
- **Daily site-safety check** — by the on-site PM/super (Rocky)
- **Fall protection** — N/A in this single-story interior renovation; ladders + scaffolds rated for use
- **No-Notice Inspections** — Contractor cooperates with DOL inspectors or installation Safety per SOW §OCCUPATIONAL SAFETY
- **Dust + debris control** — Daily cleanup; covered dumpsters; no spread to airfield
- **Government-furnished restroom** — Used per SOW; paint cleanup explicitly NOT in facility restrooms or janitor closet
- **Personnel identification** — Hard-hat company markings; AF-approved ID for each employee
- **PII handling** — No SSNs in offer email; base-access vetting forms collected post-NTP through 301 LRS sponsor

## 6. Personnel

For this 90-day, \$90-105K-target project at AFRC small-scale, the firm's owner-operator pattern applies:

| Role | Name | Bio source |
|------|------|------------|
|------|------|------------|

|                                                                           |                                                                                                    |                                                                                                                                             |
|---------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------|
| Project Manager /<br>Superintendent / Safety Officer<br>/ Quality Control | <b>Ravikiran (Rocky)<br/>Nudurupati</b> , Founder &<br>Managing Director, Blue Print<br>Constructs | Per<br>firm/firm-profile.json<br>→ key_personnel[0]. PMP,<br>CSM, SAFe; 22 years<br>professional + 4 years<br>construction-firm leadership. |
| Trade crew                                                                | Mixed self-perform + sub crew,<br>depending on Gate 4<br>sub-quote decisions                       | See 02-scope-of-work.md<br>§8                                                                                                               |
| Bonding agent                                                             | _____                                                                                              | Per<br>firm/firm-profile.json<br>→ bonding (data to surface)                                                                                |

This staffing arrangement is consistent with BPC's prior delivery model on similar-scale projects (Hindu Temple of Southlake, Holiday Inn Hall Park).

## 7. Affirmations

- All proposed materials are **domestic-manufactured** per FAR 52.225-9 (Buy American). No Buy American determination requested.
- Davis-Bacon TX20260270 wages will be paid; certified payroll (WH-347) submitted weekly per FAR 52.222-6, 52.222-8, 52.222-10.
- Blue Print Constructs is a **Small Business** under NAICS 236220 (\$45M size standard) per its current SAM.gov registration.
- Blue Print Constructs has the **bonding capacity** to provide the FAR 52.228-13 payment bond at 100% of contract price within 10 days of award. Commitment letter attached.
- Blue Print Constructs has **current Commercial General Liability** coverage; ACORD 25 attached.
- The offeror is not subject to any **debarment, suspension, or proposed-for-debarment** action; not listed on SAM Exclusions.

SECTION 03

# 03

---

## Past Performance — FA667526Q0002 B1710 Office Refurbishment



# Past Performance — FA667526Q0002 B1710 Office Refurbishment

**Offeror:** RK Residential Homes and Commercial Constructions, LLC dba Blue Print Constructs  
**Solicitation:** FA667526Q0002

**Past-performance picks for this bid** (from *firm/firm-profile.json* → *past\_project\_selection\_rules*): Most-relevant analog set for this 100% Small-Business AFRC interior-finishes RFQ at NAS JRB Fort Worth: 1. **Hindu Temple of Southlake** — institutional finishes (10,700 SF Assembly A-3 renovation: demo, finishes, toilet partitions, partition framework). Most-comparable to B1710 in scope shape (multi-room interior finishes), in delivery context (occupied institutional building), and in trade mix (drywall, paint, flooring). 2. **Holiday Inn (Hall Park, Frisco)** — commercial hospitality renovation; closest analog to AFRC office-occupied work where guests/personnel are in adjacent rooms. 3. **Lavon RV Park** — federal-style coordination + scope discipline + \$1M performance-bond procurement. Demonstrates BPC's capability to deliver under formal contract terms equivalent to federal procurement standards.

Per the comparative-evaluation regime (see *../04-evaluation-strategy.md*), the CO will likely use CPARS, SPRS, and direct contact with these references. Each reference below provides: project shape, scope, contract value, delivery method, role, completion status, and the owner-side reference contact.

## Reference 1 — Hindu Temple of Southlake (institutional interior renovation)

| Field                | Value                                                             |
|----------------------|-------------------------------------------------------------------|
| Project name         | Hindu Temple of Southlake — Place of Religious Worship renovation |
| Owner                | North Texas Hindu Heritage Society                                |
| Owner address        | 595 South Kimball Avenue, Southlake, TX 76092                     |
| Owner-side project # | 2024-024                                                          |
| Project size         | ≈10,700 SF Assembly A-3 (Place of Religious Worship) renovation   |
| Contract value       | _____                                                             |

|                   |                                                                         |
|-------------------|-------------------------------------------------------------------------|
| Delivery method   | Negotiated lump-sum (owner direct)                                      |
| Role              | General Contractor                                                      |
| Start             | Drawings dated 2025-06-20 (PDF), updated 2025-09-12 (Arch + Structural) |
| Status            | In execution per material quote 2025-10-30                              |
| Reference contact | _____                                                                   |
| Source folder     | Hindu Temple of South Lake/ on OneDrive                                 |

**Relevance to B1710 (CO-facing narrative):**

- **Multi-room interior finishes scope** — demolition, drywall (limited), toilet partitions, partition framework, finishes — parallels the multi-room (16-room) interior finishes scope at B1710.
- **Institutional / nonprofit owner** — comparable formality of contract administration and owner-coordination requirements.
- **Trade mix** — drywall, painting, flooring, specialty (partition) — all present in both projects.
- **Active execution as of 2025-10-30** — proves BPC's mid-execution capacity for an institutional client.

---

## Reference 2 — Holiday Inn (Hall Park, Frisco) (commercial hospitality renovation)

| Field           | Value                                            |
|-----------------|--------------------------------------------------|
| Project name    | Holiday Inn (Hall Park) — hospitality renovation |
| Owner           | Holiday Inn franchisee at Hall Park, Frisco, TX  |
| Owner address   | Hall Park, Frisco, TX                            |
| Contract value  | _____                                            |
| Delivery method | _____                                            |

|                   |                                                                                                   |
|-------------------|---------------------------------------------------------------------------------------------------|
| Role              | General Contractor                                                                                |
| Completion        | _____                                                                                             |
| Reference contact | _____                                                                                             |
| Scope summary     | Commercial renovation projects for hospitality client per Rocky Nudurupati's professional profile |

#### Relevance to B1710 (CO-facing narrative):

- **Occupied-building renovation** — hospitality renovations are inherently occupied-condition; rooms are vacated in rolling batches while adjacent rooms remain in operation. **Direct analog** to B1710 SOW §3.1.2 *"minimize interruption of the normal duty day of Government activity"*.
- **Commercial finishes scope** — hospitality renovations are dominantly carpet + paint + drywall work, same trade mix as B1710.
- **Repeat client / preferred-vendor relationship** — Rocky's profile lists Holiday Inn (Hall Park) as a featured client, indicating sustained quality and on-time delivery.

### Reference 3 — Lavon RV Park (federal-style coordination + bonding)

| Field          | Value                                                                |
|----------------|----------------------------------------------------------------------|
| Project name   | Lavon RV Park — 30-lot RV park new construction                      |
| Owner          | Lavon Leisure 78 RV Park LLC                                         |
| Owner address  | 614 Forest Hill Dr, Murphy, TX 75094                                 |
| Site address   | County Road 597, Farmersville, TX 75442                              |
| Contract value | \$1,050,000                                                          |
| Contract type  | Standard AIA A101-2020 fixed-price; AIA A201-2020 general conditions |

|                        |                                                                          |
|------------------------|--------------------------------------------------------------------------|
| Delivery method        | Design-Bid-Build (fixed lump-sum)                                        |
| Role                   | General Contractor                                                       |
| Start date             | 2025-07-30                                                               |
| Substantial completion | 2026-04-30 (per contract; status to confirm before citing as 'complete') |
| Bond                   | <b>\$1,000,000 performance bond</b> per contract Article 8               |
| Reference contact      | _____                                                                    |
| Source folder          | Lavon RV Park/ on OneDrive                                               |

#### Relevance to B1710 (CO-facing narrative):

- **Bonding capacity demonstrated** — BPC successfully procured a \$1,000,000 performance bond on this project, establishing firm-level bonding capacity well above the B1710 payment-bond requirement (~\$100K max under FAR 52.228-13).
- **Formal contract administration** — AIA A101-2020 + A201-2020 mirrors the contract-administration formality of federal FAR-flowdown procurement. Demonstrates BPC's capability to operate under formal contract terms equivalent to federal procurement standards.
- **Multi-trade GC coordination** — site work, MEP, utilities, fencing, retaining walls, building construction — proves BPC's GC depth across many trades, including the carpentry / framing / drywall trades present at B1710.
- **Fixed-lump-sum execution discipline** — both projects are firm-fixed-price, requiring tight cost control and accurate takeoffs.

#### At-a-glance summary table

| # | Project | Owner | Value | Status | Trade-mix overlap with B1710 |
|---|---------|-------|-------|--------|------------------------------|
|   |         |       |       |        |                              |

|   |                                 |                                    |             |                                 |                                                                                                                |
|---|---------------------------------|------------------------------------|-------------|---------------------------------|----------------------------------------------------------------------------------------------------------------|
| 1 | Hindu Temple of Southlake       | North Texas Hindu Heritage Society | —           | In execution (2025-2026)        | Demo + drywall + finishes + paint — <b>direct analog</b>                                                       |
| 2 | Holiday Inn (Hall Park, Frisco) | Holiday Inn franchisee             | —           | —                               | Carpet + paint + drywall + occupied-building — <b>direct analog</b>                                            |
| 3 | Lavon RV Park                   | Lavon Leisure 78 RV Park LLC       | \$1,050,000 | In execution (start 2025-07-30) | GC coordination + bonding capability + DBA-equivalent formal contract — <b>federal-style discipline analog</b> |

## CPARS / SPRS background

Blue Print Constructs is a new federal contractor; **no CPARS history yet** on prior federal awards. The references above are commercial / institutional / nonprofit — equivalent past performance in scope and shape, even if not specifically federal-CPARS-rated.

Per FAR 15.305(a)(2)(iv) and SAP comparative-evaluation practice, the CO may treat the **lack of negative CPARS findings as neutral** (rather than a strike against the offeror), and may give weight to non-federal past performance that is otherwise analogous in scope, magnitude, and complexity. The three references above are submitted on that basis.

If the CO requests **additional references** beyond the three above, BPC can provide on request from: - Volli (pickleball) — interior + exterior painting commercial reference - 250+ single-family-home portfolio — cumulative volume reference via GC partner contacts (That 1 Painter, Touchmark, Bridge View Build, Hill Design Build) - Commercial strip mall — drywall + tape/bed/texture reference

## Owner authorization to contact references

By submission of this offer, the offeror authorizes the Contracting Officer to contact any of the listed reference contacts directly for verification of past performance. The offeror's preferred mode of contact verification is by email to the listed owner-side POC in the first instance; phone follow-up at the POC's discretion.