



Blue Print Constructs

Proposal — 2026-05-23

TAMU Harrington Lab 303 — Proposal package

Solicitation: 2025-06813

Prepared by RK Residential Homes and Commercial Constructions, LLC dba Blue Print
Constructs

UEI: LM4YHVQ71QG7 CAGE: 9LET0

Authorized signer

Ravikiran (Rocky) Nudurupati

Founder & Managing Director / Owner (100%)

rocky@blueprintconstructs.com

(469) 213-1838

Confidential — Proposal — tamu-harrington-2025-06813

Table of Contents

00	TAMU Harrington Lab 303 — Proposal package
01	01 — Executive summary
02	02 — Technical approach
03	03 — Project team + key personnel
04	04 — Past performance + references
05	05 — Schedule narrative + critical path
06	06 — Quality control plan
07	07 — Site-specific safety plan
08	08 — CSP Proposal Form fill guide
09	09 — HSP (HUB Subcontracting Plan) form fill guide
10	10 — Price proposal
11	11 — Submission checklist
12	12 — Bid bond request letter template (to bonding agent)

TAMU Harrington Lab 303 — Proposal package

Solicitation: 2025-06813 — Harrington Education Center Lab 303 Renovation **Owner:** Texas A&M University, Part 02 (project administered by SSC Services for Education on TAMU's behalf) **A/E:** Patterson Architects (Fred Patterson) **Submission deadline:** 2026-06-10, 2:00 PM CT (T-19 calendar days from 2026-05-22) **Public opening:** 2026-06-10, 2:30 PM CT — SSC Facilities Services Conf Rm 204 + Teams link in the Notice **Submission address:** SSC Service Solutions, Facilities Services EDCS — 1371 TAMU / 600 Agronomy Road Suite 218, College Station TX 77843

STATUS — DRAFT, BLOCKED ON eBUILDER ACCESS + ELIGIBILITY CONFIRMATION. This package is a scaffold built off the only document we have (the public Notice of Project, [inbox/.../ESBD_514190_..._2025-06813_Notice of Project-CS_26.05.08.pdf](https://app.e-builder.net/public/publicLanding.aspx?QS=323d686fd1304ccbb2a0ee7d143af64b)). The full CSP construction document set lives behind the e-Builder Public Landing page at <https://app.e-builder.net/public/publicLanding.aspx?QS=323d686fd1304ccbb2a0ee7d143af64b> and has **not yet been downloaded**. Every section flagged [PENDING e-BUILDER ACCESS] needs to be re-walked once the CSP package is in hand.

1. Why this draft is mostly scaffold, not content

We are the **most source-poor** of the three active bids in this estimator workspace:

Bid	Source material in hand
Angelo State Carr EFA (bids/angelo-state-carr-efa-26-007/)	Full CSP + 5 attachments (A: Bid Form, B.2: Sample CSA, C: 2010 UGSC + SGC, D: HSP form, E: Tax Exempt, F.1: Prevailing Wage)
USFWS San Marcos (bids/usfws-san-marcos-140FC126R0017/)	Full SF-1442 solicitation, attachments 1–3 (Specs, Drawings, DOL Wage Determination), SOW, and amendment
TAMU Harrington (this)	Only the public Notice of Project. Drawings, specs, sample CSA, TAMU SGC, HSP form, pricing form, evaluation matrix — all behind the e-Builder portal.

The Notice itself says only: "This notification is the only documentation that will be posted to the Electronic State Business Daily (ESBD). Please refer to Trimble Unity Construct Bid Package at the above link for all documentation for this solicitation." So the next 19 days hinge on pulling that bid package on Monday morning.

The honest consequence: this draft has **more [USER TO FILL] and [PENDING e-BUILDER ACCESS] markers** than its Angelo State and USFWS siblings will. That is correct and expected. **Do not invent TAMU-specific values where the source material is missing.** Where we've used a stand-in (e.g. citing

the TTU-System 2010 UGSC from the Angelo State packet as a clause-shape proxy for the TAMU SGC), it is explicitly labeled.

2. THE BIG MISSING ITEMS (read this before scoring the draft)

These five gaps are the difference between "review-ready scaffold" and "submittable proposal":

1. **e-Builder CSP package** — drawings, specs, sample CSA, TAMU SGC, pricing form, HSP form, evaluation matrix, any addenda, RFI cutoff date. Everything quantitative depends on this. Owner: bid-prep lead. ETA: Monday 5/24 EOD.
2. **Eligibility confirmation post-missed pre-proposal meeting** — the 5/14 pre-proposal meeting was missed. The Notice does not state whether it was mandatory. Joelle Shidemantle (SSC PM) must confirm in writing that a non-attending firm can still submit a responsive proposal. If mandatory, we walk. Owner: bid-prep lead. ETA: Monday 5/24 EOD via `outreach/01-email-joelle-shidemantle-eligibility.md`.
3. **TAMU-specific HSP form** — Patty Winkler (TAMU HUB Operations) must provide the TAMU-branded HSP template or confirm we use the State of Texas standard form with a TAMU header. The HSP good-faith-effort outreach must start the same day; the form itself can wait 24-48 hours. Owner: bid-prep lead → HUB outreach. ETA: Tuesday 5/26.
4. **Lab utility scope clarification** — the Notice describes "303 Science Education Classroom/Lab Renovation" with no MEP detail. The room could be a finishes-only classroom refresh (\$95–\$140/SF), a light science classroom-lab (\$140–\$210/SF), or a heavy wet lab with fume hood / DI water / lab gas / acid waste (\$210–\$310/SF). Until Fred Patterson confirms the lab program from the drawings, the bid envelope is uncertain to roughly 2×. See `10-price-proposal.md` §B for the implied range. Owner: estimator. ETA: pending site walk + MEP drawings.
5. **Insurance + bonding limits per TAMU SGC** — the TAMU SGC will overwrite the 2010 UGSC baseline. We are carrying the TTU System SGC limits (\$1M / \$2M GL, \$1M Auto, \$5M Umbrella) as a floor expectation pending confirmation. Insurance broker and bonding agent need the final TAMU number to size policies. Owner: insurance/bonding broker. ETA: Wednesday 5/28.

3. Go / no-go gate — three rows, sequential

The bid is not viable unless all three gates close green:

Gate	Trigger	Deadline	If miss
G1 — Eligibility confirmed	Joelle confirms in writing we can still bid after missing 5/14 pre-proposal meeting	EOD Mon 2026-05-24	If pre-proposal was mandatory and no late-arriver accommodation: walk away.

G2 — e-Builder package downloaded + scanned	Full CSP package pulled, drawings sheet count > 0, specs CSI sections enumerated, pricing form and HSP form identified	Within 24 hrs of G1 close (i.e. EOD Tue 2026-05-26)	If portal still gated or package not posted by Wed 5/27, escalate to TAMU System Office of Facilities Planning & Construction; if no path by Thu 5/28, walk away.
G3 — Internal go/no-go meeting	PM + estimator + safety lead review the now-known scope, lab-utility extent, schedule constraints, and HSP feasibility; deliver go/no-go decision	EOD Tue 2026-05-26	If no-go, archive this folder under local/ and notify Joelle as a no-bid courtesy.

If all three gates close green, the rest of the proposal completes on the schedule in `../timeline.md` — submission Wed 2026-06-10, 2:00 PM CT.

4. Proposal package contents (this folder)

#	File	Purpose	Draftable now?
00	00-readme.md	(this file) Submission overview, missing items, go/no-go gate	Yes
01	01-executive-summary.md	1-page firm intro + project understanding + why-us	Mostly yes; project-understanding has [PENDING e-BUILDER ACCESS] on scope specifics
02	02-technical-approach	Phased work plan, demo sequencing, lab-utility coordination, finish schedule, university-calendar coordination	Structure yes; lab-utility specifics blocked

03	03-project-team.md	Org chart + key personnel	Template ready; needs [USER TO FILL] data
04	04-past-performance.md	3 similar projects	Template ready; needs [USER TO FILL] data
05	05-schedule-narrative.md	Backwards-planned schedule, critical path, long-lead items	Yes (with assumed substantial-completion placeholder)
06	06-quality-control-plan	3-phase inspection per TAMU UGSC	Yes (clause references [TBD per CSP package])
07	07-safety-plan.md	OSHA 1926 + TAMU EHS coordination + lab-specific hazards	Yes
08	08-csp-proposal-form	Anticipated fields for the TAMU CSP Proposal Form	Placeholder pending CSP package
09	09-hsp-form-fill-guide	Placeholder guide for TAMU HSP form	Placeholder pending Patty Winkler / CSP package
10	10-price-proposal.md	Base bid + unit prices + alternates summary	Formulas yes; values pending final takeoff
11	11-submission-checklist	Submission shape — copies, sealing, signatures, deadline	Yes (anticipated; verify against CSP package)
12	12-bid-bond-letter-template	Bonding-agent request letter template	Yes

5. Sibling-bid cross-reference (for the reviewer)

If you've already reviewed the Angelo State Carr EFA proposal draft in `bids/angelo-state-carr-efa-26-007/proposal/`, the parts that should look familiar (state-RFCSP

shape, three-phase QC, OSHA 1926 baseline, HSP outreach playbook) are reusable across both bids. The parts that are TAMU-specific (TAMU System UGSC + SGC, TAMU EHS coordination, TAMU Tech Services low-voltage scope split, TAMU HUB Operations contact, Brazos County prevailing wage, e-Builder portal) are noted with TAMU-specific markers throughout.

We deliberately did **not** copy specifics from the Angelo State package — TAMU's contract clauses, LD rates, insurance limits, and HUB form are not assumed to match Angelo State even though both are Texas state-higher-ed CSPs.

6. What the reviewer should look at first

1. Section 2 above — the five missing items. If any of these can be unblocked Friday afternoon (before Monday), please escalate.
2. `../outreach/01-email-joelle-shidemantle-eligibility.md` — the single most important email to send Monday 8 AM. Confirm the firm signature block + the "from" address before send.
3. `10-price-proposal.md` § B — the implied bid envelope and the sensitivity to lab-utility scope. Decide whether the envelope is in our wheelhouse before we sink more estimator hours.
4. `08-csp-proposal-form-fill-guide.md` and `09-hsp-form-fill-guide.md` — these are deliberately thin until the CSP package and the TAMU HSP form land. They will need to be filled in immediately on G2 close.

01 — Executive summary

Page target: 1 page when typeset (this draft is slightly long to give the reviewer the full intended copy; cut to 1 page before submission). **Tone:** Direct, technical, owner-facing. TAMU evaluators are construction PMs — they read for substance.

To

SSC Services for Education Attn: Joelle Shidemantle, SSC Project Manager Re: **Solicitation 2025-06813 — Harrington Education Center Lab 303 Renovation**

From

RK Residential Homes and Commercial Constructions, LLC dba Blue Print Constructs 16283 Willowick Ln Frisco, TX 75033 (469) 213-1838 | contactus@blueprintconstructs.com | <https://www.blueprintconstructs.com> Texas Comptroller Taxpayer ID: 32082600456 TX HUB Cert (if applicable): VID 1874292998900 — EXPIRED 2024-08-31 per source cert; user to confirm renewal Federal EIN: 87-4292998

Date

[USER TO FILL: submission date — target 2026-06-09 for hand-delivery]

1. Statement of intent

RK Residential Homes and Commercial Constructions, LLC dba Blue Print Constructs is pleased to submit this Competitive Sealed Proposal for the renovation of the **Harrington Education Center Lab 303** (Texas A&M University, Bldg 0435, College Station, TX). We acknowledge the Notice of Project dated 2026-05-08 and any addenda issued through the proposal due date (addenda received and acknowledged: [USER TO FILL: list addenda # / "none received as of submission"]).

2. Project understanding

Lab 303 is a **science education classroom / laboratory** in the Harrington Education Center Office Tower on TAMU's College Station campus. Based on the Notice and on typical TAMU System single-room educational lab renovations, we understand the scope to include:

- Selective interior demolition of existing finishes, casework, and ceiling
- New finishes (LVT and/or chemical-resistant sheet vinyl flooring, 4" rubber base, painted GWB walls, suspended acoustical ceiling)
- Lab-grade casework with phenolic-resin or epoxy-resin work surfaces
- MEP modifications — lighting + controls retrofit, branch wiring for lab benches, HVAC diffuser/grille relocation and TAB rebalancing, plumbing modifications for lab fixtures

- Lab utility coordination — [PENDING e-BUILDER ACCESS: confirm whether scope includes DI water, lab gas, vacuum, compressed air, fume hood exhaust, eye-wash/safety shower]
- Technology infrastructure coordination — low-voltage pathway (conduit, J-boxes, ring-and-string) with TAMU Technology Services providing cabling and termination
- Coordination with TAMU Environmental Health & Safety for any chemical / biological / radiological clearance prior to demo, EHS-controlled shutdown windows for fire-alarm and sprinkler work, and active-occupancy dust containment for adjacent rooms

We will perform all work in compliance with the TAMU System Uniform General Conditions and Supplementary General Conditions [PENDING e-BUILDER ACCESS: confirm current TAMU SGC revision], IBC 2021 (or current adopted edition), the Texas Accessibility Standards (TAS), and OSHA 29 CFR 1926.

3. Why us

[USER TO FILL – pick 3-5 of the following themes that apply to the firm, then put concrete supporting bullets under each]

- **Right-sized GC for a single-room educational renovation.** Large GCs treat sub-\$500K renos as nuisance work. We make them our core practice. [USER TO FILL: cite firm's typical project-size band and # of similar single-room renos delivered in the last 24 months]
- **TAMU System / Texas higher-ed past performance.** [USER TO FILL: name 1-3 prior TAMU System / TX higher-ed projects, ideally with owner contact and completion-date data – see 04-past-performance.md]
- **Lab-specific technical depth.** Our team has executed renovations on active university labs with shared utility infrastructure, coordinated EHS shutdown windows, and managed dust/vibration containment for sensitive adjacent equipment.
- **HUB Subcontracting Plan competence.** We will meet or exceed the applicable statewide ~21.1% special-trade construction HUB goal (or the project-specific goal published with the CSP package, whichever is higher) and submit a fully documented good-faith-effort binder.
- **Bonding capacity headroom.** Single-project capacity of [USER TO FILL: \$X amount], with aggregate capacity reserved against the projected \$170K–\$250K bid envelope — bonding-agent letter included with this proposal.

4. Summary of price

Item	Amount
Base Lump-Sum Proposal Price	\$(USER TO FILL – pulled from 10-price-proposal.md final number)

Owner Contingency Allowance (if specified by CSP)	[\$[PENDING e-BUILDER ACCESS: confirm if CSP form requires a carried allowance line]
Total Proposed Contract Sum	[\$[USER TO FILL]]

Unit prices and alternates are submitted on the TAMU CSP Pricing Proposal Form [PENDING e-BUILDER ACCESS: confirm form layout]; the table above is reproduced for reviewer convenience.

5. Team summary

- **Project Executive:** [USER TO FILL: name, title]
- **Project Manager:** [USER TO FILL: name, years of experience, lab/educational reno project count]
- **Project Superintendent:** [USER TO FILL: name, OSHA 30 date, years on TAMU System / TX higher-ed sites]
- **Safety Lead:** [USER TO FILL: name, OSHA 30 + CHST/CSP credential if held]

Detailed bios and project lists in 03-project-team.md.

6. Schedule summary

- **Notice to Proceed assumed:** [PENDING e-BUILDER ACCESS: confirm anticipated NTP from CSP package] (the Notice lists Project Start as "TBD")
- **Substantial completion:** [X] calendar days from NTP – see 05-schedule-narrative.md for the trade-sequenced Gantt. We have planned around the TAMU academic-calendar window and EHS shutdown availability.
- **Final completion + closeout:** [X+30] calendar days from NTP

7. Bonds + insurance

- **Bid Bond — 5% of proposal price** on TAMU System form, payable to the Board of Regents of The Texas A&M University System (per Tex. Gov't Code Ch. 2253 pattern; [PENDING e-BUILDER ACCESS: confirm exact bond form]). Original attached.
- **Performance + Payment Bond** commitment letters — included; bonding agent: [USER TO FILL: bonding agent name + AM Best rating].
- **Commercial General Liability, Auto, Workers Comp, Umbrella ACORDs** — included, naming TAMU System as additional insured with waiver of subrogation, limits confirmed against [PENDING e-BUILDER ACCESS: TAMU SGC Article 5]. Insurance broker: [USER TO FILL].

8. Acknowledgments

- We acknowledge the Notice of Project dated 2026-05-08 and the e-Builder Public Landing CSP package and all addenda issued through **[USER TO FILL: date of final addendum check]**.
- We acknowledge the HUB Subcontracting Plan requirement and have submitted our completed HSP as a separate document with this proposal (see 09-hsp-form-fill-guide.md and the bound HSP exhibit).
- We acknowledge the public proposal opening at SSC Facilities Services Conf Rm 204 (and Teams link) on 2026-06-10, 2:30 PM CT.

9. Open assumptions + clarifications

We submit this proposal subject to the assumptions and clarifications listed in 02-technical-approach.md § F — most notably regarding lab-utility scope, hazardous-materials clearance, EHS shutdown-window availability, and working-hours envelope. We have not added unsolicited value-engineering deductions; any post-award refinements are noted in the cover memo, not the priced base bid.

Signed:

[USER TO FILL – wet-ink signature, blue ink per TAMU System pattern]

[USER TO FILL: signer's printed name] [USER TO FILL: signer's title – typically President, VP, or authorized officer with proposal-binding authority] [USER TO FILL: date]

02 — Technical approach

Page target: 2–4 pages when typeset. **Cross-references:** ../04-scope-of-work.md (trade-by-trade), ../07-risk-register.md (R-01..R-12), 05-schedule-narrative.md (Gantt), 06-quality-control-plan.md (3-phase QC), 07-safety-plan.md (OSHA + EHS).

A. Project understanding

The Harrington Education Center Lab 303 Renovation is a **single-room renovation of an active educational laboratory space** at **540 Ross Street, Harrington Tower (Bldg #0435)** on TAMU's College Station campus. The project is designed by **Patterson Architects** (PA Project No. 2605, Bryan, TX) with MEP by **River MEP, LLC** (Navasota, TX). Drawings are **Issued for Construction, dated 5/7/2026** — 10 sheets total (A0.1, A0.2 TAS, A0.3 TAS, A2.1 Floor Plans, A2.2 Ceiling Plan & Details, MEP1.0 MEP Specifications, M1.1 Mechanical Plan, E1.1 Electrical Demo, E1.2 Electrical Plans, P1.1 Plumbing Plans).

Our project understanding, post-portal-pull (2026-05-23):

1. **Interior-only scope** — no structural modifications, no envelope work, no roof. Slab and overhead structure stay. Spec Divisions 03 (Concrete), 04 (Masonry), 05 (Metals), 31 (Earthwork), 32 (Exterior), 33 (Utilities) all explicitly **NOT USED**.
2. **Single room** — Lab 303 only. Drawings cover only Lab 303 in Harrington Tower.
3. **Active-occupancy condition** — Harrington Tower is an operating academic tower. Spec Section 01 41 00 "General Requirements for Renovation Work" (5 pp) governs renovation procedures; Section 01 50 00 (9 pp) governs temporary facilities. Adjacent rooms continue normal use during construction. Dust containment, vibration management, after-hours scheduling for noisy or odor-generating work, and SSC/TAMU-coordinated shutdown windows are required.
4. **No fume hood / no lab equipment in GC scope** — Spec Division 11 "Equipment" is **NOT USED**. The "lab" portion of the program is a teaching classroom-lab with lab sinks (per P1.1) but not a wet/heavy chemistry lab. This **rules out the high-tier price envelope** and substantially derisks the schedule (no 12–16 week fume hood lead time on the critical path).
5. **No new doors or hardware** — Spec Division 08 "Doors and Windows" is **NOT USED**. Existing classroom door, frame, and hardware remain.
6. **No casework spec in project manual; casework appears to be a deferred design or H2I sub-bid (Sub-06 file, posted 5/13 on the portal, currently blocked at our end by network policy — re-share requested via outreach 01).** Division 06 in the project manual is limited to 06 10 00 Rough Carpentry (5 pp). A casework allowance is carried in the price; refined upon H2I file retrieval.
7. **Asbestos handling is procedurally scoped** in Spec Section 02 26 23 (15 pp). We assume a clearance certificate is in place or that asbestos abatement, if encountered, proceeds per that procedure. A modest asbestos abatement allowance (\$3K–\$10K) is carried in the base bid.
8. **Owner-furnished items** — TAMU Technology Services furnishes and installs all low-voltage cabling, terminations, jacks, patch panels, and active gear. GC scope ends at the pathway (conduit, J-box,

ring-and-string). AV equipment is OFOI per the typical TAMU pattern.

B. Phased work plan (60–90 calendar days, single-shift baseline)

Phase 0 — Pre-construction (NTP through Day 14)

- Notice to Proceed + contract execution (per SSC UGSC Section 00 72 00)
- Pre-construction meeting with SSC PM (Joelle Shidemantle, Joelle.Shidemantle@sscserv.com, (979) 286-3497), A/E (Fred Patterson, Patterson Architects), MEP (George, River MEP LLC), TAMU EHS, TAMU Facilities, TAMU Technology Services
- TAMU EHS clearance review for Bldg 0435 Lab 303 per Spec Section 02 26 23 Asbestos Assessment procedure
- Submittal package per Spec Section 01 33 00 (3 pp) and 01 34 00 (9 pp Shop Drawings, Product Data and Samples): casework shop drawings (per H2I or alternate sub), lab fixture cut sheets, lighting cut sheets, low-voltage pathway routing, paint colors against TAMU finish standard, MEP shop drawings
- Long-lead order placement (see § E)
- Site logistics plan: dumpster placement (TAMU-approved location, coordinated with Joelle), loading-dock route, walk-off matting, dust-containment perimeter
- Site signage and life-safety walk

Phase 1 — Demolition (Day 15–25)

- Establish negative-pressure dust containment at room perimeter; isolate corridor and adjacent-room HVAC returns
- EHS-coordinated 2-week-noticed shutdowns for: fire alarm devices in Lab 303 (smoke detectors, strobes); sprinkler branch line serving Lab 303; any plumbing branches shared with adjacent labs
- Selective demolition: existing finishes (flooring + base, paint, ceiling tile), casework + countertops, fixtures slated for removal, lighting, MEP devices and rough-in
- After-hours scheduling for any noisy or odor-generating tasks (typically 5 PM – 11 PM weekdays, full-day Saturday/Sunday as agreed with Joelle)
- Haul-off to TAMU-approved dumpster
- Phase 1 closeout walk with TAMU EHS, A/E, owner

Phase 2 — Rough-in + MEP modifications (Day 20–45, overlap with Phase 1 end)

- Metal-stud framing for any new or furred partitions (if scope)

- Electrical rough-in: branch wiring for lab benches (dedicated 20A circuits, GFCI within 6' of any sink), classroom lighting controls (occupancy + daylight + dimming where applicable), low-voltage pathway (conduit, J-boxes, ring-and-string for TAMU Tech Services cable pull)
- Plumbing rough-in per P1.1: lab fixture supply + waste piping, eye-wash + safety shower rough-in (if shown on P1.1)
- HVAC modifications per M1.1 + MEP1.0: diffuser/grille relocation per new RCP (A2.2), VAV box retrim. **No fume hood scope** — Spec Division 11 NOT USED.
- Fire suppression: sprinkler head relocation per new ceiling layout. **No Div 21 spec or FP sheets in the package** — proceed via (a) deferred submittal proposed in this Technical Proposal, or (b) coordination with the existing TAMU building sprinkler vendor on T&M (NICET-certified) with EHS-coordinated shutdown windows.
- Inspections: in-wall electrical inspection, plumbing rough-in inspection, fire suppression hydrostatic test, framing inspection

Phase 3 — Finishes (Day 40–70)

- Drywall hang + finish (level 4 typical for paint-grade) per Spec 09 22 00
- Acoustical ceiling grid + tile install per Spec 09 51 00 (full 2x4 lay-in replacement, per A2.2)
- Painting per Spec 09 91 00 (2-coat institutional latex, low-VOC)
- Resilient flooring install per Spec 09 65 00 (single spec — type per A2.1 finish plan)
- Resilient base
- Lab casework install (per A2.1/A2.2 details + H2I Sub-06 specifics once retrieved)
- Plumbing fixture set per P1.1 (lab sinks, faucets, eye-wash + safety shower if shown)
- Electrical trim per E1.2 (devices, plates, light fixtures, controls programming)
- Low-voltage pathway termination; TAMU Tech Services cable pull and termination
- **No new doors / hardware** — Division 08 NOT USED; existing door stays
- Specialties per Spec 10 14 00: room signage (ADA-compliant per A0.2/A0.3 TAS sheets)

Phase 4 — Closeout (Day 65–90)

- Test, Adjust, Balance (TAB) report for HVAC per MEP1.0
- Fire alarm + sprinkler reconnect, full system test, EHS sign-off
- Punch list walk with A/E, SSC PM, TAMU Facilities per SSC UGSC Article 12
- Punch list completion per Spec Section 01 77 00 Closeout Procedures
- Final cleaning (lab-grade — no construction residue on bench tops)
- O&M manuals, attic stock, training per Spec Section 01 78 23 (Operation and Maintenance Data, 4 pp) + Section 01 78 20 (Facilities Management Data, 11 pp)

- As-built drawings
- TAMU EHS final clearance
- Substantial Completion + **30-day fixed Final Completion window** (per CSP §00 42 13); final payment + retainage release per SSC UGSC Article 10 + 12

C. Lab-specific considerations (the pain-points worth pricing for)

This is the differentiator. Most GCs treat single-room labs like classroom finish work and then get burned on the lab utilities. We don't.

1. **Shared utility infrastructure with active adjacent labs.** Lab 303 likely shares an exhaust stack, return-air plenum, lab-gas main, DI water riser, or acid waste branch with adjacent labs that remain in operation. Any cutover that affects an active adjacent lab requires PI-coordinated scheduling — often a single 4-hour window outside normal lab use. We will identify these shared systems in pre-construction and schedule cutovers explicitly.
2. **EHS shutdown windows.** Fire alarm, sprinkler, plenum work, and any plumbing branch tied to an active lab requires 2-week-noticed shutdown windows coordinated with TAMU EHS. We do not bid these as same-day-flex work; the schedule carries explicit shutdown-window placeholders.
3. **Hot-work permitting.** Soldering, brazing, welding, cutting in or around an active academic building requires TAMU EHS hot-work permits. We will incorporate the TAMU EHS hot-work procedure into our Phase 2 / Phase 3 plan.
4. **Legacy chemical contamination in existing dressing/lab spaces.** Older university lab rooms may have legacy chemical residue on bench tops, in sink traps, in fume hood interiors, or on the floor (mercury splashes, perchloric acid residue near old hoods). We will assume the room is **not** clear of legacy chemical residue and coordinate with TAMU EHS for any pre-demo wipe-down / clearance step. If TAMU EHS surveys the room and clears it, this allowance drops to zero.
5. **Ventilation isolation during demo.** Demo dust and odor cannot enter the adjacent-lab return-air plenum. We will install temporary plenum dampers or seal the existing return grilles in Lab 303 throughout demo and rough-in. This is a typical missed scope item by inexperienced bidders.
6. **Lab equipment owner-furnished, contractor-installed (OFCI) vs owner-furnished, owner-installed (OFOI).** TAMU labs usually have a mix. Fume hoods and casework-mounted instruments are sometimes OFCI; balance tables and bench-top instruments are usually OFOI. Pre-construction submittal will explicitly enumerate this split per the lab equipment schedule [PENDING e-BUILDER ACCESS: lab equipment schedule].
7. **TAMU Technology Services scope split.** GC scope ends at the low-voltage pathway. Cable, jacks, termination, patch panels, and active gear are TAMU Tech Services. We will coordinate Tech Services' cable pull window with our finishes phase to avoid ceiling re-opening after install.
8. **Lab fixture trim premium.** Lab fixtures (gooseneck spouts, lab-grade faucets, eye-wash bowls, integral fixture trim plates) cost roughly 50–80% more than commercial-grade fixtures. We have priced lab-grade fixture trim where the program calls for it; we have not assumed any "value engineer to commercial-grade" trim swap.

D. Coordination with the academic calendar

The CSP package leaves Project Start and Substantial Completion as "TBD" — proposers select their own Substantial Completion duration in CSP Part 1 (Section 00 42 13), and this is scored at 10% of the evaluation per CSP §00 21 00 ¶11.2. Final Completion is fixed at 30 calendar days after Substantial Completion.

Our proposed duration: **70 calendar days from NTP to Substantial Completion**, plus 30 calendar days to Final Completion (100 calendar days total). See 05-schedule-narrative.md for the trade-sequenced Gantt with EHS-shutdown windows and casework lead time built in.

Most likely academic-calendar windows:

- **Summer-to-fall window:** NTP early-to-mid June, Substantial Completion ~late-August (start of fall semester) — 70-day commitment fits comfortably.
- **Fall-to-spring window:** NTP late October, Substantial Completion ~mid-January (start of spring semester) — 70-day commitment fits with built-in holiday float.

E. Long-lead items + procurement plan

Item	Typical lead time	Order placement target	Risk if missed
Lab casework (per A2.1/A2.2 + H2I Sub-06 specifics)	8–10 weeks fabricated; 10–12 weeks with custom configuration	Day 5 post-NTP	Schedule slip on Phase 3 finishes
Lab work tops (resin / chemical-resistant)	8–10 weeks	Day 5 post-NTP	Same
Lab fixtures (faucets, gooseneck spouts, eye-wash + safety shower)	6–8 weeks	Day 10 post-NTP	Manageable; carry stock alternates
LED lighting fixtures + controls per E1.2	4–6 weeks	Day 5 post-NTP	Manageable

Sprinkler heads (recessed, white-cover) — coordinated with existing TAMU sprinkler vendor	2–4 weeks	Day 15 post-NTP	Minor
HVAC diffusers / grilles + VAV retrim per M1.1	4–6 weeks	Day 5 post-NTP	Manageable

No fume hood on critical path — Division 11 NOT USED in spec → eliminates the historical biggest single-room lab schedule risk. The binding lead-time constraint is now casework (8–12 weeks), which sets the **earliest Substantial Completion at ~70 days** for a clean NTP-to-finishes sequence.

F. Assumptions + clarifications

We submit this proposal subject to the following assumptions. If any prove false at the pre-construction meeting or during construction, the resulting scope adjustment will be handled per the change-order procedure in SSC UGSC Article 11 (Changes).

1. **Room area** measured from drawing A2.1 ([**USER TO FILL: actual SF after Bluebeam measure**]); price scaled accordingly.
2. **No structural modifications** — confirmed by spec (Divs 03–05 NOT USED).
3. **No envelope work** — confirmed by spec (Divs 31–33 NOT USED).
4. **Asbestos handling per Spec Section 02 26 23**, with a modest abatement allowance (\$3K–\$10K) in the base bid. If the room is fully cleared by TAMU EHS prior to NTP, the allowance returns to the owner via change order.
5. **Lab utility scope** per drawings (P1.1 plumbing, M1.1 mechanical, MEP1.0 specifications). **No fume hood** — Div 11 NOT USED. DI water / lab gas / acid waste / vacuum only if shown on P1.1 (carried per the takeoff).
6. **No new doors or hardware** — Division 08 NOT USED; existing door + frame + hardware remain.
7. **Casework scope** per A2.1/A2.2 details and the H2I Sub-06 file (currently pending re-share from Joelle); carried as a \$20K–\$60K allowance in the base bid pending H2I retrieval.
8. **Fire suppression** handled either as deferred-submittal (a) or via the existing TAMU building sprinkler vendor on T&M (b); modest allowance (\$1K–\$5K) in the base bid.
9. **Working-hours envelope** assumed to be 7 AM – 5 PM weekdays for routine work; after-hours (5 PM – 11 PM weekdays, Saturday and Sunday) for any noisy or odor-generating tasks. After-hours premium labor reflected in the base bid.
10. **EHS shutdown windows** assumed to be available within 2 weeks of request, in 4-hour blocks, with 2-week notice.

11. **TAMU Technology Services** furnishes and installs all low-voltage cabling, jacks, terminations, patch panels, and active gear. GC scope ends at the pathway.
12. **Substantial Completion** targeted at **70 calendar days from NTP**; Final Completion + closeout at **100 calendar days** (30-day fixed window per CSP §00 42 13).
13. **Owner-furnished items** assumed to include all lab instruments, balances, AV (projector, display, ceiling speakers, microphone arrays).
14. **Patterson Architects + River MEP RFI turnaround** assumed at 5 business days. Slower turnaround will be flagged.
15. **Proposal valid 90 calendar days** post-submittal per CSP §00 42 13.
16. **No bid bond required** (CSP §00 42 13 does not call for one). Performance + Payment bonds will be furnished at award per Spec Sections 00 61 13 + 00 61 14.

03 — Project team + key personnel

Page target: 2–3 pages when typeset. All personnel sections below are templates with **[USER TO FILL]** markers. Do not invent personnel data — TAMU evaluators verify references and credentials.

A. Org chart

TAMU Project Owner (Joelle Shidemantle, SSC PM) ■ ■ (Owner-to-GC interface) ▼ **[USER TO FILL: Project Executive]** ■ ▼ **[USER TO FILL: Project Manager (PM of Record)]** ■ ■ ■ ▼ ▼ ▼ **[USER TO FILL: [USER TO FILL: [USER TO FILL: Project Safety Lead]** Project Superintendent] Estimator] ■ ■■ Demolition sub ■■ Framing / drywall sub ■■ Flooring sub ■■ Painting sub ■■ Acoustical ceiling sub ■■ Lab casework sub ■■ Electrical sub (lab-experienced) ■■ HVAC sub (lab-experienced) ■■ Plumbing sub (lab-experienced) ■■ Fire suppression sub (NICET-cert) ■■ Lab utility specialty sub (if scope) ■■ Low-voltage pathway (coordinate with TAMU Tech Services)

External interfaces (not part of GC org chart but referenced throughout the project):

- **Fred Patterson** — Patterson Architects (A/E of record); RFI + submittal routing
- **Patty Winkler** — TAMU HUB Operations; HSP monthly PAR reporting
- **TAMU Environmental Health & Safety (EHS)** — hazmat clearance, shutdown windows, hot-work permits, final EHS sign-off
- **TAMU Facilities Services** — utilities coordination, dumpster placement, loading-dock access
- **TAMU Technology Services** — low-voltage cabling + termination

B. Key personnel — Project Executive

Field	Value
Name	[USER TO FILL]
Title	[USER TO FILL – typically VP Construction, Director of Operations, or Principal]
Years with firm	[USER TO FILL]
Years in construction industry	[USER TO FILL]

Role on this project	Executive accountability; client interface for any escalation; signature authority on change orders above [USER TO FILL: \$ threshold]
Time commitment	~5–10% throughout project
Relevant credentials	[USER TO FILL: LEED AP, CCM, etc.]
Relevant prior projects	[USER TO FILL: 1-2 sentences naming similar institutional / educational reno engagements]

C. Key personnel — Project Manager (PM of Record)

This is the role TAMU evaluators care most about. A strong PM-of-record bio is worth more on technical-approach scoring than 5 extra pages of process boilerplate.

Field	Value
Name	[USER TO FILL]
Title	Project Manager
Years with firm	[USER TO FILL]
Years in construction industry	[USER TO FILL]
Role on this project	Single point of accountability for the project. Owns schedule, budget, RFIs, submittals, change orders, subcontractor coordination, client communication. Reports to Project Executive; reports out to SSC PM (Joelle Shidemantle) and A/E (Patterson Architects).
Time commitment	~40–60% throughout project (heavier during preconstruction and Phase 4 closeout)
Relevant credentials	[USER TO FILL: PMP, CCM, OSHA 30, LEED AP, etc.]
Education	[USER TO FILL]

Similar prior projects (≥ 3 , ideally with university lab or science classroom work)	[USER TO FILL: row per project – project name, owner, value, completion year, GC role]
--	---

Project-PM narrative paragraph **[USER TO FILL: 4–6 sentence narrative explaining why this PM is the right fit for a single-room TAMU lab reno – touch on (a) educational / institutional experience, (b) lab-specific experience, (c) Texas state-CSP procurement familiarity, (d) HUB / HSP submission familiarity, (e) prior TAMU System work if any].**

D. Key personnel — Project Superintendent

Field	Value
Name	[USER TO FILL]
Title	Project Superintendent
Years with firm	[USER TO FILL]
Years in construction industry	[USER TO FILL]
Role on this project	Day-to-day site lead. Subcontractor scheduling, daily safety briefings, quality control inspections (Phase 1 prep-work, Phase 2 in-progress, Phase 3 punch-list per the 3-phase QC plan in 06-quality-control-plan.md), daily reports, materials staging, dumpster + lay-down area management, coordination with TAMU EHS for shutdown windows, hot-work permit holder.
Time commitment	100% on site during all on-site construction phases
Relevant credentials	OSHA 30 (date: [USER TO FILL]), [USER TO FILL: CHST, STSC, lab-specific safety training, EHS-related certifications]
Similar prior projects (≥ 3)	[USER TO FILL]

Superintendent narrative paragraph **[USER TO FILL: 4–6 sentences on (a) occupied-building experience, (b) Texas higher-ed / TAMU experience, (c) lab-specific site management, (d) coordination with university EHS / Facilities counterparts].**

E. Key personnel — Safety Lead

Field	Value
Name	[USER TO FILL]
Title	Safety Lead / Corporate Safety Manager
Role on this project	Project-specific safety plan author (see 07-safety-plan.md); weekly safety audits; serves as TAMU EHS interface; OSHA-incident reporting; coordinates lab-specific hazard procedures (chemical, electrical, plenum, after-hours egress, hot work).
Time commitment	~5–10% throughout project; on-site for kickoff, phase transitions, any incident
Relevant credentials	OSHA 30 (date: [USER TO FILL]), [USER TO FILL: CHST, CSP, ASP, lab-experienced safety training, university EHS coordination experience]
Firm EMR (most recent 3 years)	[USER TO FILL: year – EMR / year – EMR / year – EMR] — strong scores (≤ 1.0 , ideally ≤ 0.85) are competitive on TAMU scoring
Firm OSHA recordables (most recent 3 years)	[USER TO FILL]
OSHA citations (most recent 5 years)	[USER TO FILL – list or "none"]

F. Key personnel — Project Estimator

(Often present at pre-construction meeting and at any change-order pricing event.)

Field	Value
Name	[USER TO FILL]
Years in construction industry	[USER TO FILL]

Role on this project	Owns the takeoff, sub buyout, change-order pricing, monthly cost-to-complete reporting. Not on-site full-time.
----------------------	--

G. Subcontractor list

TAMU CSPs vary on whether a subcontractor list is required at proposal or only at award [PENDING e-BUILDER ACCESS: confirm CSP Instructions to Proposers section]. If required at proposal, populate the table below with named subs:

Trade	Subcontractor name	HUB-certified?	T	T	Relationship
			H	H	history
			Cert	Cert	
			#	#	
Demolition	[USER TO FILL]	[Y/N]	[Y]	[Y]	[# prior projects]
Framing / drywall	[USER TO FILL]	[Y/N]			
Flooring	[USER TO FILL]	[Y/N]			
Painting	[USER TO FILL]	[Y/N]			
Acoustical ceilings	[USER TO FILL]	[Y/N]			
Lab casework	[USER TO FILL]	[Y/N]			
Electrical (lab-exp)	[USER TO FILL]	[Y/N]			
HVAC (lab-exp)	[USER TO FILL]	[Y/N]			
Plumbing (lab-exp)	[USER TO FILL]	[Y/N]			
Fire suppression	[USER TO FILL]	[Y/N]			
Lab utility specialty	[USER TO FILL – or "N/A if scope absent"]	[Y/N]			
Low-voltage pathway	[USER TO FILL]	[Y/N]			

If the CSP package only requires a sub list at award, this exhibit may be replaced with a narrative committing to a sub-list submittal within 5 business days of award.

H. Self-performing scope (cross-reference HSP)

The firm self-performs **[USER TO FILL: list – typically project supervision / general conditions, possibly carpentry/demo if in-house]**. Self-performed scope is removed from the HUB Subcontracting Plan denominator; see 09-hsp-form-fill-guide.md § "Self-Performing Justification."

I. Resume + reference exhibits

Attach as separate exhibits (one PDF per key person, 1–2 pages each):

- Exhibit T-1: Project Executive resume
- Exhibit T-2: Project Manager resume
- Exhibit T-3: Project Superintendent resume
- Exhibit T-4: Safety Lead resume

Past-performance references — see 04-past-performance.md.

04 — Past performance + references

Past-performance picks for this bid (from *firm/firm-profile.json* → *past_project_selection_rules.tamu-harrington-2025-06813*):

1. **Hindu Temple of Southlake** — North Texas Hindu Heritage Society (nonprofit religious owner); ≈10,700 SF Assembly A-3 (Place of Religious Worship) renovation at 595 South Kimball Avenue, Southlake, TX 76092; owner-side project # 2024-024; scope: demolition + finishes + phenolic toilet partitions + partition framework; drawings dated 2025-06-20 (PDF), updated 2025-09-12 (Arch + Structural); in execution per material quote 2025-10-30; delivery method: negotiated lump-sum (owner direct); role: GC. Final contract value: **[USER TO FILL — not in BPC source files]**. Reference contact: **[USER TO FILL — North Texas Hindu Heritage Society POC]**.
2. **Holiday Inn (Hall Park, Frisco)** — Holiday Inn franchisee (hospitality owner); commercial renovation at Hall Park, Frisco, TX; role: GC. Contract value, scope detail, and completion date: **[USER TO FILL — cited by name in BPC/Rocky Business Profile.docx but no project-folder source on OneDrive; reconstruct from project records]**. Reference contact: **[USER TO FILL — Holiday Inn Hall Park property POC]**.
3. **250–500+ single-family-home portfolio (cumulative since 2022)** — executed primarily as a specialty trade sub through GC partners That 1 Painter, Touchmark, Bridge View Build, and Hill Design Build across the DFW metroplex; scope: interior + exterior painting, drywall (tape/bed/texture), flooring, tile, trims, roofing repairs; role: specialty sub. Reference contacts: **[USER TO FILL — named contact at each of the four featured GC partners]**.

The per-project entry templates below have been pre-filled for sections that match the standard TAMU/ASU reference-header shape. Bid workspaces with a different template shape (USACE / federal) still need the user to copy the recommended pick data manually into each Project N section.

Page target: 1–2 pages when typeset. **Sourcing rule:** every entry below must reflect actual completed projects with verifiable owner-side references. TAMU evaluators do call references. Do not embellish. **Selection priority:** (1) prior TAMU System / TAMU campus work — strongest signal; (2) other Texas higher-ed (UT System, TTU System, UH System, TSU, etc.); (3) Texas K-12 lab / science classroom work; (4) other institutional renovation of similar dollar value and scope shape.

A. Reference 1 — Hindu Temple of Southlake

Hindu Temple of Southlake — North Texas Hindu Heritage Society (nonprofit religious owner); ≈10,700 SF Assembly A-3 (Place of Religious Worship) renovation at 595 South Kimball Avenue, Southlake, TX 76092; owner-side project # 2024-024; scope: demolition + finishes + phenolic toilet partitions + partition framework; drawings dated 2025-06-20 (PDF), updated 2025-09-12 (Arch + Structural); in execution per material quote 2025-10-30; delivery method: negotiated lump-sum (owner direct); role: GC. Final contract value: **[USER TO FILL — not in BPC source files]**. Reference contact: **[USER TO FILL — North Texas Hindu Heritage Society POC]**.

Source: Hindu Temple of South Lake/ on OneDrive.

Field	Value
Project name	[USER TO FILL]
Owner / agency	[USER TO FILL]
Owner POC (name, title, current email, current phone)	[USER TO FILL – verify the contact is still in that role; if they've moved on, list current successor too]
A/E firm	[USER TO FILL]
Location	[USER TO FILL]
Contract type	[USER TO FILL – CSP / Job Order Contract / IDIQ task / Design-Bid-Build / etc.]
Contract value (final)	\$(USER TO FILL)
Original contract value	\$(USER TO FILL)
Change order % over original	[USER TO FILL – TAMU evaluators look for low CO % as a quality signal]
Substantial completion date	[USER TO FILL]
Original substantial completion target	[USER TO FILL]
Days early / late vs original	[USER TO FILL – on-time or early scores best]
Scope summary (3–5 sentences)	[USER TO FILL – emphasize parallels to Lab 303: single-room educational reno, lab utilities if applicable, occupied building, EHS coordination, finishes mix, lab casework, MEP coordination scope]

Why this project is relevant to TAMU Harrington Lab 303	[USER TO FILL – 2-3 sentences explicitly tying the prior project to the current bid: e.g. "same single-room educational lab reno scope; coordinated EHS shutdowns on active university campus; delivered on time and 1.2% under budget"]
---	---

B. Reference 2 — Holiday Inn (Hall Park)

Holiday Inn (Hall Park, Frisco) — Holiday Inn franchisee (hospitality owner); commercial renovation at Hall Park, Frisco, TX; role: GC. Contract value, scope detail, and completion date: [USER TO FILL — cited by name in BPC/Rocky Business Profile.docx but no project-folder source on OneDrive; reconstruct from project records]. Reference contact: **[USER TO FILL — Holiday Inn Hall Park property POC]**.

Field	Value
Project name	[USER TO FILL]
Owner / agency	[USER TO FILL]
Owner POC	[USER TO FILL]
A/E firm	[USER TO FILL]
Location	[USER TO FILL]
Contract type	[USER TO FILL]
Contract value (final)	\$(USER TO FILL)
Change order % over original	[USER TO FILL]
Substantial completion date	[USER TO FILL]
Days early / late vs original	[USER TO FILL]
Scope summary	[USER TO FILL]
Why relevant to TAMU Harrington Lab 303	[USER TO FILL]

C. Reference 3 — 250-500+ single-family-home portfolio

250–500+ single-family-home portfolio (cumulative since 2022) — executed primarily as a specialty trade sub through GC partners That 1 Painter, Touchmark, Bridge View Build, and Hill Design Build across the DFW metroplex; scope: interior + exterior painting, drywall (tape/bed/texture), flooring, tile, trims, roofing repairs; role: specialty sub. Reference contacts: **[USER TO FILL — named contact at each of the four featured GC partners]**.

Field	Value
Project name	[USER TO FILL]
Owner / agency	[USER TO FILL]
Owner POC	[USER TO FILL]
A/E firm	[USER TO FILL]
Location	[USER TO FILL]
Contract type	[USER TO FILL]
Contract value (final)	\$(USER TO FILL)
Change order % over original	[USER TO FILL]
Substantial completion date	[USER TO FILL]
Days early / late vs original	[USER TO FILL]
Scope summary	[USER TO FILL]
Why relevant to TAMU Harrington Lab 303	[USER TO FILL]

D. (Optional) Reference 4 + 5

If the CSP package requires 5 references (some TAMU CSPs do; the Notice does not specify), include two more rows in the same shape. If only 3 are required, omit.

E. Past-performance narrative (1 paragraph, framing the references)

[USER TO FILL – 4–6 sentences. Suggested arc:]

Our firm has delivered [X] institutional / educational renovations in Texas in the last [N] years, totaling \$[Y]M in contract value. We have specifically completed [Z] single-room laboratory or science-classroom renovations in occupied university or K-12 buildings during that period, with an average schedule performance of [on time / X% early] and an average change-order ratio of [X.X%] over original contract value. The three references above are the most directly comparable to the Harrington Lab 303 scope; we are prepared to provide additional references on request.

F. Safety + financial performance summary

(Often required by TAMU CSPs as a separate exhibit; cross-referenced from 03-project-team.md § E.)

Metric	Value
EMR — most recent year	[USER TO FILL]
EMR — 3-year average	[USER TO FILL]
OSHA Recordable Incident Rate (most recent year)	[USER TO FILL]
Days Away, Restricted, Transferred (DART) rate	[USER TO FILL]
Workers' Comp claims (3-year history)	[USER TO FILL]
Litigation / claim history on completed projects (3-year history)	[USER TO FILL – "none" or list]
Surety / bonding capacity — single project	\$(USER TO FILL)
Surety / bonding capacity — aggregate	\$(USER TO FILL)
Currently bonded backlog	\$(USER TO FILL)
Audited financials available on request?	[USER TO FILL – Y/N]

05 — Schedule narrative + critical path

Page target: 1 page narrative + 1 separate Gantt exhibit. **Baseline duration:** 70 calendar days Substantial Completion + 30 calendar days fixed window to Final Completion (per CSP §00 42 13) = **100 calendar days total**. Bidder-chosen, scored at **10% of evaluation** per CSP §00 21 00 ¶11.2. **Critical-path items:** lab casework lead time (8–12 weeks). **NO fume hood** — Division 11 NOT USED in spec, so the 12–16-week fume-hood lead-time risk is OFF THE TABLE. EHS shutdown-window availability is a secondary constraint.

A. Anchor dates (working assumption)

Event	Assumed date
Proposal due to TAMU	2026-06-10, 2:00 PM CT
Public proposal opening	2026-06-10, 2:30 PM CT
TAMU evaluation period	2026-06-10 to ~2026-06-30 (typical 2–3 weeks for sub-\$500K CSP)
Best-and-final / clarifications	~2026-06-30 to ~2026-07-10
Award notification (estimated)	~2026-07-15
Notice to Proceed (estimated)	~2026-07-25 to ~2026-08-01
Substantial completion target	NTP + 70 calendar days = ~2026-10-09 if NTP 2026-08-01
Final completion + closeout	NTP + 100 calendar days = ~2026-11-08

CSP confirmed (post-portal-pull 2026-05-23): there is NO fixed Substantial Completion date in the CSP package. The proposer **chooses** the duration in CSP §00 42 13 (Substantial Completion calendar days from NTP). Final Completion is **fixed at 30 calendar days after Substantial Completion**. This is the **10%-weighted "Construction Time"** criterion. Shorter is better (more points) but only if defensible by a real Gantt; padded short durations get penalized in evaluation if Patterson + River MEP flag the proposal as not credible.

B. Phased schedule summary (backwards-planned from substantial completion)

Calendar-day count from NTP. Adjust phase overlaps based on actual EHS shutdown-window availability and lab-utility cutover scheduling at preconstruction.

Phase	Days	Calendar-day span (assumed NTP 2026-08-01)	Key milestones
0 — Preconstruction	1–14	2026-08-01 to 2026-08-15	Submittals, long-lead orders, EHS coordination, hazmat survey review
1 — Demolition	15–25	2026-08-15 to 2026-08-26	Containment up; EHS shutdowns; selective demo; haul-off
2 — Rough-in (MEP + framing)	20–45	2026-08-21 to 2026-09-15	Branch wiring; plumbing rough-in; HVAC mods; sprinkler relocation; in-wall inspections
3 — Finishes (drywall, ceiling, paint, flooring, casework)	40–70	2026-09-10 to 2026-10-09	GWB hang/finish; ACT install; paint; flooring; lab casework + tops; fixture set; electrical trim; low-voltage pathway termination + TAMU Tech Services cable pull
4 — Closeout	65–100	2026-10-05 to 2026-11-08	TAB report; fire alarm + sprinkler retest; punch list; final cleaning; O&M + training; EHS final sign-off; substantial completion + acceptance

Substantial completion: Day 70 (~2026-10-09).

(Detail per Phase: see 02-technical-approach.md § B.)

C. Critical path

The critical path runs through two sequential constraints (fume-hood eliminated by spec):

Lab casework fabrication. 8–12 weeks from approved shop drawings → delivered to site.

Casework shop drawings must be submitted by Day 7 post-NTP, approved by Day 14, fabricated by Day 70, installed by Day 75. **This is the binding constraint** for our 70-day Substantial Completion commitment. H2I Sub-06 specifics (pending re-share from Joelle) confirm whether (a) a single specified casework manufacturer is committed (binding to their lead time) or (b) competitive subs are allowed (~2 weeks of additional shopping float).

EHS shutdown-window availability. 2-week notice + 4-hour blocks for fire alarm, sprinkler, and shared-utility cutovers. EHS coordination starts at preconstruction; shutdown windows are scheduled by Day 14 for Phase 1 demo work. Asbestos handling per Spec 02 26 23 is procedural (no abatement scope unless EHS finds material in the room) — modest float is built in for hazmat-survey review.

Float: 30 calendar days between Day 70 Substantial Completion and Day 100 Final Completion — this is the CSP-fixed window per §00 42 13 and is used for punch list, TAB, EHS final clearance, O&M closeout, and minor finishes touch-up.

D. Long-lead items (procurement plan)

Cross-reference 02-technical-approach.md § E. Summary:

Long-lead item	Lead time	Order target (days post-NTP)
Lab casework (per A2.1/A2.2 + H2I Sub-06)	8–12 weeks	Day 5
Lab work tops (chem-resistant)	8–10 weeks	Day 5
~~Fume hood~~	—	NOT IN SCOPE — Div 11 NOT USED
Lab fixtures (faucets, gooseneck, eye-wash, safety shower)	6–8 weeks	Day 10
~~Specialty doors~~	—	NOT IN SCOPE — Div 08 NOT USED
LED lighting + controls per E1.2	4–6 weeks	Day 5

HVAC diffusers / grilles + VAV retrim per M1.1	4–6 weeks	Day 5
Recessed sprinkler heads (coord. with existing TAMU sprinkler vendor)	2–4 weeks	Day 15

E. Coordination dependencies (off the critical path but worth calling out)

Dependency	Owner	Risk if late
TAMU EHS hazardous-materials clearance for Lab 303 (per Spec 02 26 23)	TAMU EHS	Phase 1 demo slip; ~5–10 calendar days
EHS shutdown approval for fire alarm + sprinkler	TAMU EHS	Phase 2 + Phase 4 slip; ~3–5 calendar days each event
Patterson Architects RFI turnaround (assumed 5 business days)	Patterson	Cumulative ~5–10 calendar days
River MEP LLC (George) RFI turnaround (assumed 5 business days)	River MEP	Cumulative ~5–10 calendar days
TAMU Technology Services cable pull window	TAMU TS	Phase 3 finishes hold; ~3–7 calendar days
Patterson + River MEP submittal review (assumed 10 business days)	A/E	Phase 0 to Phase 2 hold
Lab equipment owner-furnished delivery (if OFCI)	TAMU	Phase 3 hold pending equipment receipt
H2I Sub-06 file (currently re-share pending from Joelle)	SSC PM	Day 5 casework order target slips

F. Schedule risks (cross-reference [../07-risk-register.md](#))

Risk	Schedule impact	Mitigation in this schedule
R-03 — hidden lab utilities	+5–15 calendar days if DI water / lab gas added post-bid (fume hood not in scope)	Float in Phase 3
R-06 — thin drawing package, RFI churn	+5–10 calendar days cumulative	5-day RFI cadence; PM staffing buffer; River MEP + Patterson both available
R-07 — after-hours work premium	Schedule impact neutral (work happens off-hours); cost impact only	Already priced
R-08 — existing-conditions surprises (asbestos finding)	+5–15 calendar days	Asbestos handling per Spec 02 26 23; modest allowance + float in Phase 1
R-11 — Substantial Completion slip	Per SSC UGSC Article 9 (Time of Performance) liquidated damages	Defensible 70-day baseline; 30-day fixed Final Completion window absorbs minor slips
R-12 — A/E RFI slow	+5–10 calendar days	Establish 5-day cadence at kickoff; escalate to Joelle + Cherise Toler on slip
R-NEW — H2I Sub-06 missing	+2 weeks on casework order if not re-shared in next 7 days	Outreach to Joelle (see ../outreach/01-...md) requesting Zscaler-blocked file

G. Schedule exhibit

A separate Gantt chart exhibit ([exhibit-G-1-gantt.pdf](#) or similar; tool-agnostic — MS Project, Smartsheet, or hand-drawn) must accompany this narrative. The Gantt shows:

- Calendar-day axis from Day 1 (NTP) to Day 100 (final completion)
- One swimlane per trade
- Critical path highlighted (casework + fume-hood-if-scope)
- Phase boundaries at Day 14, Day 25, Day 45, Day 70, Day 100
- Long-lead procurement bars (typically off-site, shown as separate row)

- EHS shutdown windows shown as red event markers
- Owner-decision points (submittal approval, RFI responses, lab equipment delivery if OFCI) shown as diamond markers
- Substantial completion and final completion shown as flag markers

[USER TO FILL: produce the Gantt in MS Project or Smartsheet, export to PDF, attach as Exhibit G-1.]

06 — Quality control plan

Page target: 1–2 pages when typeset. **Approach:** Three-phase inspection (prep / in-progress / completion) per the US Army Corps of Engineers "3-phase QC" pattern that TAMU System UGSC has historically required. Article reference: **[TBD per CSP package – typically TAMU SGC Article 7 "Quality of Work" / "Contractor Quality Control" or equivalent. The 2010 TFC UGSC base (in the Angelo State packet Attachment C) carries this in Article 7 and Article 8; TAMU SGC overlays may shift the article number.]**

A. QC organization

Role	Person	Responsibilities
QC Manager (overall)	[USER TO FILL – typically the Project Manager or a dedicated QC lead]	Authors the project QC plan; reviews submittals against specs; chairs preparatory + initial + follow-up inspection meetings; signs off on each phase.
QC field representative	[USER TO FILL – typically the Project Superintendent]	Performs daily QC walks; documents each three-phase inspection with photos; tracks corrective actions to closure.
Independent testing agency (if required)	[USER TO FILL – typically the owner's third-party testing agency for concrete, soils, fireproofing; not common for a single-room interior reno but verify against CSP package]	Independent verification testing per the specs.

B. The three phases (per CSI section / per trade)

Phase 1 — Preparatory inspection

Held **before** the trade starts on-site. Attendees: QC Manager, QC field rep, the subcontractor's foreman, the A/E (Patterson Architects) if requested, the SSC PM (Joelle Shidemantle) on a notice basis.

Checklist:

- ☐ Submittal status: shop drawings, product data, samples — approved (not "approved as noted with major comments")
- ☐ Materials on site or with confirmed delivery date
- ☐ Drawings + specs current revision (with any addenda)
- ☐ All RFIs answered for this scope
- ☐ Subcontractor's site-specific safety plan signed
- ☐ Required testing agency notified (if applicable)
- ☐ Coordination with adjacent trades verified
- ☐ EHS shutdown windows scheduled (if applicable)
- ☐ Hot-work permits issued (if applicable)

Documentation: signed preparatory inspection form, dated; uploaded to project file.

Phase 2 — Initial inspection

Held **at the start of the first significant work** on a given trade (first 10–20% of installation complete). Confirms the trade is being executed correctly before significant rework cost is incurred. Same attendees as Phase 1.

Checklist:

- ☐ Installation matches approved shop drawings + specs
- ☐ Workmanship is per agreed-upon quality standard (mockup, sample area, or industry standard cited)
- ☐ Dimensional tolerance verified (e.g. plumb / level / square of partitions; flatness of flooring substrate)
- ☐ Safety practices being followed in the field
- ☐ Adjacent work not damaged
- ☐ Drawings + specs are still current revision (no in-flight addenda)
- ☐ Any deficiency noted in writing with corrective action and re-check date

Documentation: signed initial inspection form, dated, with photos; uploaded.

Phase 3 — Follow-up + completion inspection

Held **throughout** the trade's on-site work (regular cadence) and at **completion** (before A/E punch list). Same attendees, but the SSC PM is more likely to attend the completion inspection.

Checklist (recurring):

- ☐ Workmanship continues to meet the standard set at initial inspection
- ☐ Any deficiency noted at initial inspection is corrected and closed out

- ☐ No new deficiencies have emerged
- ☐ Adjacent trades not damaged

Checklist (final completion of trade):

- ☐ All work for the trade complete to spec
- ☐ All required testing, balancing, commissioning complete
- ☐ All required submittals (O&M, warranties, training records) collected
- ☐ Punch list pre-walk complete; punch items identified before A/E walk
- ☐ Areas left broom-clean
- ☐ As-built information captured

Documentation: signed follow-up + final inspection forms; final report uploaded with photos and the closed punch list.

C. Project-specific QC checkpoints

Tied to the phased work plan in 02-technical-approach.md § B:

Phase	Trade / scope	Preparatory	Initial	Follow-up + final
1	Selective demolition	Day 14	Day 16	Daily through Day 25
1	Hazardous-materials clearance	Day 13	Day 14 (pre-demo)	Day 25 (post-demo)
2	Metal-stud framing	Day 19	Day 21	Day 28
2	Plumbing rough-in (incl. lab fixtures)	Day 19	Day 22	Day 30
2	Electrical rough-in (incl. lab branch wiring)	Day 19	Day 22	Day 30
2	HVAC modifications	Day 22	Day 26	Day 35

2	Sprinkler relocation	Day 25	Day 27	Day 32
2	Low-voltage pathway	Day 25	Day 27	Day 32
3	Drywall hang + finish	Day 39	Day 42	Day 50
3	Acoustical ceiling	Day 49	Day 51	Day 55
3	Painting	Day 54	Day 56	Day 62
3	Flooring (LVT + chem-resistant sheet vinyl)	Day 56	Day 58	Day 64
3	Lab casework + work tops	Day 70 (after lead time)	Day 72	Day 76
3	Lab fixtures set	Day 65	Day 67	Day 70
3	Electrical trim	Day 60	Day 62	Day 68
3	Door / frame / hardware (if scope)	Day 60	Day 62	Day 65
4	TAB	Day 80	Day 82	Day 88
4	Fire alarm + sprinkler retest	Day 85	Day 87	Day 90
4	Final cleaning	—	—	Day 95

(Day numbers anchored to NTP per the schedule in 05-schedule-narrative.md.)

D. Punch list discipline

We pre-walk before the A/E punch walk. Standard procedure:

1. **Internal pre-punch walk** by QC field rep + Project Manager (typically Day 88 of schedule). Internal punch list captured in a project-management tool (Procore, BlueBeam Studio, or PDF markup). Subcontractors notified of their items same-day.
2. **Sub-by-sub clearance** before the A/E walk — every sub closes their pre-punch items first.
3. **A/E + owner punch walk** (typically Day 92). Attendees: Patterson Architects, SSC PM (Joelle), TAMU Facilities representative, TAMU EHS representative, our PM + QC field rep. List captured at the walk; sub notifications sent within 24 hours.
4. **Punch closeout** target Day 100. Items requiring lead-time material may extend beyond Day 100 with owner approval per the standard substantial-completion + open-punch-item agreement.

E. Submittals + RFIs

- **Submittal log** maintained in project-management tool from Day 1; targeted 10-business-day A/E turnaround (assumed; adjust per CSP package [PENDING e-BUILDER ACCESS]). Critical-path submittals (lab casework, fume hood if scope, lab fixtures) submitted by Day 5–7 post-NTP.
- **RFI log** maintained in same tool; targeted 5-business-day A/E turnaround. Each RFI is logged with: question, drawing/spec reference, schedule impact, cost impact (if any), proposed answer.
- **Distribution:** all submittal + RFI logs distributed to SSC PM (Joelle) weekly with the project status report.

F. Owner-facing QC reporting

- **Weekly project status report** distributed to Joelle Shidemantle, Fred Patterson, and the firm's Project Executive every Monday morning. Includes: % complete by phase, schedule status (on / ahead / behind), open RFI count + aging, open submittal count + aging, open punch items, safety incidents, EHS coordination notes, photo highlights.
- **Monthly pay application** with HUB Progress Assessment Report (PAR) per TAMU HUB Operations standard, filed with Patty Winkler. Pay app submission discipline: complete G702/G703 (or TAMU-equivalent form [PENDING e-BUILDER ACCESS]) with sworn statement, lien waivers from all paid subs, photos of work-in-place, and HSP progress narrative.
- **Closeout documentation** per the TAMU SGC closeout requirements [PENDING e-BUILDER ACCESS – typically O&M manuals, attic stock, training records, warranties, as-built drawings, EHS final clearance letter].

G. Continuous-improvement loop

After substantial completion, the QC Manager holds a 1-hour internal lessons-learned session and produces a 1-page memo of "what worked / what didn't / what we'll do differently next time." The memo is

filed in the firm's project archive and informs the QC plan for the next TAMU System project.

H. Reference framework

This plan is consistent with:

- USACE EM 385-1-1 and 3-phase QC pattern (the source of the prep / initial / follow-up structure used here)
- ISO 9001:2015 process-approach pattern (PDCA cycle for each trade)
- TAMU System UGSC quality requirements [PENDING e-BUILDER ACCESS: confirm exact article reference]
- AIA A201 General Conditions Article 3.5 (Warranty) and 12 (Uncovering and Correction of Work) baseline expectations

If the CSP package requires a specific QC plan format (some TAMU CSPs prescribe a 1-page form; some require a multi-page narrative), this plan will be re-formatted on G2 close.

07 — Site-specific safety plan

Page target: 2 pages narrative + 1 page hazard / control matrix. **Baseline standard:** 29 CFR 1926 (OSHA Construction Industry standards), supplemented by 29 CFR 1910 (OSHA General Industry standards where applicable to occupied-building work), TAMU EHS protocols, and TAMU System SGC safety requirements [PENDING e-BUILDER ACCESS: confirm exact SGC safety article – typically Article 4 or Article 8]. **Safety lead on this project:** [USER TO FILL – see 03-project-team.md § E]

A. Safety philosophy + culture

Our firm operates under a documented Injury and Illness Prevention Program. We hold a daily pre-task safety briefing on every active site; every employee and subcontractor on site has stop-work authority for any hazard they observe. We track OSHA recordables, near-misses, and EMR transparently and review them quarterly with our insurance carrier.

Firm EMR + OSHA history is reported in 04-past-performance.md § F.

B. Project-specific hazards (this site, this scope)

B-1. Active-occupancy hazards (Harrington Education Center is in use during construction)

Hazard	Control
Pedestrian traffic in adjacent corridors / rooms	Hard-barrier corridor protection at lab entry; floor-protection rolled past lab door; clear signage; restricted material-staging in public corridors
Adjacent-lab occupant health (dust, fumes, noise)	Negative-pressure dust containment at lab perimeter; HVAC return isolation; daytime quiet-work / after-hours noisy-work scheduling; coordination with adjacent-lab PI on chemical-odor sensitive procedures
University academic schedule (exams, large lectures in nearby rooms)	Coordinated with Joelle for any after-hours window changes during peak academic days
Emergency egress	Demo + construction debris kept clear of corridor egress paths; daily superintendent walk to verify

Fire alarm + sprinkler temporarily disabled in work zone	EHS-coordinated shutdown windows only; fire watch posted continuously during any shutdown per NFPA 241 and TAMU EHS hot-work / impairment procedure
--	---

B-2. Lab-specific hazards (the differentiating section)

Hazard	Control
Legacy chemical contamination in existing dressing/lab spaces (mercury splash, perchloric acid residue, biological residue, radiological residue)	Pre-demo TAMU EHS wipe-down + clearance; no demo until EHS clearance letter in hand; personnel use lab-grade PPE (Tyvek + nitrile + N95 minimum, escalating per EHS guidance) during demo of legacy bench tops, sink traps, and fume hood interiors
Existing fume hood / lab exhaust contamination (if present)	EHS-coordinated lock-out / tag-out of exhaust fan; HEPA-vacuum interior before any disassembly; specialty disposal of contaminated components
Ventilation isolation during demo (preventing demo dust + odor reaching adjacent active labs via shared return-air plenum)	Temporary plenum dampers or full seal at Lab 303 return grilles; HEPA-filtered negative-air machines exhausting to a location approved by TAMU Facilities; daily measurement of differential pressure
Lab-gas line cutover (if present)	Lab gas main shut at source by TAMU Facilities; line purged and verified zero-pressure before disconnect; specialty sub (no general plumber) performs gas line work; reconnection follows TAMU lab gas commissioning procedure
Acid-waste piping cutover (if present)	pH-neutralization and flush before any cut; PPE upgrade (face shield + acid-resistant suit + nitrile or butyl gloves); specialty disposal of removed sections
DI water cutover (if present)	Low-hazard but disrupts adjacent-lab DI loop; coordinate cutover window with adjacent-lab PI

Hot-work permitting (soldering, brazing, welding, cutting)	TAMU EHS hot-work permit obtained before any hot work; fire-watch posted per permit; nearby combustibles relocated or fire-blanket protected; sprinkler shut-down only if EHS-approved with fire-watch in place
--	---

B-3. Standard construction hazards (29 CFR 1926)

Hazard	Standard	Control
Falls (any work at height $\geq 6'$; ladders; scaffolds)	1926 Subpart M, X	Fall protection at $\geq 6'$; ladder inspection daily; scaffold-competent person on site for any scaffold use
Electrical	1926 Subpart K	Lock-out / tag-out per 1910.147; qualified electricians on all energized work; GFCI on all temp power
Power tools + hand tools	1926 Subpart I	Daily inspection; required guarding; PPE per tool
Materials handling + storage	1926 Subpart H	Loads under hoisting-equipment ratings; staging clear of egress
Personal protective equipment	1926 Subpart E	Hard hat, safety glasses, high-vis vest, steel-toe boots minimum at all times on active site; task-specific PPE added per task
Respiratory protection (demo dust, painting in confined room, any abatement work)	1910.134	Written respiratory protection program; medical clearance + fit-test on file for each respirator user; N95 or P100 escalation per task
Hazard communication	1910.1200	SDS binder on site; SDS reviewed at each preparatory inspection for trade-specific chemicals

Welding + cutting + brazing	1926 Subpart J	Hot-work permit per § B-2
Confined-space work (plenum entry)	1910.146	Written confined-space program; permit + atmospheric monitoring for any plenum entry
Crystalline silica (drywall demo, concrete work)	1926.1153	Wet-cutting or HEPA-vacuum dust collection; respirator + medical clearance per Table 1

C. Required programs + documentation (kept on site, accessible to TAMU EHS)

- ☐ Project-specific Safety Plan (this document, project-edited)
- ☐ Site-specific Emergency Action Plan (evacuation routes, muster point, severe-weather shelter, TAMU EHS contact)
- ☐ Subcontractor safety plan sign-off for each on-site sub
- ☐ OSHA 300 log
- ☐ Daily safety briefing log (signed by each on-site worker)
- ☐ Tool-box-talk records (weekly minimum)
- ☐ PPE inspection + replacement log
- ☐ Hot-work permit binder
- ☐ Lockout/tagout log
- ☐ Respiratory protection program records (medical clearance, fit-test, training)
- ☐ Confined-space entry permits (if applicable)
- ☐ SDS binder
- ☐ First-aid + CPR certifications for designated on-site responders
- ☐ OSHA 10 / 30 cards for all on-site workers (10 minimum, 30 for superintendents)

D. TAMU EHS coordination

Touchpoint	Owner	Cadence
Pre-construction safety meeting with TAMU EHS	Safety Lead + Project Manager	Day 0 (pre-NTP if possible)

Hazardous-materials clearance review for Bldg 0435 Lab 303	TAMU EHS + Project Manager	Day 1
EHS shutdown-window scheduling (fire alarm, sprinkler, plenum, lab utilities)	Project Manager → TAMU EHS	2-week advance request for each event
Hot-work permits	Project Superintendent → TAMU EHS	Per event, 24-hour advance
Phase 1 demo clearance + close-out walk	Project Superintendent + TAMU EHS	Day 25
Incident reporting to TAMU EHS	Safety Lead	Immediately on any near-miss, first-aid, recordable, or property damage
Phase 4 final EHS clearance	Project Manager + Safety Lead + TAMU EHS	Day 95–98
Substantial completion sign-off	TAMU EHS (with SSC PM + A/E)	Day 100

E. Incident response

- **Immediate response:** Trained on-site responder provides first-aid; serious injury → call 9-1-1 + TAMU EHS emergency line + project Safety Lead.
- **Securing the scene:** Project Superintendent secures the area; preserves evidence; documents conditions.
- **Notification:** TAMU EHS notified within 1 hour for any serious injury or property damage; SSC PM (Joelle Shidemantle) notified within 4 hours; firm Safety Lead notified immediately.
- **Investigation:** Within 24 hours, Safety Lead initiates a root-cause investigation with the responsible sub. Written report to TAMU EHS within 72 hours for any recordable.
- **Lessons learned:** Findings shared with all on-site personnel at the next daily safety briefing; corrective actions tracked to closure.

F. Safety training matrix

Course	Required for	Frequency
--------	--------------	-----------

OSHA 10	All on-site workers	Once, prior to site access
OSHA 30	All supervision (superintendent, foreman) + Safety Lead	Once, valid 5 years
First Aid + CPR + AED	At least 2 designated on-site responders	Every 2 years
Hazard Communication (HazCom)	All on-site workers	Per OSHA, refresher on new chemicals
Respiratory Protection (1910.134)	Any worker using a respirator	Annual + after any program change
Lockout / Tagout (1910.147)	Any worker performing energized-work isolation	Annual
Fall Protection (1926 Subpart M)	Any worker on work-at-height $\geq 6'$	Annual
Silica (1926.1153)	Any worker on silica-generating tasks	Annual
Lab-specific hazards (TAMU EHS overview)	All on-site supervision + electrical / plumbing / HVAC subs working on lab utilities	Once, prior to lab-utility work
Hot-work permit holder training	Project Superintendent	Annual
Confined-space entry (1910.146)	Any worker entering plenum or other confined space	Annual

G. Subcontractor safety qualification

Every subcontractor on this project must provide before mobilization:

- Subcontractor's site-specific safety plan addressing the hazards above
- Insurance certificates (per 02-bid-prep-checklist.md § A)
- OSHA training records for all on-site personnel
- EMR for the last 3 years (we require sub EMR ≤ 1.0 for any sub doing work outside their core trade; ≤ 1.25 for specialty subs where the pool is thin; > 1.25 requires Safety Lead sign-off and a written

remediation plan)

- Sub's own OSHA citation history (last 3 years)
- Sub's representative attendance at our preconstruction safety kickoff

08 — CSP Proposal Form fill guide

STATUS as of 2026-05-23: ACTUAL FORM NOW IN HAND. The CSP package was pulled from the e-Builder portal on 2026-05-23. The real form lives in the project specifications at:

- `inbox/opportunities/attachments/2026-05-21/tamu-csp/Harrington_Lab303_Specifications.pdf`, pages **20–24** (Section 00 42 13 — CSP Part 1 Proposal Form & Pricing Schedule), and is part of a 4-Part submission package: Part 1 (00 42 13), Part 2 Technical (00 45 16), Part 3 Safety/Risk/QC (00 45 17), Part 4 HUB/VetHUB Subcontracting Plan (00 45 17.1).

The pre-portal-pull anticipated-fields table below has been **superseded** by the actual fields described in § A.bis. The table in § B is kept for now as a transitional cross-reference; **on the actual fill, use the printed form from the specs PDF, not § B.** The pre-portal table will be deleted in the final pre-submission cleanup pass.

Do not submit the proposal package without filling in the actual printed SSC Section 00 42 13 form (wet ink, in words AND figures, with the CSI-division line-item pricing table populated).

A. What this form is

A TAMU System Competitive Sealed Proposal under Tex. Gov't Code Ch. 2269 is anchored on a "Proposal Form" (also called the "Bid Form" on some packages). It is the legally-binding cover page of the priced proposal. The TAMU CSP Proposal Form typically:

- Identifies the solicitation, the project, and the proposer
- States the total lump-sum price
- States unit prices (if requested) and alternates (if requested)
- States proposed substantial completion duration
- Acknowledges all addenda
- Certifies HSP commitment
- Bears a wet-ink signature by an authorized officer

The Angelo State Carr EFA solicitation in our inbox (`inbox/.../ESBD_516718_..._26-007 Carr EFA Dressing Room Renocation Attachment A.pdf`) is a content-shape proxy. **The Texas TFC Bid Form structure is broadly common across Texas state higher-ed CSPs.** We expect the TAMU form to track the same structure but with:

- TAMU System / SSC Services for Education branding header
- TAMU-specific routing address (1371 TAMU / 600 Agronomy Road, Suite 218)
- TAMU System-specific allowance + alternate categories (if any)
- TAMU System-specific certification language (HUB commitment, conflict of interest, lobbying)

■ Resolved 2026-05-23 from the portal-pulled spec PDF. See § A.bis below for the actual structure.

A.bis. Actual form structure (from portal pull, 2026-05-23)

The real Section 00 42 13 in the CSP package is **4 pages**, structured as:

Page	Section	What it asks for
1 of 4	Header + Boilerplate	Business name + DBA designation (Corp / Partnership / Individual), affirmation that the bid is based on the SSC UGSC, SSC Special Conditions, the Drawings, the Project Manual/Specifications, and any Addenda; the four-bullet certification (collusion-free, full performance, 90-day acceptance window, 10-business-day contract execution after award, "amounts in words govern over figures")
2 of 4	Pricing Schedule	A CSI-division line-item table: Contractor must enter a \$ amount for each CSI division actually in scope OR mark blank if the division is not in scope, OR bid will be disqualified for being incomplete. Divisions listed on the form: 01, 02, 03, 04, 05, 06, 07, 08, 09, 10, 11, 12, 13, 14, 21, 22, 23, 25, 26, 27, 28, 31, 32, 33, 34, 44, 45. BASE PROPOSAL AMOUNT at bottom. (For this Lab 303 project: per the specs, only 01, 02, 06, 07, 09, 10, 21, 22, 23, 26 appear in the work scope; the rest will be marked blank.)

3 of 4	Item No. 1 — Base Proposal Amount, Substantial Completion, Addenda	The complete construction price for "Harrington Education Center Lab 303 Renovation, including all general, plumbing, mechanical, and electrical work indicated on the drawings by Patterson Architects dated 5/7/2026" — entered in both words AND figures (words govern); Substantial Completion in calendar days from NTP (bidder-chosen — this is the 10%-weighted "Construction Time" criterion); Final Completion is fixed at 30 calendar days after Substantial Completion ; Addenda numbers acknowledged.
4 of 4	Respondent block	Company name, EIN, authorized signature, title, date, phone, email/fax, contact for invoice.

No alternates section. No unit-prices section. No allowances section. The CSP is a single base-proposal lump-sum with division-level subtotals. This is a meaningful simplification from the anticipated structure in § B below.

No bid bond at proposal. The package has Performance Bond (00 61 13) and Payment Bond (00 61 14) forms — required at award, not at proposal.

Submission packaging (CSP §00 21 00 ¶5.2): - 1 sealed envelope: Parts 1–3 in hard copy, labeled CSP Submission for Project Number 2025-06813 Parts 1-3 with the firm's name on the outside. - 1 separate sealed envelope: Part 4 HSP/VetHUB, labeled HUB Subcontracting Plan for Project Number 2025-06813 with the firm's name on the outside. - 1 USB flash drive: PDF of all four parts, inserted inside the Part 4 envelope. - Mailing address: **SSC Facilities Services Bldg. #1156, 600 Agronomy Road, Suite 218, College Station, TX. 77843, ATTN: Joelle Shidemantle, "PROPOSAL ENCLOSED".**

Evaluation weighting (CSP §00 21 00 ¶11.2): - Base Proposal Amount & Alternates: **51%** - Construction Time: **10%** - Technical Proposal: **24%** (Company Info, Experience, Personnel, Approach, Subs) - Litigation & Claims: **5%** Pass/Fail - Safety, Risk Assessment & QC: **5%** Pass/Fail - Quality Control: **5%** Pass/Fail - HUB Subcontracting Plan: **disqualifier if missing, incomplete, or late** (no point value — pure P/F gate)

B. Anticipated fields (place holders for fast fill on G2 close)

B-1. Solicitation identification (top of form)

Field	Value to enter
Solicitation # / Project #	2025-06813
Project name	Harrington Education Center Lab 303 Renovation
Owner	Texas A&M University (Part 02)
Issuer (Facilities Services Contractor)	SSC Services for Education
Proposal due date	2026-06-10, 2:00 PM CT
Proposal opening	2026-06-10, 2:30 PM CT

B-2. Proposer identification

Field	Value to enter
Legal company name	[USER TO FILL – exact match to W-9 + CIQ + 1295]
DBA (if applicable)	[USER TO FILL]
Federal EIN	[USER TO FILL]
Texas Taxpayer ID	[USER TO FILL]
Street address	[USER TO FILL]
Mailing address	[USER TO FILL]
Phone	[USER TO FILL]
Email	[USER TO FILL]
Web	[USER TO FILL]

Authorized signatory (name, title)	[USER TO FILL]
TX HUB cert # (if applicable)	[USER TO FILL or "Not HUB-certified"]

B-3. Price proposal

Field	Value to enter
Base Proposal Price (lump sum)	\$(USER TO FILL – from 10-price-proposal.md final number)
Owner Contingency Allowance (if specified by CSP)	\$(PENDING e-BUILDER ACCESS – TAMU sometimes specifies a carried allowance; if specified, do NOT roll into lump sum and do NOT mark up. Carry per CSP instructions.)
Alternate #1 (if applicable)	\$(PENDING e-BUILDER ACCESS)
Alternate #2 (if applicable)	\$(PENDING e-BUILDER ACCESS)
Unit prices (if applicable)	per separate exhibit; see § B-4
Total Proposed Contract Sum	\$(USER TO FILL – sum of above per CSP instructions)

B-4. Unit prices (if requested by CSP)

Typical TAMU CSP unit-price categories [PENDING e-BUILDER ACCESS]:

Unit-price item	Unit	Unit price (USD)
Additional sq ft of LVT flooring	SF	\$(USER TO FILL)
Additional sq ft of sheet vinyl flooring (heat-welded seams)	SF	\$(USER TO FILL)
Additional sq ft of paint (2-coat)	SF	\$(USER TO FILL)
Additional door + frame + hardware	EA	\$(USER TO FILL)

Additional duplex receptacle (in-wall)	EA	\$[USER TO FILL]
Additional LED lighting fixture	EA	\$[USER TO FILL]
Additional acoustical ceiling tile (replacement)	SF	\$[USER TO FILL]
Additional sprinkler head relocation	EA	\$[USER TO FILL]
Additional lab sink + faucet	EA	\$[USER TO FILL]
Additional lab gas outlet (if scope)	EA	\$[USER TO FILL]
Hazmat abatement allowance (lead/asbestos/PCB; per the OSHA-class)	per CY or per LS	\$[USER TO FILL]
After-hours shift premium (per labor hour)	HR	\$[USER TO FILL]
Hand-mucking / non-mechanized demo allowance (per CY)	CY	\$[USER TO FILL]

Pricing discipline: unit prices should be at full retail (sub cost + full GC markup). They set the ceiling for change orders — do not strip them down to be price-competitive.

B-5. Schedule

Field	Value to enter
Proposed substantial completion (calendar days from NTP)	70 (per 05-schedule-narrative.md)
Proposed final completion (calendar days from NTP)	100

B-6. Addenda acknowledgment

Addendum #	Date	Acknowledged?
[USER TO FILL: 1, 2, 3 ...]	[USER TO FILL]	[Y]

Verify addenda on the e-Builder portal the morning of submission (2026-06-10) and again immediately before sealing the package.

B-7. HSP certification

"Proposer certifies that a Historically Underutilized Business (HUB) Subcontracting Plan is submitted with this proposal and that the Proposer has made a good-faith effort to subcontract with HUBs in accordance with 34 TAC § 20.284." (Anticipated language; verify against actual form [PENDING e-BUILDER ACCESS].)

B-8. Conflict of interest + lobbying certifications

Anticipated [PENDING e-BUILDER ACCESS]:

- Texas Form CIQ — Conflict of Interest Disclosure (Tex. Local Gov't Code Ch. 176) — attached or attested not-applicable
- Texas Form 1295 — Certificate of Interested Parties (if contract value ≥ \$1M or if otherwise required by TAMU) — TEC-filed copy attached or attested not-applicable
- TAMU System Disclosure of Lobbying Activities — completed
- Conflict-of-interest certification specific to TAMU System procurement

B-9. Bonds + insurance

Item	Status
Bid Bond (5% of total proposal price)	Original attached on TAMU System form, payable to Board of Regents of TAMU System
Performance Bond commitment letter	Attached
Payment Bond commitment letter	Attached
Insurance ACORDs	Attached; TAMU System named as additional insured; waiver of subrogation noted

B-10. Signature block

- Authorized signatory: **[USER TO FILL: name]**
- Title: **[USER TO FILL: title – must have proposal-binding authority per firm's bylaws]**
- Date signed: **[USER TO FILL – typically the day of hand-delivery, 2026-06-09]**
- Signature: **WET INK, BLUE INK preferred** per TAMU System pattern. Confirm against actual CSP package **[PENDING e-BUILDER ACCESS]**.

C. Common form-fill failures (TAMU clerks reject for these)

1. **Legal-name mismatch.** Name on CSP Proposal Form $\neq$ name on W-9 $\neq$ name on CIQ $\neq$ name on 1295. Triple-check.
2. **Unsigned form.** Or photocopied signature. TAMU System pattern requires wet ink, originals only.
3. **Math errors.** Lump sum + alternates $\neq$ Total Proposed Contract Sum. Subtotal + unit-price multiplier $\neq$ stated total. Run the math twice.
4. **Missing addenda acknowledgment.** Even if no addenda were issued, the form typically has a "no addenda received" checkbox; do not leave blank.
5. **Wrong bond form.** TAMU System has its own bond forms; AIA A310 / A312 stand-ins may not be accepted at submission.
6. **Out-of-date insurance ACORDs.** ACORDs typically expire 30 days from issue for proposal use; re-pull within 30 days of submission.
7. **Missing HSP.** HSP must be a separate submitted document; not in lieu of the Proposal Form HSP-certification box, both are required.
8. **Late submission.** TAMU's clock is the wall clock at the SSC Service Solutions desk; arrive early. Late = non-responsive, no exceptions.

D. Fill workflow (when CSP package lands)

1. **Pull the actual TAMU CSP Proposal Form PDF** from the e-Builder package.
2. **Re-author this guide section-by-section** against the actual fields. Delete any anticipated sections that don't appear; add any actual sections that do.
3. **Print the form on the firm's letterhead-compatible printer** (if the form is fillable PDF, fill the PDF first, then print).
4. **Fill in values** per the table in § B (or per the re-authored guide).
5. **Internal 2-person QC pass** against `../11-submission-checklist.md`.
6. **Wet-ink signature** in blue ink by authorized officer.
7. **Date** at signing.

8. **Insert into the sealed proposal envelope** per the submission packaging requirements (per CSP instructions).

E. Backup if form is not posted by Tue 2026-05-26

If by EOD Tuesday 2026-05-26 the CSP package is not on the e-Builder portal and Joelle has not provided direct file links:

1. Escalate to TAMU System Office of Facilities Planning & Construction (per the no-go gate G2 in `00-readme.md`).
2. Consider whether to draft a generic TFC-style Proposal Form using the Angelo State Attachment A as a structural template — **only as a draft for internal review, NOT for submission**. TAMU clerks will reject a non-TAMU form.
3. Issue go/no-go decision per G2 on Wed 2026-05-27.

09 — HSP (HUB Subcontracting Plan) form fill guide

STATUS as of 2026-05-23: ACTUAL FORM NOW IN HAND, AND IT'S A DIFFERENT FORM THAN ASSUMED.

The CSP package was pulled from the e-Builder portal on 2026-05-23. **Section 00 45 17.1** of the project manual (inbox/opportunities/attachments/2026-05-21/tamu-csp/Harrington_Lab303_Specifications.pdf pp. 33–40) is **NOT** the older State of Texas HUB Subcontracting Plan form. It is the **TX State Subcontracting Plan (Rev. 5/26)** which uses the **VetHUB (Veteran Heroes United in Business)** framework — a Texas Comptroller-administered certification for veteran-owned businesses (Tex. Gov't Code Ch. 2161 Subchapter F; 34 TAC §20.285).

The whole strategy in ../05-hsp-plan.md was built around the older HUB framework. It will need to be revised against the VetHUB framework. Initial findings:

- The form is **mandatory for every respondent**, even if the respondent intends to self-perform (in which case only pages 1–2 are completed + Section 3 affirmation).
- GFE consists of **NIGP-code-based outreach to ≥2 VetHUBs per subcontracting opportunity**, with at least 7 business days for response. Notification template provided in the spec.
- **HUB / VetHUB cert numbers are tracked by Texas Comptroller VID** (Vendor Identification Number), and certifications are looked up via the comptroller's CMBL (<https://commbook.app.cpa.state.tx.us/>) using the **VetHUB-only search** and Active Bidder (A-Approved) VetHUB status filter.
- **Action: Brittany Crawley** (BrittanyFew@tamu.edu, (979) 845-9010, per CSP §00 21 00 ¶3.3) is the TAMU HUB-Operations contact for this project — NOT Patty Winkler as previously assumed from the Notice. Update outreach/04-email-patty-winkler-hub.md to retarget Brittany.
- **Action: revise ../05-hsp-plan.md** — replace HUB outreach with VetHUB outreach; refresh CMBL search guidance.

Action TODAY (post-portal-pull): start the VetHUB outreach immediately per ../05-hsp-plan.md § D (with the revised VetHUB filtering). The form structure is in hand; the GFE outreach clock is now the binding constraint.

A. What this form is

The HSP is the document by which the prime contractor commits to a HUB-participation goal on the project and documents the good-faith effort to achieve that goal. Under 34 TAC §20.281–.298:

- Texas state agencies (including TAMU) require an HSP when subcontracting opportunities exist

- The applicable HUB participation goal varies by procurement class — for renovation work, the **statewide 21.1% goal for "special trade construction"** applies unless TAMU has set a project-specific higher goal ([**USER TO FILL – confirm with Patty Winkler**])
- The HSP commits the prime to either (a) meeting the goal with named HUB subcontractors or (b) documenting a good-faith effort if the goal cannot be met
- The HSP must be submitted **with** the proposal (not after)
- Failure to submit or to document a defensible GFE renders the proposal non-responsive

[PENDING e-BUILDER ACCESS or Patty Winkler confirmation: download the actual TAMU HSP form and re-author this guide section-by-section against the actual fields.]

B. Cross-reference: existing HSP strategy

The full HSP strategy is in `../05-hsp-plan.md`. Key inputs that feed this form:

- Per-trade subcontracting plan with target HUB allocation (`../05-hsp-plan.md` § C)
- HUB sub outreach plan (CMBL search results, contact log) (`../05-hsp-plan.md` § D)
- GFE documentation (advertising, written notice, HUB-event attendance) (`../05-hsp-plan.md` § E)

This document is the **form-completion guide**, not a restatement of the strategy. Read `../05-hsp-plan.md` first.

C. Anticipated form sections (standard TX HSP shape)

C-1. Cover page (commitment summary)

Field	Value to enter
Solicitation #	2025-06813
Project name	Harrington Education Center Lab 303 Renovation
Agency	Texas A&M University (Part 02)
Issuing entity	SSC Services for Education
Proposer (Prime)	RK Residential Homes and Commercial Constructions, LLC dba Blue Print Constructs

Prime's TX HUB status	[USER TO FILL: HUB-certified Y/N; if Y, list cert #]
Total proposal value	[\$[USER TO FILL: matches 10-price-proposal.md]
Total self-performed value	[\$[USER TO FILL: from 03-project-team.md § H and self-performing justification]
Total subcontracted value	[\$[USER TO FILL: total proposal value – self-performed]
HUB goal applicable	21.1% (statewide special-trade construction goal per 34 TAC §20.284, current as of 2024 amendment) — [USER TO FILL: confirm vs project-specific goal from Patty Winkler]
HUB participation committed	[USER TO FILL: \$ amount and %]
HUB goal met? (Y/N)	[USER TO FILL] — if N, full GFE documentation required in §§ C-4, C-5

C-2. Self-performing justification

For each self-performed scope, fill in:

Scope	Estimated value	Justification
[USER TO FILL: e.g. "Project supervision and general conditions"]	[\$[USER TO FILL]]	[USER TO FILL: "Required to maintain single-point project accountability per our standard project-execution model; not feasible to subcontract."]
[USER TO FILL: e.g. "Internal carpentry / demo crew" – if applicable]	[\$[USER TO FILL]]	[USER TO FILL]

Self-performed dollars are removed from the denominator before computing the HUB target percentage.

C-3. Per-trade HUB subcontracting plan

For **every** subcontracted trade, the form requires a named HUB sub OR a documented GFE record.

Trade	Sub name	T #	H c	S d	E v	% \$ of total subcontracted
Demolition	[USER TO FILL]	[T F	[T F	[T F	\$ T F	[USER TO FILL] — must be current]
Framing / drywall	[USER TO FILL]					
Doors / frames / hardware (if scope)	[USER TO FILL]					
Flooring	[USER TO FILL]					
Painting	[USER TO FILL]					
Acoustical ceilings	[USER TO FILL]					
Lab casework	[USER TO FILL]					
Electrical (lab-exp)	[USER TO FILL]					
HVAC (lab-exp)	[USER TO FILL]					
Plumbing (lab-exp)	[USER TO FILL]					
Fire suppression	[USER TO FILL]					
Lab utility specialty (if scope)	[USER TO FILL]					
Low-voltage pathway	[USER TO FILL]					

Sum check: sum of HUB-sub \$ values ÷ total subcontracted value = HUB participation %.

C-4. Good-faith effort documentation (mandatory if HUB goal not met)

For each trade where the HUB goal was not met or where no HUB sub was selected, attach:

1. **CMBL search records** — screenshot of search filtered by HUB-certified + NIGP/NAICS for that trade + Brazos County area; dated.
2. **Written outreach log** — per . . /05-hsp-plan.md § D: date, sub name, contact method, response. Per-trade minimum of 3 documented HUB outreaches.
3. **Bid solicitation packet** — the exact packet sent to HUB subs for that trade (project name, scope, due date, contact).
4. **Sub responses** — any quotes received; reasons for non-selection (price, schedule, qualification).
5. **Non-response evidence** — for HUB subs that did not respond, the outreach log itself is the evidence.
6. **Advertisement in 2+ HUB publications** — copies of the ad; publication name; date of publication; circulation.
7. **HUB outreach event attendance** — sign-in sheet / event registration confirmation for any HUB-targeted event attended.

C-5. Per-trade GFE narrative

For each trade where no HUB sub was selected, a 2–4 sentence narrative explaining why:

Trade	Narrative
[Trade]	[USER TO FILL – example: "We solicited 5 HUB-certified electrical subcontractors via CMBL search. 2 declined due to scheduling conflicts with existing commitments; 2 did not respond; 1 quoted at a 23% premium over the selected non-HUB sub due to lack of lab-experience pricing. Documented GFE per § C-4."]

C-6. Subcontract administration plan

Field	Value to enter
Monthly Progress Assessment Report (PAR) submitter	[USER TO FILL – typically Project Manager]

PAR recipient	Patty Winkler, TAMU HUB Operations, p-winkler@tamu.edu (per Notice)
PAR cadence	Monthly with each pay application (per Notice)
HSP change-management procedure	Per 34 TAC §20.285; prime must request TAMU HUB Operations approval for any HSP modification post-award

C-7. Affirmation + signature

Field	Value to enter
Affirmation language	(standard TX HSP affirmation; verify exact text against actual form [PENDING – Patty Winkler])
Authorized signatory	[USER TO FILL – name + title]
Date	[USER TO FILL]
Signature	wet ink, blue ink preferred

D. Pre-submission checklist (HSP-specific)

- ☐ CMBL search records (screenshot per trade, dated)
- ☐ Outreach log (≥3 HUB subs per trade, with dates and methods)
- ☐ Sub-bid solicitation packet (master copy + per-trade copies)
- ☐ HUB-publication advertisement copy (2 publications minimum) — **[USER TO FILL: which publications, dates of publication]**
- ☐ HUB-event attendance records (if any)
- ☐ HUB cert # verification — re-verify on CMBL search within 7 days of submission (expired certs get the HSP kicked back)
- ☐ Form-side math reconciles (HUB \$ ÷ subcontracted \$ = stated %)
- ☐ HSP signed in wet ink
- ☐ HSP bound with the proposal (typically as a separate, tabbed exhibit)
- ☐ HSP separately delivered to Patty Winkler if TAMU requires both Proposal Form delivery and direct HSP delivery [PENDING – confirm with Patty]

- [] Internal 2-person QC pass

E. Common HSP rejection reasons

1. **Expired HUB certifications** for listed subs. Re-verify within 7 days of submission.
 2. **HUB sub listed but no contract / scope detail.** Form requires named scope and estimated dollar value, not just "Sub XYZ, electrical."
 3. **GFE narrative too thin.** "We tried but no HUB subs responded" is not GFE — must show the outreach log, the CMBL search, the publications.
 4. **Math errors.** HUB \$ doesn't sum to the stated %; subcontracted \$ doesn't reconcile with total \$ minus self-performed.
 5. **Missing publications.** Both required publications listed in the form must be from the approved TX HUB publication list (see `../05-hsp-plan.md` § E for the list).
 6. **Form on wrong template.** TAMU uses its own header; do not submit on a non-TAMU template once TAMU's is in hand.
-

F. Workflow when TAMU HSP form lands

1. Download the actual TAMU HSP form (from Patty Winkler or the e-Builder portal).
2. Compare against the State of Texas standard HSP form and the Angelo State Attachment D HSP form. Note any TAMU-specific additions (commitment-letter format, narrative-length limits, attestation language).
3. Re-author this guide section-by-section against the actual TAMU form.
4. Populate per the data in `../05-hsp-plan.md` and the live outreach log (`local/hub-outreach-log.csv`).
5. Internal 2-person QC pass.
6. Sign, bind with proposal.

10 — Price proposal

STATUS: FORMULAS REFINED 2026-05-23 against the actual downloaded CSP package (drawings A0.1–E1.2 + Project Manual). Quantities still **[USER TO FILL]** after Bluebeam takeoff against A2.1 / P1.1 / M1.1 / E1.2. Cross-references: `../price-references.md` for refined \$/SF benchmarks, `../takeoff-template.json` for the line-item skeleton (now scope-pruned per spec), `../price-sheet-skeleton.json` for the CSI-grouped pricing-form skeleton.

Pricing form structure: Single CSI-division line-item sheet inside `Harrington_Lab303_Specifications.pdf` (Section 00 42 13 Proposal Form). Bidder fills: - One \$ figure per CSI division (Divs 01, 02, 06, 09, 22, 23, 26, 27, 28; Divs 03–05, 07, 08, 11, 13, 14, 31–33 NOT USED) - One \$ figure for total lump-sum - Substantial Completion calendar days (proposer-chosen) - Acknowledgment of any addenda - Respondent info + VetHUB plan + bonding-agent commitment (separate enclosure)

No bid bond required (CSP §00 42 13 does not call for one). **No alternates** (CSP §00 42 13 has no alternate lines). **No unit-price form** (CSP §00 42 13 has no unit-price grid).

A. Methodology

We construct the base bid as:

```
Base Bid = (Direct trades + Self-performed labor) × Region multiplier + General
Conditions (duration × monthly rate) + Bond + Insurance (% of subtotal) +
Contingency (% of subtotal) + Overhead (% of subtotal) + Profit (% of subtotal)
```

Where:

- **Direct trades** sum the priced line items in `../takeoff-template.json` (each = quantity × unit cost × waste factor; line items pruned to match Divs that ARE USED per spec)
- **Region multiplier** = ~0.93–0.96 for College Station (Brazos County) per current RSMeans CCI. Carry **1.0** until the final estimator pass.
- **General conditions** = project duration (70 days commitment) × monthly GC rate (PM + super + temp services + project setup)
- **Bond + insurance** = ~1.5–2.0% of subtotal (no bid bond required; P&P bonds at 0.6–1.2% of contract value; insurance per SSC/Compass MVA limits)
- **Contingency** = 7% for a single-room reno with the now-confirmed drawing+spec set; **drop from 10% to 7%** as G2 is CLOSED GREEN per `../README.md`
- **Overhead** = 10% typical
- **Profit** = 6% typical for institutional state work; consider 5% to optimize the 60%-weighted Price criterion if pursuing aggressively

B. Implied bid envelope (refined per [../price-references.md](#) § B post-portal-pull)

The high-tier "wet lab with fume hood" is **eliminated** per Spec Division 11 NOT USED. The realistic tiers are now:

Scenario	Lab program	\$/SF	× 1,200 SF (assumed)	Implied total
Low	Finishes-only refresh — but spec includes MEP rough-in so NOT this	\$95	× 1,200	~\$114K (floor only)
Mid (low)	Light classroom-lab (light MEP + casework, no fume hood)	\$140	× 1,200	~\$168K
Mid (high)	Standard classroom-lab (MEP rough-in + casework + safety shower / eye-wash)	\$210	× 1,200	~\$252K

Working bid envelope (refined): \$170K–\$240K assuming a mid-tier classroom-lab program without fume hood and without DI water. The envelope tightens further once (a) room SF is measured from A2.1 and (b) H2I Sub-06 casework specifics are retrieved.

Net effect of portal pull: the high outlier (\$310/SF ≈ \$372K) is OFF THE TABLE. The bid-envelope width tightens from ~\$258K to ~\$70K. Pricing posture moves squarely into the **\$180K–\$220K sweet spot**.

C. Base bid summary table (pricing form skeleton, matched to CSP §00 42 13)

This matches the actual CSP §00 42 13 Proposal Form structure: one \$ per CSI division (Divs that ARE USED only) + lump-sum + Substantial Completion days. Divisions that are NOT USED per spec are explicitly marked \$0 / N/A.

C-1. By CSI division (per CSP §00 42 13 form structure)

CSI Div	D \$ amount
01	G \$[USER TO FILL] Requirements (PM, super, temp services, dumpster, project closeout)
02	Ex\$[USER TO FILL] Conditions / Selective Demolition + asbestos handling per Spec 02 26 23 (modest \$3K-\$10K allowance)
~~03-05~~	N N/A USED (no concrete, masonry, metals per spec)

06	Lal\$[USER TO FILL] Casework per A2.1/A2.2 + H2I Sub-06 (carry \$20K-\$60K allowance pending H2I retrieval)
~~07~~	N N/A USED (no thermal/moisture protection per spec)
~~08~~	NOT/A USED — existing door + frame + hardware stay

09	F \$[USER TO FILL] — framing, GWB (09 22 00), ACT (09 51 00), resilient flooring (09 65 00), paint (09 91 00) per A2.1/A2.2
10	Sp\$[USER TO FILL] per Spec 10 14 00 (ADA signage per A0.2/A0.3)
~~11~~	N N/A USE — no fume hood, no lab equipment

~~12, 13, 14~~	NOT/A USED
21	F \$[USER TO FILL] Suppression (sprinkler-head relocation; no spec — deferred submittal allowance \$1K–\$5K)
22	Plu\$[USER TO FILL] per P1.1 (lab fixtures, eye-wash + safety shower if shown)
23	H \$[USER TO FILL] per M1.1 + MEP1.0 (diffuser relocation, VAV retrim, TAB report)

26	Ele\$[USER TO FILL] per E1.1 + E1.2 (lighting + controls retrofit, branch wiring + devices)
27	C \$[USER TO FILL] / low-voltage pathway (TAMU TS pulls cable)
28	Ele\$[USER TO FILL] Safety / Fire Alarm (device relocation)
~~31-33~~	N N/A USED (no earthwork, utilities, exterior)
Subtotal direct trades	\$(USER TO FILL)
× Region multiplier (~0.93–0.96 College Station)	\$(USER TO FILL)
Subtotal trades (region-adjusted)	\$(USER TO FILL)

General Conditions (70 days × monthly rate)	\$[USER TO FILL]
Bond + Insurance (~1.5–2.0% of subtotal; no bid bond)	\$[USER TO FILL]
Subtotal pre-OH/P/C	\$[USER TO FILL]
Contingency (7%)	\$[USER TO FILL]
Overhead (10%)	\$[USER TO FILL]
Profit (6%, or 5% if aggressive on the 60%-weighted Price criterion)	\$[USER TO FILL]
BASE LUMP-SUM PROPOSAL PRICE	\$[USER TO FILL]
Substantial Completion (calendar days from NTP, proposer-chosen, 10% weight)	70 cal days
Final Completion (fixed at Subs.Comp. + 30 cal days per CSP §00 42 13)	100 cal days

C-2. Owner contingency allowance

Not specified in CSP §00 42 13 (confirmed against the downloaded form). No owner-controlled contingency line to carry.

C-3. Alternates

Not specified in CSP §00 42 13 (confirmed against the downloaded form). Do NOT submit any unsolicited alternates — risks non-responsiveness.

C-4. Unit prices

Not specified in CSP §00 42 13 (confirmed against the downloaded form). No unit-price grid. Any pricing for change-order work is governed by SSC UGSC Article 11 (Changes).

D. Pricing posture (refined per ../price-references.md § F post-portal-pull)

- **Contingency:** 7% baseline (G2 CLOSED GREEN so we no longer need the 10% drawing-uncertainty bump).
- **Bid posture:** middle of the mid-tier range (~\$175–\$200/SF effective rate). Aggressive: lower end (\$150–\$175/SF) for an experience-light TAMU portfolio.

- **Floor:** do not go below ~\$140/SF — below this, the 10%-weighted Construction Time + bond + insurance start eating margin given the Net-75 payment terms in the SSC MVA.
- **Ceiling:** do not go above ~\$240/SF — TAMU evaluators reading Patterson + River MEP scope confirm will mark higher pricing as unjustified.

E. Bid bond

NOT REQUIRED. Per CSP §00 42 13 (confirmed against the downloaded form), no bid bond is required for this CSP. Skip the bid-bond enclosure entirely.

`../12-bid-bond-letter-template.md` is now **not needed for submittal** — keep on file as a generic template for future use.

F. Performance + payment bond commitment

- **100% of contract value, each**, on award per Spec Section 00 61 13 (Performance Bond) and 00 61 14 (Payment Bond)
 - TAMU System bond forms are referenced in the Project Manual — use the forms attached to the spec sections, not generic AIA forms
 - Bonding-agent commitment letter included with proposal — letterhead, signed by underwriter
 - Bond premium typically 0.6–1.2% of contract value; included in the Bond + Insurance line in § C-1
 - Insurance limits flow from the SSC/Compass Master Vendor Agreement (referenced in Spec Section 00 73 00 Supplementary Conditions); confirm GL + Auto + W/C + Umbrella against current carrier before bid submittal
-

G. Pricing-form workflow (post-portal-pull state)

1. ■ CSP §00 42 13 Proposal Form is in hand (within `Harrington_Lab303_Specifications.pdf`).
 2. ■ Format compared — single CSI-division line-item sheet + lump-sum + Substantial Completion days. No alternates, no unit prices, no owner allowance.
 3. ■ This guide is now matched to the actual form (§ C-1 above).
 4. **NEXT:** populate from the takeoff (`../takeoff-template.json`) against the actual drawings (A2.1 / P1.1 / M1.1 / E1.2).
 5. Run the math twice. Sum check against `../price-references.md` § C per-trade benchmarks.
 6. 2-person QC pass.
 7. Sign and seal per `08-csp-proposal-form-fill-guide.md` § D.
-

H. Pricing risks (cross-reference `../07-risk-register.md`)

Risk	Pricing impact	Mitigation
R-03 (hidden lab utilities)	Now bounded — fume hood OFF, DI/lab gas only if shown on P1.1; +5–10% on MEP scopes max	Carry \$5K–\$10K lab-utility allowance; confirm P1.1 scope at takeoff
R-06 (thin drawings)	RESOLVED — full drawing set + spec in hand; contingency stays at 7%	No bump needed
R-07 (occupied building / after-hours)	+10–25% on affected trades (demo, fire alarm, sprinkler, plumbing cutover)	Already priced
R-08 (existing-conditions surprises — asbestos)	\$3K–\$10K allowance per Spec 02 26 23 procedural handling	Allowance line in § C-1 Div 02
R-09 (Brazos County prevailing wage)	+1–5% on direct labor	Pull TAMU SGC prevailing wage; cross-check against firm labor rates
R-10 (insurance limits per SSC/Compass MVA)	+\$2K–\$8K one-time premium for Umbrella increase	One-line bid adder if material; confirm at G3
R-NEW (Net-75 payment terms per SSC MVA)	Working capital float on a 70-day job → ~2% effective margin impact	Bake into the 6% profit assumption or move to 5%+ if pursuing aggressively
R-NEW (H2I Sub-06 not yet retrieved)	Casework allowance \$20K–\$60K wide range until file in hand	Retrieve via Joelle outreach (<code>../outreach/01-...md</code>); tighten range to ~\$15K wide at G3

I. Honest dependency note for the reviewer

The numbers in this document are **placeholders for the SF-driven line items** until:

1. ■ CSP package landed (G2 CLOSED GREEN per `../README.md`) → drawings + spec in hand
2. ■ Bluebeam takeoff against A2.1 / P1.1 / M1.1 / E1.2 → fills `../takeoff-template.json` with real quantities

3. ■ H2I Sub-06 retrieval (Zscaler-blocked; user to fetch manually or Joelle re-share) → tightens casework allowance
4. ■ Sub quotes from 2-3 trades (demo, casework, MEP combined) → fix sub-line unit costs
5. ■ SSC/Compass MVA insurance + Net-75 payment terms confirmed against carrier → fix bond + insurance + working-capital load

Items 2 and 4 are the main remaining estimator work; items 3 and 5 are 30-minute calls. The earliest a defensible final price exists is the morning of Mon 2026-06-01 per `../timeline.md`.

11 — Submission checklist

Submission deadline: 2026-06-10, 2:00 PM CT — hard. TAMU clock is the wall clock at SSC Service Solutions desk. **Hand-delivery target:** 2026-06-09 (Tue) to allow margin for delivery confirmation. **STATUS** — anticipated submission shape; verify against the actual CSP package on G2 close [PENDING e-BUILDER ACCESS].

A. Submission location + contact

Mode	Location
Physical / hand-delivery	SSC Service Solutions, Facilities Services EDCS, 600 Agronomy Road, Suite 218, College Station, TX 77843
Mailing address	1371 TAMU, College Station, TX 77843
Receiving contact (verify before delivery)	Joelle Shidemantle, SSC PM, (979) 286-3497
Backup contact	Patty Winkler, TAMU HUB Operations, (979) 845-4556

Recommended: hand-deliver. Confirm with Joelle the receiving-hours window the morning of delivery; do not assume late-day staffing.

B. Public opening

Field	Value
Date / time	2026-06-10, 2:30 PM CT
In-person location	SSC Facilities Services, Conf Rm 204
Virtual link	Teams link in the Notice: https://teams.microsoft.com/meet/255338032450076?p=64H
Representative	[USER TO FILL – name + role; in-person preferred, virtual acceptable]

C. Submission package contents (anticipated)

The exact submission packaging shape is published in the CSP package "Instructions to Proposers" section [PENDING e-BUILDER ACCESS]. Anticipated TAMU System CSP shape (verify against actual):

C-1. The sealed proposal envelope

Outside labeling (printed; verify exact format against CSP):

SEALED CSP PROPOSAL Project: Harrington Education Center Lab 303 Renovation Project
#: 2025-06813 Due: 2026-06-10, 2:00 PM CT Proposer: [USER TO FILL – firm legal name]
DO NOT OPEN BEFORE 2:30 PM CT, 2026-06-10

Number of copies (typical TAMU System pattern; verify): 1 original + 2–3 copies + 1 USB digital copy.
The original carries wet-ink signatures throughout.

C-2. Contents (in tabbed order; verify against CSP)

Tab	Document	Original signatures?	Notes
1	TAMU CSP Proposal Form (signed)	Yes — wet ink, blue ink	Per 08-csp-proposal-form-fill-guide.m
2	Cover letter / Executive Summary	Yes	Per 01-executive-summary.md
3	Technical Approach	—	Per 02-technical-approach.md
4	Project Team + Key Personnel + resumes (Exhibits T-1 .. T-4)	—	Per 03-project-team.md
5	Past Performance + References	—	Per 04-past-performance.md
6	Schedule Narrative + Gantt Exhibit (G-1)	—	Per 05-schedule-narrative.md
7	Quality Control Plan	—	Per 06-quality-control-plan.md

8	Safety Plan + EMR Letter + OSHA history	—	Per 07-safety-plan.md and 04-past-performance.md § F
9	HSP (HUB Subcontracting Plan)	Yes — wet ink	Per 09-hsp-form-fill-guide.md; bound separately if CSP requires
10	Pricing Proposal (lump sum + alternates + unit prices)	Yes	Per 10-price-proposal.md
11	Bid Bond (original)	Yes — wet ink + bonding-agent corporate seal	Per 12-bid-bond-letter-template.md and bonding agent
12	Performance + Payment Bond commitment letters	Yes	Bonding-agent letterhead
13	Insurance ACORDs (CGL, Auto, WC, Umbrella)	Per ACORD	Within 30 days of issue; TAMU System listed as AI w/ waiver of subrogation
14	W-9	Yes	Current calendar year
15	Texas Form CIQ (Conflict of Interest Disclosure)	Yes	Per Tex. Local Gov't Code Ch. 176
16	Texas Form 1295 — Certificate of Interested Parties (if applicable)	Filed with TEC	Certified copy + acknowledgement; or attestation of non-applicability
17	Addenda acknowledgments	Yes	One per addendum, signed

18	TAMU System Disclosure of Lobbying Activities (if required at proposal stage)	Yes	[PENDING e-BUILDER ACCESS: confirm]
19	Subcontractor list (if required at proposal)	—	[PENDING e-BUILDER ACCESS: TAMU CSPs vary]
20	Assumptions + Clarifications	—	Per 02-technical-approach.md § F
21	USB / digital copy	—	Searchable PDF; mirrors hard copy

C-3. Copies discipline

If CSP requires N copies:

- Mark each copy clearly: "ORIGINAL", "COPY 1", "COPY 2", etc.
- The ORIGINAL carries wet-ink signatures throughout
- Copies may carry signature copies / "/s/" notation if CSP allows; verify
- All copies have identical content; verify page-for-page

D. Pre-sealing QC checklist (2-person walk through, day before delivery)

- ☐ CSP Proposal Form: signed, dated, all fields completed, math verified twice
- ☐ Lump sum + alternates + unit prices: math reconciles across all forms (Proposal Form, Pricing Form, Executive Summary, Bid Bond)
- ☐ Legal entity name matches exactly across: Proposal Form, W-9, CIQ, 1295, Bid Bond, all bonds
- ☐ All addenda acknowledged (verify against the e-Builder portal morning-of)
- ☐ HSP signed; HSP math reconciles; per-trade GFE binder included
- ☐ Bid bond original attached (not photocopy); bonding-agent seal present
- ☐ Performance + Payment bond commitment letters signed by bonding agent
- ☐ Insurance ACORDs within 30 days of issue; TAMU System listed as AI with waiver of subrogation
- ☐ W-9 current calendar year

- ☐ CIQ + 1295 included (or non-applicability attested)
 - ☐ All exhibits included (T-1..T-4 resumes, G-1 Gantt, past-performance references, safety EMR letter)
 - ☐ Sealed envelope properly labeled
 - ☐ N copies + USB included as required
 - ☐ Internal sign-off by a second-set-of-eyes reviewer
-

E. Day-of-delivery (Tue 2026-06-09 — target)

- ☐ Confirm with Joelle that the receiving desk is staffed for delivery (call ~9 AM)
 - ☐ Print delivery cover letter (1 page; restates project name, project #, proposer name, package contents)
 - ☐ Hand-deliver to SSC Service Solutions desk
 - ☐ Obtain dated, signed receipt
 - ☐ Photograph the sealed envelope being handed over (timestamp + GPS)
 - ☐ Email confirmation to Joelle: "Proposal delivered today at [time]; receipt attached."
-

F. Day-of-opening (Wed 2026-06-10)

- ☐ Representative on site at SSC Facilities Services Conf Rm 204 by 2:15 PM CT (15 min early)
 - ☐ OR representative on the Teams link by 2:25 PM CT
 - ☐ Capture all proposer names + prices read aloud at the public opening
 - ☐ Send a brief summary internally same day
-

G. If the actual CSP package overrides any item above

The CSP package is authoritative. Re-author this checklist section-by-section on G2 close. In particular, watch for:

- Different number of copies (some TAMU CSPs require 1 original + 5 copies)
- Different tab order or section requirements (some require a specific cover-page format)
- Different sealed-envelope labeling rules
- Different signature requirements (wet ink vs digital)
- Different submission window rules (some allow electronic submission via the e-Builder portal as a primary or backup; verify)

- Different bond form requirements (TAMU System has specific forms that override AIA stand-ins)

H. Late-submission rules

TAMU System CSP rules: a proposal received even 1 minute after 2:00 PM CT on 2026-06-10 is non-responsive and will not be opened. There is no late-arriver exception. Plan delivery for Tue 2026-06-09 to avoid any same-day delivery risk.

12 — Bid bond request letter template (to bonding agent)

Send this to the bonding agent on Monday 2026-05-24 (in parallel with the eligibility email to Joelle). The agent needs the projected final bid amount by 2026-06-04 to issue the bond by 2026-06-05.

The TAMU System bid bond must be issued on the TAMU System bond form (typically appended to the CSP package [PENDING e-BUILDER ACCESS]). Until the form is in hand, the bonding agent can issue a draft on AIA A310 as a placeholder for internal review only — the final issued bond on submission must be on the TAMU System form.

Letter template

[FIRM LETTERHEAD] [Date – target Mon 2026-05-24] [Bonding Agent Name] [Title]
[Bonding Agency Name] [Address] [Email | Phone] RE: Request for Bid Bond +
Performance/Payment Bond Commitment Solicitation 2025-06813 – Harrington Education
Center Lab 303 Renovation Owner: The Texas A&M University System (Part 02),
administered by SSC Services for Education Bid due: 2026-06-10, 2:00 PM CT Project
location: Bldg 0435, College Station, TX 77843 Dear [bonding agent first name], RK
Residential Homes and Commercial Constructions, LLC dba Blue Print Constructs is
preparing a Competitive Sealed Proposal for the Harrington Education Center Lab 303
Renovation at Texas A&M University, College Station campus. Proposals are due to SSC
Services for Education on Wed 2026-06-10 at 2:00 PM CT. We are reserving bonding
capacity against a projected total proposal value in the range of \$170,000 to
\$250,000 (working envelope; final number to be provided on or before Thu
2026-06-04). The scope is a single-room educational laboratory renovation; project
duration is estimated at 70 calendar days substantial completion + 30 days closeout.
Project description and timeline detail are available on request. We are requesting
the following from your office, on or before the dates below: 1. BID BOND - Amount:
5% of the total final proposal value (per Tex. Gov't Code Ch. 2253 pattern; the TAMU
System bid bond form to be confirmed against the CSP package – we will forward the
exact TAMU System form as soon as we have downloaded the construction document
package, anticipated Mon-to-Tue 2026-05-24/25) - Payable to: "The Board of Regents
of The Texas A&M University System" - Original issued bond delivered to our office
by Fri 2026-06-05 for hand-delivery with the proposal on Tue 2026-06-09 2.
PERFORMANCE BOND COMMITMENT LETTER - 100% of contract value upon award - On bonding
agency letterhead - Signed by underwriting authority - Delivered with the bid bond
on Fri 2026-06-05 3. PAYMENT BOND COMMITMENT LETTER - 100% of contract value upon
award - On bonding agency letterhead - Signed by underwriting authority - Delivered
with the bid bond on Fri 2026-06-05 4. CAPACITY CONFIRMATION - Please confirm by
reply that our firm's current bonding capacity supports a single-project bond up to
[\$ – typically 1.5x of the working envelope, so ~\$375,000] and that aggregate
capacity reserves are available for this project against our existing bonded
backlog. Notes: - The TAMU System Supplementary General Conditions may publish
specific bond form requirements that override the AIA A310 / A312 standard forms. We

will forward the actual TAMU System forms as soon as we have the CSP package. - We anticipate giving you a final bid amount on Thu 2026-06-04 EOD. - If our final number lands outside the \$170-250K envelope above, we will notify you immediately. Please confirm receipt and timing. Available on the phone any time today or tomorrow to discuss. Thank you, [Authorized signatory name] [Title] RK Residential Homes and Commercial Constructions, LLC dba Blue Print Constructs [Phone] [Email]

Notes for the user before sending

- **Substitute the bracketed fields** with the firm-specific values.
- **Confirm the bonding agent's working capacity** before sending the request — if the firm is bonded by **[USER TO FILL]** already, ensure the agent has been pre-warned about the \$250K-ish reserve.
- **If multiple bonding agents are in rotation**, send to the one with the strongest TAMU System work history (TAMU has informal preferences for sureties with TX higher-ed experience).
- **The exact bond-form requirement** is part of the CSP package. Until G2 closes, the bonding agent is working off a placeholder. Re-confirm the bond form on G2 close and forward to the agent same-day.
- **Bid-bond cost** is typically a flat \$100–\$300 issuing fee for a sub-\$500K bond. P&P-bond cost is typically 0.6–1.2% of contract value, collected from the contractor at award (not at bid).
- **If the agent cannot accommodate** the timeline or capacity, escalate immediately — bonding-agent issues are a hard go/no-go gate.

Follow-up timeline

Date	Action	Owner
Mon 2026-05-24	Send this letter	bid-prep lead
Tue 2026-05-25	Confirm receipt + capacity with agent	bid-prep lead
Tue 2026-05-26	Forward TAMU System bond forms (assuming G2 closes Mon 2026-05-25 EOD)	bid-prep lead
Thu 2026-06-04 EOD	Send final bid amount to agent	estimator
Fri 2026-06-05 EOD	Receive original bid bond + P&P commitment letters	bid-prep lead

Tue 2026-06-09	Hand-deliver proposal with original bid bond enclosed	bid-prep lead
----------------	---	---------------